SCALE
20' 0 20' 40'

Remove Existing Curb & Gutter
Install Standard C.O.W. Wheelchair Ramp
Remove and Stockpile Fence
Const. Comb. Curb & Gutter, (6 5/8")
Install W1-7
Remove and Stockpile Fence
Const. 6" A.C. Pavement On 5" Crushed Rock
Δ=86°00'44"
L=15.01'
R=10.00' Fc.
T=9.33'
Install Standard C.O.W. Wheelchair Ramp
-0.97% CL Grade
12" Gas Line Kansas Gas Service
End Ret.
10+32.23
10+50
11+00
11+50
12+00
12+50
13+00
13+50
13+59.56
13+84.46
14+00
14+08.90
14+50
℄ Sta. 9+84.43 Governeour Street
℄ Orme Street
Remove existing Curb and Gutter and Replace with 6" A.C. Pavement On 5" Crushed Rock
Radius= 11.50'
Install New Curb & Gutter and Match Existing
Match
Match
GOVERNEOUR STREET
80' R/W
23' B-B
21' B-B
21' B-B
30' R/W
31' B-B
ORME STREET
Bgn. Ret.
End Ret.
Match Point
WHITTIER STREET
60' R/W
31' B-B
Δ=89°55'00"
L=15.69'
R=10.00' Fc.
T=9.99'
Remove And Replace Exisitng Asphalt Pavement
Install 6" Reinforced Valley Gutter Match FL Both Sides
Install Street Name Sign
Install 6" Reinforced Valley Gutter Remove Existing Curb & Gutter Match FL Both Sides
Δ=91°07'05"
L=15.90'
R=10.00' Fc.
T=10.20'
Install Standard C.O.W. Wheelchair Ramp
Remove and Stockpile Fence
Install Standard C.O.W. Wheelchair Ramp
Δ=90°00'16"
L=15.71'
R=10.00' Fc.
T=10.00'
1
28
Pavement Removal
Curb & Gutter Removal
Construction Limits

© AM Consulting, Inc.

AM CONSULTING Inc.
142 N. Emporia Wichita, KS 67202
316/265-2870 fax: 316/265-2839

PROJECT NUMBER				AM NO. 00102
DESIGN my	DRAWN mp	FILE 00102-3	DATE 8/23/02	SCALE 1"=20'

ORME ST. PAVING PLANS
SEGMENT TWO
WICHITA, KANSAS

SHEET 5 OF 27
REVISED 8/27/03

F:\APPS\DCA\P1\1050AM\projects\00102\00102\plans\00102-3.dwg Tue Jan 25 11:17:12 2005 Steve Schmidt-Poe © Associates of Kansas, Inc.