For North Half See Sheet #12

For East Court See Sheet #14

ADD ALTERNATE #2

SAW CUT, REMOVE EXISTING ASPH. PAVEMENT IN COURT 9 .
CONSTRUCT 3" ASPH. ON 4" REINFORCED CRUSHED ROCK.

ADD ALTERNATE #3

ADD EXTRA 1" ASPH. TO THE ADD ALTERNATE #2. THE COST OF EXTRA EXCAVATION FOR THIS ADDITIONAL 1" ASPH. IS SUBSIDIARY TO THE OTHER BID ITEMS.

ADD ALTERNATE #2
SAW CUT

DATE	BY	REMARKS
5-29-75	T.S.	REMOVE WALLS & SOME WALKS
5-29-75	T.S.	RAISE COURT ELEV.

REVISION

SOUTH HALF

TENNIS COMPLEX

SOUTH RIVERSIDE PARK

NDEX # 185469

BOARD OF PARK COMMISSIONERS
WICHITA, KANSAS

DATE	DRAWN	SCALE	SHEET
1-31-75	A.R.K.	1"=10'	4 of 6