TRIPLE CROWN COURT

STATION	AREAS Square Feet			VOLUMES Cubic Yards			CUMULATIVE VOLUMES Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.08	154.12	0.00	0.00	85.85	0.00	0.00	85.85	0.00	0.00
0+34.58	151.15	0.00	0.00	25.44	0.00	0.00	111.29	0.00	0.00
0+39.98	148.05	0.00	0.00	29.92	0.00	0.00	141.21	0.00	0.00
0+50	168.36	0.00	0.00	58.71	0.00	0.00	199.92	0.00	0.00
1+00.00	186.26	0.00	0.00	328.35	0.00	0.00	528.27	0.00	0.00
1+46	134.25	0.00	0.00	273.03	0.00	0.00	801.30	0.00	0.00
1+46.26	133.94	0.00	0.00	1.29	0.00	0.00	802.59	0.00	0.00
1+73.57	146.25	0.00	0.00	141.70	0.00	0.00	944.30	0.00	0.00
1+96.43	123.71	1.20	0.00	114.28	0.51	0.00	1058.58	0.51	0.00
2+16.21	94.20	0.71	0.00	79.82	0.70	0.00	1138.40	1.21	0.00
2+32.71	43.38	15.72	0.00	42.04	5.02	0.00	1180.44	6.23	0.00
2+51.21	21.86	14.13	0.00	22.35	10.23	0.00	1202.79	16.45	0.00
2+51.71	21.01	13.12	0.00	0.40	0.25	0.00	1203.18	16.71	0.00
2+66.21	0.00	2.83	0.00	5.64	4.28	0.00	1208.83	20.99	0.00
				0.00	0.00	0.00	1208.83	20.99	0.00

BUCKSKIN COURT

STATION	AREAS Square Feet			VOLUMES Cubic Yards			CUMULATIVE VOLUMES Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.11	10.55	30.23	0.00	5.88	16.86	0.00	5.88	16.86	0.00
0+32.54	12.20	28.62	0.00	1.02	2.65	0.00	6.91	19.50	0.00
0+38.02	15.97	25.45	0.00	2.86	5.49	0.00	9.77	24.99	0.00
0+50	19.96	21.16	0.00	7.97	10.34	0.00	17.74	35.33	0.00
0+53.20	20.94	20.11	0.00	2.42	2.45	0.00	20.16	37.78	0.00
0+75	27.69	11.73	0.00	19.63	12.85	0.00	39.79	50.63	0.00
1+00.00	28.50	8.81	0.00	26.01	9.51	0.00	65.81	60.14	0.00
1+25	35.99	6.07	0.00	29.86	6.89	0.00	95.66	67.03	0.00
1+50	33.02	6.62	0.00	31.95	5.88	0.00	127.61	72.90	0.00
1+75	33.58	7.76	0.00	30.83	6.68	0.00	158.44	79.56	0.00
2+00.00	29.86	11.55	0.00	29.37	8.94	0.00	187.82	88.50	0.00
2+25	28.87	13.39	0.00	27.19	11.55	0.00	215.01	100.05	0.00
2+50	38.28	5.59	0.00	31.09	8.79	0.00	246.09	108.84	0.00
2+72.45	17.99	22.26	0.00	23.39	11.58	0.00	269.49	120.41	0.00
2+94.32	6.89	54.46	0.26	10.08	31.07	0.10	279.56	151.49	0.10
3+13.36	4.70	59.26	2.16	4.09	40.10	0.85	283.65	191.59	0.96
3+31.00	10.29	41.41	1.12	4.90	32.88	1.07	288.55	224.47	2.03
3+47.50	0.36	102.08	5.15	3.25	43.84	1.92	291.80	268.31	3.94
3+66	0.00	101.90	2.54	0.12	69.88	2.63	291.92	338.20	6.58
3+66.50	0.03	99.88	1.51	0.00	1.87	0.04	291.92	340.06	6.62
3+81.00	0.00	114.86	0.00	0.01	57.66	0.40	291.93	397.73	7.02
				0.00	0.00	0.00	291.93	397.73	7.02

BUCKSKIN COURT

STATION	AREAS Square Feet			VOLUMES Cubic Yards			CUMULATIVE VOLUMES Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.02	0.03	68.33	1.67	0.02	37.99	0.93	0.02	37.99	0.93
0+34.58	0.00	77.72	2.29	0.00	12.33	0.33	0.02	50.32	1.26
0+35.88	0.00	80.26	2.47	0.00	3.80	0.11	0.02	54.12	1.38
0+50	0.00	98.28	3.43	0.00	46.69	1.54	0.02	100.81	2.92
1+00.00	0.00	157.90	8.91	0.00	237.20	11.43	0.02	338.01	14.35
1+23.48	0.00	198.60	12.97	0.00	155.01	9.51	0.02	493.02	23.86
1+50.21	0.00	387.13	38.75	0.00	289.93	25.60	0.02	782.96	49.46
1+66.71	0.00	450.96	45.10	0.00	256.08	25.62	0.02	1039.04	75.08
1+83.21	0.00	424.13	41.87	0.00	267.39	26.57	0.02	1306.43	101.66
2+01.71	0.00	421.62	37.01	0.00	289.75	27.02	0.02	1596.18	128.68
2+02.21	0.00	399.87	37.97	0.00	7.61	0.69	0.02	1603.79	129.37
2+16.71	0.00	135.70	0.00	0.00	143.81	10.20	0.02	1747.60	139.57
				0.00	0.00	0.00	0.02	1747.60	139.57

EARTHWORK SUMMARY

STREET	CUT CU. YDS.	LOOSE FILL CU. YDS.	COMPACTED FILL CU. YDS.
STAMPEDE	4519	6246	539
TRIPLE CROWN	4289	6794	552
BUCKSKIN	2468	2620	141
TRIPLE CROWN COURT	1209	21	0
BUCKSKIN COURT	292	398	7
BUCKSKIN COURT	0	1748	140
** RESERVE A	15627	4502	0
** RESERVE C	37833	3202	0
** RESERVE D	1787	6149	0
** RESERVE E	34	308	0
BLOCK 1	0	8719	0
BLOCK 2	0	22137	0
BLOCK 3	0	1630	0
BLOCK 6	0	63	0
TOTAL	68058	64537	1379
15% SHRINKAGE		9681	207
STREETS TOTAL	*68058*	*74218 **	*1586*

* LOOSE FILL AND COMPACTED FILL SHALL NOT EXCEED EXCAVATION (7,746 CY WILL BE NEEDED TO COMPLETE SITE GRADING - BY OTHERS)

** FROM COMPANION POND PROJECT

EQUESTRIAN ESTATES - PHASE 1
STREET IMPROVEMENTS
EARTHWORK SUMMARY
CITY OF WICHITA, KANSAS
MICHAEL E. LINDSAY, P.E. - CITY ENGINEER
C.O.W. Project # 472-83424 O.C.A. # 765705

POE & ASSOCIATES OF KANSAS, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FINAL
Designed By: J. Ubert / J. Dickman
Drawn By: J. Dickman
Poe Job No.: 1684A
Date: March 2002

Sheet 89 of 112

G:\APPS\DCA\P\684A\BASE-ST.dwg Mon Mar 25 09:06:17 2002 James Ubert - Poe & Associates of Kansas, Inc.