BENCHMARK:

BM #1 – City of Wichita Bench Mark Disc, NW Corner of Traffic Signal Pole on the NW Corner of Womer and 37th Street North. Elev. = 136.66 (City Datum)

SCALE: 1" = 20'

MERIDIAN

66' R/W

37TH STREET NORTH

WOMER PLAZA ADDITION Lot "A"

PARCEL "B" of CHEROKEE SUNRISE WEST

Proposed Kwik Shop

Womer Street

Sta. 10+00.00 Sec. Corner SE Cor. Sec. 25 T 26S R 1W

Sta 11+94.00 Begin Construction Begin Asph. Shoulder

Sta 12+15.00 Begin Pvmt. Removal

Sta 12+33.00 Begin Taper

Sta 13+33.00 End Taper

Sta 13+51.44 End Asph. Pvmt. Begin Conc. Widening

Sta 13+84.61 End Construction Left Side

Sta 14+19.40 End Construction Right Side

Construct 8" Reinf. Conc. Pvmt. on 6" Reinf. Crushed Rock Base Dowel as Required (See Typical Section)

Const. 8" Reinf. Conc. Entrance Dowel with #4 Dowels, 2' Long, On 24" Centers

Const. 6" A.C. Shoulder

Const. 8" A.C. Shoulder

Construct 6" A.C. Pavement (4" Bit. Base) on 8" Reinf. Crushed Rock Base

Match New Concrete Joints to Existing Concrete Joints.

Abandon Existing Traffic Loop

Const. 6" A.C. Shoulder

Note:

Pavement, Sidewalks, and Etc. To Be Removed Are Indicated By:

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472 76 245 83452	Pav01	F:\Kwikshop-37th_LT Lane\Pav

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
JFB/KK	JCC/TA	JFB	MAY 02	Noted	02 01 E225

LEFT TURN LANE IMPROVEMENT

PAVING PLAN

37TH STREET NORTH BETWEEN MERIDIAN & WOMER

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

SHEET 3 OF 5

F:\Eng\Kwikshop - 37th & Meridian\LT_Lane\pav\pav01.dwg, 05/01/02 11:18:02 AM, DesignJet 750C Plus.pc3