REMOVAL OF EXISTING STRUCTURES			
STATION	**OFFSET**	**ITEM**	
125+75	17.7' LT	SIGN	
126+24	22.5' RT	SIGN	
126+28	17.6' LT	SIGN	
126+28	0.4' RT	18" RCP (45 LF)	Ω
126+49	41.6' LT	SIGN	
126+84	45.9' RT	SIGN	
126+88	37.8' LT	SIGN	
126+97	30.0' RT	SIGN	
128+25	17.1' RT	SIGN	
132+77	26.8' LT	42"X29" HECMP (24 LF)	Ω
133+83	27.8' RT	12" CMP (25 LF)	Ω
134+79	43.0' RT	13 LARGE TREES	Δ
135+55	52.0' RT	SIGN	
135+89	31.3' RT	18" RCP (71 LF)	Ω
136+18	49.3' RT	SIGN	
140+22	30.7' LT	42"X29" HECMP (45 LF)	Ω
144+59	43.1' LT	LARGE TREE	Δ
145+04	15.7' RT	SIGN	
145+07	30.8' RT	5 LARGE TREES	Δ
145+16	16.9' RT	HEADWALL & WINGWALLS	
145+29	16.5' RT	SIGN	
145+29	3.1' RT	2-96"X36" RCB	
145+30	15.0' LT	SIGN	
145+41	14.8' LT	HEADWALL & WINGWALLS	
145+57	14.8' LT	SIGN	
146+92	43.0' RT	LARGE TREE	Δ
147+38	50.0' LT	TREE ROW INCLUDING 8 LARGE TREES	Δ
147+79	33.8' RT	SIGN	
148+26	28.2' RT	42"X29" HECMP (102 LF)	Ω
148+59	54.9' RT	SIGN	
152+57	28.8' RT	24" CMP (30 LF)	Ω
153+24	26.6' RT	33"X24" HECMP (30 LF)	Ω
153+66	32.5' LT	2-36" RCP (72 LF TOTAL)	Ω
155+33	44.2' RT	REDGUARD SIGNS (AS NEEDED FOR CONSTRUCTION)	
155+34	32.0' LT	2-36" RCP (100 LF TOTAL)	Ω
155+63	27.4' RT	24" CMP (40 LF)	Ω
157+04	32.1' LT	2-36" RCP (100 LF TOTAL)	Ω
158+01	24.6' RT	18" CMP (30 LF)	Ω
159+75	25.1' RT	18" CMP (40 LF)	Ω
160+16	54.5' LT	3-DECORATIVE ROCKS	
160+19	40.6' LT	GATE & POSTS (RETURN TO OWNER)	
160+36	31.1' LT	2-36" RCP (84 LF TOTAL)	Ω
162+28	25.1' RT	15" CMP (46 LF)	Ω
162+65	34.4' LT	42"X29" HECMP (35 LF)	Ω
163+94	16.6' RT	MAILBOX	Φ
164+31	24.2' RT	35"X24" HECMP (49 LF)	Ω
166+04	47.4' RT	REDGUARD SIGNS (AS NEEDED FOR CONSTRUCTION)	
166+15	30.1' RT	18" CMP (72 LF)	Ω
167+13	16.7' RT	MAILBOX	Φ
167+34	29.1' RT	18" CMP (22 LF)	Ω
168+20	32.1' LT	2-24" CMP (122 LF TOTAL)	Ω
168+62	63.8' LT	1-SMALL TREE	Δ
168+64	16.7' RT	MAILBOX	Φ
168+81	30.6' RT	24" CMP (20 LF)	Ω
169+21	29.7' RT	24" CMP (24 LF)	Ω
169+32	58.0' LT	1-SMALL TREE	Δ
169+74	29.6' RT	18" CMP (21 LF)	Ω
171+12	17.9' RT	MAILBOX	Φ
171+23	27.3' RT	18" RCP (21 LF)	Ω
171+93	27.3' RT	18" CMP (21 LF)	Ω
172+41	14.7' RT	MAILBOX	Φ
172+64	29.7' RT	24" CMP (32 LF)	Ω
173+51	65.6' LT	1 SMALL TREE	Δ
173+79	32.3' LT	2-24" CMP (64 LF TOTAL)	Ω
173+80	27.9' RT	18" RCP (21 LF)	Ω
174+01	61.2' LT	1 SMALL TREE	Δ
174+08	68.1' LT	15 BUSHES	
174+25	72.7' LT	6 BUMPER BLOCKS	
174+37	26.6' RT	18" RCP (25 LF)	Ω
174+44	68.0' LT	FLAG POLE (RESET AFTER CONST.)	
174+80	63.9' LT	1 SMALL TREE	Δ
174+85	70.7' LT	1 SMALL TREE	Δ
174+90	32.9' RT	LARGE TREE	Δ
175+56	21.6' RT	SIGN	
175+73	5.0' RT	24" RCP (70 LF)	Ω
224+56	27.1' RT	ROSE BUSH	
228+70	16.6' RT	SIGN	
168+30	40.7' RT	LARGE TREE	Δ
168+64	42.9' RT	LARGE TREE	Δ
148+91	47.5' RT	FENCE (40 LF)	
154+22	73.4' LT	11 BUMPER BLOCKS	
133+66	16.9' RT	MAILBOX	Φ

Φ TO BE PAID FOR BY THE BID ITEM, "MAILBOX, REMOVED AND RESET".

Δ TO BE PAID FOR BY THE BID ITEMS, "TREE REMOVED, SMALL" AND "TREE REMOVED, LARGE".

Ω TO BE PAID FOR BY LINEAR FOOT UNDER THE BID ITEM, "PIPE REMOVED" .

REMOVAL QUANTITIES									
	AC PAVEMENT REMOVED	CONCRETE PAVEMENT REMOVED*	GRAVEL REMOVAL #	CONCRETE APRON & RIP RAP REMOVED #	PIPE REMOVED Ø	MAILBOX, REMOVED & RESET	TREE REMOVED (SMALL)	TREE REMOVED (LARGE)	ABND. GAS LINE REMOVAL
GRAND TOTAL	18,640 SY	2,214 SY	987 SY	184 SY	1,503 LF	6 EA	6 EA	31 EA	275 LF

\# FOR INFORMATION ONLY - SUBSIDIARY TO "SITE CLEARING" BID ITEM

* INCLUDES CURB & GUTTER REMOVAL AREAS

Ø 2-8'X3' RCBC CROSSING TO BE PAID FOR UNDER THE BID ITEM "REMOVAL OF EXISTING STRUCTURES". PIPE REMOVAL QUANTITY DOES NOT INCLUDE RCBC REMOVAL.

TRANSPORTING SALVAGEABLE MATERIAL		
STATION	**OFFSET**	**ITEM**
125+75	17.7' LT	SIGN
126+24	22.5' RT	SIGN
126+28	17.6' LT	SIGN
126+49	41.6' LT	SIGN
126+84	45.9' RT	SIGN
126+88	37.8' LT	SIGN
126+97	30.0' RT	SIGN
128+25	17.1' RT	SIGN
135+55	52.0' RT	SIGN
136+18	49.3' RT	SIGN
145+04	15.7' RT	SIGN
145+29	16.5' RT	SIGN
145+30	15.0' LT	SIGN
145+57	14.8' LT	SIGN
147+79	33.8' RT	SIGN
148+59	54.9' RT	SIGN
175+56	21.6' RT	SIGN
228+70	16.6' RT	SIGN

TRANSPORT SALVAGEABLE MATERIAL TO THE CITY OF WICHITA'S CENTRAL MAINTENANCE FACILITY AT 1801 S. MCLEAN BLVD.

PEC
PROFESSIONAL ENGINEERING CONSULTANTS
303 SOUTH TOPEKA
WICHITA, KS 67202
316-262-2691 www.pec1.com

CITY OF WICHITA

LUKE PETER LENSER 27413 10/11/2024 KANSAS PROFESSIONAL ENGINEER

WEST STREET IMPROVEMENTS FROM MACARTHUR ROAD TO 47TH ST. SOUTH

CITY OF WICHITA

Issue:		

JOB NO.	210254-001
DATE	OCTOBER 2024
PM	TPA
DESIGNED BY	LGP
DRAWN BY	CP
CHECKED BY	KMS

REMOVAL OF EXISTING STRUCTURES RECAP

CD501
13 OF 206

SAVED 10/7/2024 11:40:11 AM BY LUKE.PETER
PLOTTED 10/10/2024 1:30:57 PM BY LUKE PETER
U:\WICHITA-CIVIL\2021\210254\001\PEC\DRAWINGS\210254-001 DEMO.DWG