



EROSION CONTROL ITEMS TO BE COMPLETED WITH SANITARY SEWER LINE CONSTRUCTION		
STABILIZED CONSTR ENTRANCE	1	EA

- ① LINEAR SEDIMENT BARRIER
- ② INLET SEDIMENT BARRIER
- ③ OUTLET PROTECTION

NOTES:

BMP'S INDICATED ON THIS PLAN ARE A GUIDE. CONTRACTOR SHALL ADD PERIMETER PROTECTION AS NECESSARY TO PREVENT OFF-SITE SILT TRANSPORT. CONTRACTOR IS ALSO RESPONSIBLE FOR MAINTAINING EXISTING BMP'S ONSITE.

Fawn Grove Phase 4 Water Erosion Control Plan WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		
	924 North Main (316) 264-8008 Wichita, Kansas 67203 (316) 264-4621 fax www.rbkansas.com E-mail: info@rbkansas.com		
DRAWING FILE {NPDES}	PROJECT NUMBER XXX-XXXXX	DATE June 18, 2007	DESIGN EJG DRAWN RLS REVIEW UTILITY DATE June 18, 2007
			SHEET 5 OF 13