

262 - 3649

VICKI

ADDENDUM NO. 3 TO  
PLANS AND SPECIFICATIONS  
FOR AN ADDITION TO  
THE INDEPENDENT SCHOOL  
8301 E. DOUGLAS  
MAY 16, 1991

Lawrence Wells

ITEM NO. 7. Plans, Sheet 1. Clarify Live Loads by adding: 2nd floor class room - 40#, Storage 2nd floor - 100#. Note: Allowance made so that 100# corridor loading is available if classroom partitions were ever added.

ITEM # 8. Plans, Sheets 3, 4 & 6. Add wall types, including stair enclosures and furnace rooms, to plans as noted on attached Exhibit "B".

ITEM #9. Plans, Sheet 2. Relocate entrance ramp as shown and detailed on attached Exhibit "C".

ITEM NO. 10. Plans, Sheet 9. Add dimensions and details to handrails as shown on attached Exhibit "D".

ITEM NO. 11. Plans. Sheet 9, Windows. Change vertical height of operable sash in Window A from 1' - 6" to 2' - 0".

ITEM NO. 12. Plans, Sheet 9, Door Schedule. Change and add to callouts for Doors 19, 26 & 27 as shown below.

MARK	FROM TO	DOOR SIZE	DOOR		FRAME		RATING AND LABEL	HARD WARE	DETAILS	REMARKS
			MATL	TYPE	MATL	JAMB WIDTH				
1	108/EXT	30 x 68 x 13/4	ALUM	III	ALUM	4"	---	*		* SEE HARDWARE SCHEDULE
18	111/EXIST	30 x 68 x 13/4	HM	IV		5 7/8	20 MIN			INSULATED
19	115/114	30 x 68 x 13/4	HM	I		5 7/8	1 HR.			1 HR. LABELED ASSEMBLY
19A	115/113	30 x 68 x 13/4	WD	I		5 7/8	---			
20	112/113	30 x 68 x 13/4		I		5 7/8	---			
21	110/115	30 x 68 x 13/4		II		5 7/8	20 MIN			
22	110/116	30 x 68 x 13/4		A		5 7/8				
23	110/118	30 x 68 x 13/4				5 7/8				
24	110/120	30 x 68 x 13/4		II		5 7/8	20 MIN			
25	122/123	30 x 68 x 13/4	WD	I		5 7/8	---			
26	120/121	30 x 68 x 13/4	HM	I		5 7/8	1 HR.			1 HR. LABELED ASSEMBLY
26A	120/123A	30 x 68 x 13/4	WD			5 7/8	---			
27	118/119	30 x 68 x 13/4	HM			5 7/8	1 HR.			1 HR. LABELED ASSEMBLY
27A	118/117A	30 x 68 x 13/4	WD	I		5 7/8	---			

ITEM NO. 13. Plans, Sheet No. 2. Change drainage pattern and add underground drainage system as shown on attached Exhibit "C". Contractor to coordinate with Flood Control as system is being installed.

ITEM NO. 14. Plans, Sheet M-1. Add approved fire dampers to all ducts penetrating walls surrounding furnace rooms 114, 119 & 121.

