



- 1 - 8"x6" HYDRANT VALVE ANCHOR TEE
- 1 - 6" MJ GATE VALVE
- 1 - 6" VALVE BOX
- 2' - 6" CIGL SJ PIPE
- 1 - FIRE HYDRANT
- 1 - 8" CI MJ PLUG

- 1 - 8" CIMJ CAP TAPPED 2"
- 1 - 2" BLOWOFF ASSEMBLY

- 1 - 8"x 8" CIMJ TEE
- 2' - 8" CIGL SJ PIPE
- 1 - 8" MJ GATE VALVE
- 1 - 6" VALVE BOX

- 1 - 8"x 8" TAPPING SLEEVE
- 1 - 8" TAPPING VALVE
- 1 - 6" VALVE BOX

**NOTE**  
ALL UTILITIES ARE CLEAR

- 1 - 8" CIMJ 45° BEND
- 41' - 8" AC PIPE

- 1 - 8" CIMJ 45° BEND
- 2' - 8" CIGL SJ PIPE
- 1 - 8"x 6" HYDRANT VALVE ANCHOR TEE
- 1 - 6" MJ GATE VALVE
- 1 - 6" VALVE BOX
- 2' - 6" CIGL SJ PIPE
- 1 - FIRE HYDRANT

**SPECIAL NOTE**  
DUE TO THE EXCESSIVE FILL ON LONGFELLOW CIR, IT IS IMPERATIVE THAT THE CONTRACTOR COORDINATE ALL WATER LINE CONSTRUCTION WITH THE PAVING CONTRACTOR.

All Water Mains and appurtenances shall be installed in accordance with Standard Specification for Water Main Installations, Number 14533

CITY OF WICHITA WATER DEPARTMENT ENGINEERING DIVISION			
Drawn D.J.S.	Scale 1"=100'	Revisions	Date
Checked			
Approved			
Date 2-28-80			
Title FUNSTON WEST OF LONGFELLOW & LONGFELLOW CIR. SOUTH OF FUNSTON B.D. 645-79			
No. 448-80-925-80518-000-000-001			