

We, Baughman Company, P.A., Surveyors in aforesaid county and state do hereby certify that we did on this 20th day of February, 1992, survey and determine the existing ground elevations on a portion of the following Lots in Lost Creek Estates, Wichita, Kansas, with building pad descriptions as follows:

**LOT 20**

Beginning at the S.W. Corner of Lot 20; thence N 48°32'28" W, along the westerly line of said Lot 20, 66.74 feet; thence N 49°46'29" E, 110.57 feet to a point on the common lot line between Lots 20 and 21; thence S 05°25'54" E, along said common lot line 36.48 feet to a deflection point in said common lot line; thence S 20°18'14" E, along said common lot line, 48.44 feet to the front corner common to said Lots 20 and 21; thence southwesterly along the front line of said Lot 20, 64.72 feet to the point of beginning.

**LOT 21**

Beginning at the front corner common to Lots 20 and 21; thence N 20°18'14" W, along the common lot line between said Lots 20 and 21, 48.44 feet to a deflection point in said common lot line; thence N 05°25'54" W, along said common lot line, 36.48 feet; thence N 66°32'06" E, 39.28 feet; thence N 87°29'34" E, 55.76 feet; thence S 70°18'32" E, 34.40 feet to a point on the common lot line between Lots 21 and 22; thence S 14°19'41" W, along said common lot line, 45.06 feet to a deflection point in said common lot line; thence S 05°25'54" E, along said common lot line, 30 feet to the front corner common to said Lots 21 and 22; thence southwesterly along the front line of said Lot 21, 97 feet to the point of beginning.

**LOT 22**

Beginning at the front corner common to Lots 21 and 22; thence N 05°25'54" W, along the common lot line between said Lots 21 and 22, 30 feet to a deflection point in said common lot line; thence N 14°14'41" E, along said common lot line, 45.06 feet; thence S 74°59'06" E, 21.92 feet; thence N 35°07'44" E, 36.49 feet; thence N 83°00'54" E, 37.57 feet to a point on the common lot line between Lots 22 and 23; thence S 05°25'54" E, 93.52 feet to the front corner common to said Lots 22 and 23; thence southwesterly along the front line of said Lot 22, 97 feet to the point of beginning.

**LOT 23**

Beginning at the front corner common to Lots 22 and 23; thence N 05°25'54" W, along the common lot line between said Lots 22 and 23, 93.52 feet; thence S 88°42'09" E, 66.71 feet; thence S 66°34'20" E, 33.79 feet to a point on the common lot line between Lots 23 and 24; thence S 09°40'22" W, 78.25 feet to the front corner common to said Lots 23 and 24; thence northwesterly and westerly along the front line of said Lot 23, 97 feet to the point of beginning.

**LOT 24**

Beginning at the front corner common to Lots 23 and 24; thence N 09°40'22" E, along the common lot line between said Lots 23 and 24, 78.25 feet; thence S 66°34'20" E, 50.22 feet; thence S 28°46'17" E, 72.01 feet; thence S 08°29'06" E, 20.55 feet; thence S 81°48'51" W, 24.36 feet to a point on the front line of said Lot 24; thence northwesterly along the front line of said Lot 24, 79.24 feet to the point of beginning.

**LOT 31**


Commencing at the S.W. Corner of Lot 31; thence N 18°31'51" E, along the westerly line of said Lot 31, 19.70 feet to a deflection point in said westerly line; thence N 05°25'54" W, 82 feet to a common corner of Lots 31 and 32; thence N 84°34'06" E, along the common lot line between said Lots 31 and 32, 41.16 feet for a place of beginning; thence continuing N 84°34'06" E, along said common lot line, 41.56 feet; thence S 10°22'19" E, 17.26 feet; thence S 27°53'57" E, 18.20 feet; thence S 70°28'06" E, 43.57 feet; thence S 17°29'41" W, 41.40 feet; thence S 37°06" W, 13.55 feet; thence N 73°20'37" W, 64.16 feet; thence N 60°43'57" W, 13.59 feet; thence N 10°21'52" W, 54.42 feet to the point of beginning.

**LOT 32**

Commencing at the S.W. Corner of said Lot 32; thence N 84°34'06" E, along the common lot line between Lots 31 and 32, 41.16 feet for a place of beginning; thence N 10°57' W, 42.23 feet; thence N 08°27' W, 71.15 feet; thence N 17°52'43" W, 26.82 feet to a point on the north line of said Lot 32; thence N 84°34'06" E along the north line of said Lot 32, 65.35 feet; thence S 16°50'07" W, 49.42 feet; thence S 10°05'50" E, 64.02 feet; thence S 11°47'39" E, 29.92 feet to a point on the common lot line between said Lots 31 and 32; thence S 84°34'06" W, 41.56 feet to the point of beginning.

The accompanying sketch is a true and correct exhibit of said survey.

*William E. Dur*  
 Surveyor



1"=30'  
 =1' CONTOURS  
 ELEVATIONS=MEAN SEA LEVEL

