



Drainage Improvements For Letter of Credit

QUANTITIES		
140 S.T. CONCRETE 6" THICK	@ 25.00	3500.00
4- 1-A CURB INLETS	@ 1750.00	7000.00
30'- 8" PVC DISCHARGE	@ 10.00	300.00
1- INLET STRUCTURE	@ 500.00	500.00
45'- 15" RCP	@ 20.00	1900.00
1- Aurora propeller pump (3000 gal/min. capacity)	@ 7500.00	7500.00
185 L.F. 24" RCP	@ 30.00	5550.00
155 L.F. 22" x 38" RCP	@ 35.00	5425.00
		<u>31,675.00</u>
		8031.25
		40,156.25
		Use \$40,000

LAMPLIGHTER MOBILE HOME PARK
WICHITA, SEDGWICK COUNTY, KANSAS

REISS & GOODNESS ENGINEERS
 2100 WEST 21ST STREET
 WICHITA, KANSAS 67204
 (316) 832-0215

SCALE: 1" = 60'