


M K E C E N G I N E E R I N G C O N S U L T A N T S , I N C



REVISED DRAINAGE REPORT

FOR

THE WATERFRONT SECOND ADDITION

SEPTEMBER 2003

Drainage Report for The Waterfront Second Addition Wichita, Kansas

Location

The site is located in Wichita, Sedgwick County, Kansas, on the northeast corner of Webb Road and 13th Street North. It lies in the Southwest Quarter, Section 9, Township 27 South, Range 2 East. The total site area is approximately 11.8 acres. The site is bounded by the Waterfront Addition to the west, 13th Street to the south, and undeveloped meadow area to the north and east. The site is shown on the Andover, Kansas Quadrangle located in Appendix A.

Soils

According to the NRCS (SCS) Sedgwick County Soil Survey (Appendix B), the site is in the Irwin Series (Ia: Irwin silty clay loam, with 1 to 3 percent slopes). The Hydrological Soil Group (HSG) for the Irwin series soils is D. The drainage calculations were based on soil group D.

Pre-developed Conditions

Current Development

The site is currently undeveloped pasture land. The site is being used as a recreational area.

Current Landform and Slope

Slopes across the site range from 1-2%. A ridge runs north to south, east of the site. The area west of the ridge drains west to the Waterfront Addition and into the lake. Elevations on the site range from 1381 ft. on the east edge to 1372 ft. on the west edge.

Current Drainage Conditions

The entire site is in Zone C. The nearest Zone A is approximately 500 feet west of the site surrounding the existing lake in The Waterfront Addition (FIRM Panel 150, Sedgwick County, June 3, 1986) (shown in Appendix C).

Upstream of Site

Approximately 555 acres drain into the existing lake in the Waterfront Addition. Approximately 225 acres drains from the north to the Eastminster Addition, directly north of the site. This runoff passes through an existing detention facility east of the Eastminster Presbyterian Church, north of the railroad. An additional 105 acres drains to the existing 11'x9' reinforced concrete box (RCB) which passes under the railroad tracks. The runoff then passes through an existing channel, under a 3-12'x3' RCB and into the lake on the

site. An additional 196 acres drains to the existing lake. This includes approximately 48 acres from the west side of Webb Road. This area drains through an existing RCB under Webb Road and into the lake. Most of the developable area upstream of the site is already developed, with the exception of the area just west of Webb Road, which is currently undeveloped pasture land.

Current Runoff Characteristics

The pre-developed watershed is divided into nine different sub-watersheds: 1 is the area North of Eastminster, 2 is the tributary from the west, 3 is the area draining to the railroad, 4 is the area draining to the silt pond, 5 is the area north and east of the site, 6 is the area directly east of the site, 7 includes part of the site, 8 is the area to the west of Webb Road, and 9 is the area draining to the lake south of Webb Road including a portion of the site. These areas have been shown on the Andover Quadrangle map in Appendix A. The TR-20 software model was used to calculate peak flows using the SCS 24-hour storm (results are shown in Appendix D). The curve numbers used for the sub-watersheds were calculated based on percentage of development within each sub-watershed. They range from 82 to 90.5. Peak discharge from the sub-watersheds and watershed for the 2, 5, 10, and 100-year return periods under existing conditions are shown in Table 1. Sub-watersheds 5, 6, 7, and 8 were modeled together for the existing conditions model. Both the Waterfront and Waterfront Second Additions were considered undeveloped for existing conditions.

Table 1. Pre-developed runoff.

| Sub-Watershed | 2-Year (cfs) | 5-Year (cfs) | 10-Year (cfs) | 100-Year (cfs) |
|--------------------|-----------------|-----------------|------------------|-------------------|
| 1 | 154 | 216 | 257 | 408 |
| 2 | 118 | 167 | 200 | 318 |
| 3 | 161 | 221 | 262 | 417 |
| 4 | 33 | 49 | 59 | 98 |
| (5-8 Combined) | 183 | 265 | 320 | 522 |
| 9 | 237 | 359 | 439 | 745 |
| Total to Lake | 740 | 1030 | 1185 | 1736 |
| Total Exiting Lake | 294 | 490 | 607 | 1091 |

Due to the complexity of modeling the lakes north and south of 13th Street North as separate reservoirs, the lakes were combined and modeled as one reservoir. The lakes were modeled based on an existing control structure and spillway at the south end of the south lake. The existing weir is a concrete structure with a 12' wide notch at elevation 1368.7', and an additional 70' of width at elevation 1369.7'. Currently, there is a wood plank covering the 12' wide notch. However, this wood plank is not bonded to the concrete with a watertight seal, and water leaks out along the seam between the wood and concrete. The owner of the Waterfront Addition has indicated that the wood plank will be removed from the weir prior to the subject development. The lake was modeled without this weir in place, for both existing and proposed conditions. Rating curves for the weir were developed using the HY-8 computer software program.

Post-Developed Condition

Proposed Development

The site will develop as three commercial lots. The anticipated use is retail.

Proposed Landform and Slope

Proposed slopes are expected to range from 0.5% to 3%. A street will be constructed along the west side of the development in the Waterfront Addition. Drainage from the west portion of the site will be conveyed under the street through RCB's as shown on the Drainage & Utility Plan in Appendix E. Approximately 4.4 acres will drain into a proposed detention pond north of the site. Preliminary lot grading is shown in Appendix F.

Proposed Runoff Characteristics

The TR-20 software model calculated peak flows for the developed watersheds using the SCS 24-hour storm (results are shown in Appendix G). Sub-watersheds 4 and 7 were changed to reflect increased runoff curve numbers and decreased times of concentration due to development of the Waterfront Addition and the Waterfront Second Addition. A curve number of 95.0 was used for the proposed developed areas, with a time of concentration estimated at 20-25 minutes. Runoff under the developed conditions for the 2, 5, 10, and 100-year return periods are shown in Table 2.

Table 2. Post-developed runoff.

| Sub-Watershed | 2-Year (cfs) | 5-Year (cfs) | 10-Year (cfs) | 100-Year (cfs) |
|-------------------------|-----------------|-----------------|------------------|-------------------|
| 1 | 154 | 216 | 257 | 408 |
| 2 | 118 | 167 | 200 | 318 |
| 3 | 161 | 221 | 262 | 417 |
| 4 | 63 | 85 | 100 | 153 |
| 5 | 34 | 53 | 66 | 117 |
| 6 | 55 | 84 | 104 | 180 |
| Total to Prop. Pond | 89 | 137 | 170 | 296 |
| Total out of Prop. Pond | 44 | 70 | 95 | 190 |
| 7 | 142 | 187 | 217 | 325 |
| 8 | 43 | 69 | 86 | 153 |
| 9 | 237 | 359 | 439 | 745 |
| Total to Lake | 769 | 1107 | 1333 | 2109 |
| Total Exiting Lake | 218 | 405 | 532 | 1098 |

The additional runoff due to development of the site will have minimal impact on the watershed as whole. The short time of concentration for the developed area will allow the additional runoff to pass through the lake prior to the peak runoff from upstream. The proposed detention pond in the Waterfront Addition will also help to reduce flows into the existing lake facilities. Discharge from the south lake will increase by 7 cfs (0.6%). Water surface elevations for the lakes will increase by 0.01' under proposed conditions. A HEC-RAS hydraulic model was prepared and indicates a 100-year water surface elevation of 1372.20 for the north lake, and 1371.92 for the south lake.

Proposed on-site storm water sewer systems have been included on the Drainage and Utility plan in Appendix E. Flows from the proposed sub-watersheds were determined using the rational method. Pipe sizes were determined using Manning's equation. Appendix H includes a spreadsheet with the results of these calculations.



Summary

The Waterfront Second Addition is a proposed 11.8-acre development at the northeast corner of Webb Road and 13th Street North in Wichita, Kansas. The site is to be developed as commercial land. Runoff will continue to drain into the existing 14-acre lake in the Waterfront Addition. The Waterfront Addition will include improvements to the lake. Development of this site was taken into account when the Waterfront Addition was designed. An additional 4-acre detention pond is planned in the Waterfront Addition, north of the Waterfront Second Addition. Hydrologic models for existing and proposed conditions with this report have shown that the development of this property will have minimal effects on properties downstream. Discharge from the existing lake

directly downstream of the site will increase by 0.6% as a result of this development and the Waterfront Addition.

Appendix A

Quadrangle



CONTOUR INTERVAL 10 FEET
 NATIONAL GEODETIC VERTICAL DATUM OF 1929



MKEC
 ENGINEERING
 CONSULTANTS
 411 N. WEBB ROAD
 WICHITA, KS. 67206
 316 - 684 - 9600

THE WATERFRONT SECOND ADDITION
 PROJECT NAME

ANDOVER, KANSAS QUADRANGLE
 SHEET TITLE

KLA DESIGN BY. **KLA** DRAWN BY. **GM** CHECKED BY.

SEPTEMBER 2002 DATE. **02014** JOB NO. **1 / 1** SHEET/OF

H:\CIVIL\02014\2ND ADD.DWG.DWG (02014_2004.DWG)

Appendix B



Soil Survey

36



1 Mile
5000 Feet

Scale 1:20000



R 2 E

(Joins sheet 28)

(Joins sheet 25)

THE WATERFRONT
SECOND ADDITION

LAKESHORE
GARDENS
CEMETERY



MKEC
ENGINEERING
CONSULTANTS
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

THE WATERFRONT SECOND ADDITION


PROJECT NAME
**SOIL SURVEY OF
SEDGWICK COUNTY, KANSAS**
SHEET - TITLE

| | | |
|-------------------------------|-------------------------|--------------------------|
| KLA DESIGN BY: | KLA DRAWN BY: | GM CHECKED BY: |
| SEPTEMBER 2002 DATE | 02014 JOB NO. | 1 / 1 SHEET/OF |

H:\CIVIL\02014\2ND_ADD\DWG\02014_255M.DWG

Appendix C

FIRM



NATIONAL FLOOD INSURANCE PROGRAM


FIRM
FLOOD INSURANCE RATE MAP

SEDGWICK COUNTY,
KANSAS
(UNINCORPORATED AREAS)



PANEL 150 OF 300

COMMUNITY-PANEL NUMBER
200321 0150 A

EFFECTIVE DATE:
JUNE 3, 1986



Federal Emergency Management Agency

MKEC
ENGINEERING CONSULTANTS
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

THE WATERFRONT SECOND ADDITION
PROJECT NAME
FIRM PANEL 150 OF 300
SEDGWICK COUNTY, KANSAS
SHEET-TITLE

| | | |
|-------------------------------|-------------------------|---------------------------|
| KLA DESIGN BY. | KLA DRAWN BY. | GJA CHECKED BY. |
| SEPTEMBER 2002 DATE | 02014 JOB NO. | 1 / 1 SHEET/OF |

H:\CIVIL\02014\2ND_ADD\DWG\DRWG\02014_27M.DWG

Appendix D

Existing TR-20 Output

1

*****80-80 LIST OF INPUT DATA FOR TR-20 HYDROLOGY*****

| JOB | TR-20 | FULLPRINT | SUMMARY | NOPLOTS |
|-------|----------|---|---------------|--------------------|
| TITLE | 001 | EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK | | |
| TITLE | BEECH2- | W/O 2X12 16 AUG 2002 | 2,5,10,100-YR | 24-HR STORM ZONE 5 |
| 4 | DIMHYD | 0.02 | | 484 |
| 8 | .000 | .030 | .100 | .190 .310 |
| 8 | .470 | .660 | .820 | .930 .990 |
| 8 | 1.000 | .990 | .930 | .860 .780 |
| 8 | .680 | .560 | .460 | .390 .330 |
| 8 | .280 | .241 | .207 | .174 .147 |
| 8 | .126 | .107 | .091 | .077 .066 |
| 8 | .055 | .047 | .040 | .034 .029 |
| 8 | .025 | .021 | .018 | .015 .013 |
| 8 | .011 | .009 | .008 | .007 .006 |
| 8 | .005 | .004 | .003 | .002 .001 |
| 8 | .000 | .000 | .000 | .000 .000 |
| 9 | ENDTBL | | | |
| 5 | RAINFL 7 | 0.5 | | |
| 8 | .000 | .002 | .005 | .009 .013 |
| 8 | .018 | .023 | .029 | .035 .042 |
| 8 | .050 | .059 | .068 | .078 .089 |
| 8 | .101 | .114 | .128 | .144 .162 |
| 8 | .183 | .208 | .244 | .339 .723 |
| 8 | .773 | .802 | .825 | .844 .861 |
| 8 | .876 | .890 | .903 | .914 .924 |
| 8 | .934 | .943 | .951 | .959 .966 |
| 8 | .972 | .977 | .982 | .986 .990 |
| 8 | .993 | .996 | .998 | 1.000 1.000 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 10 | | |
| 8 | | 1369.4 | 0.0 | 0.0 |
| 8 | | 1370.4 | 6.0 | 0.279 |
| 8 | | 1371.4 | 14.0 | 1.093 |
| 8 | | 1372.4 | 30.0 | 2.269 |
| 8 | | 1373.4 | 60.0 | 3.606 |
| 8 | | 1374.4 | 320.0 | 7.212 |
| 8 | | 1375.4 | 580.0 | 11.361 |
| 8 | | 1376.4 | 760.0 | 16.450 |
| 8 | | 1377.4 | 925.0 | 23.036 |
| 8 | | 1378.4 | 1085.0 | 31.035 |
| 8 | | 1379.4 | 1240.0 | 40.834 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 14 | | |
| 8 | | 1369.0 | 0.0 | 0.0 |
| 8 | | 1370.0 | 38.0 | 0.639 |
| 8 | | 1371.0 | 45.0 | 1.96 |
| 8 | | 1372.0 | 310.0 | 4.11 |

1

*****80-80 LIST OF INPUT DATA (CONTINUED)*****

| | | | | |
|---|--------|--------|--------|-------|
| 8 | | 1373.0 | 460.0 | 8.21 |
| 8 | | 1374.0 | 522.0 | 15.16 |
| 8 | | 1375.0 | 640.0 | 24.79 |
| 8 | | 1376.0 | 1436.0 | 36.20 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 18 | | |

EXECUTIVE CONTROL INCREM MAIN TIME INCREMENT = .10 HOURS

EXECUTIVE CONTROL COMPUT FROM XSECTION 1 TO STRUCTURE 18
 STARTING TIME = .00 RAIN DEPTH = 3.50 RAIN DURATION= 1.00
 ANT. MOIST. COND. = 2 MAIN TIME INCREMENT = .10 HOURS
 ALTERNATE NO.=11 STORM NO.= 1 RAIN TABLE NO.= 7

OPERATION RUNOFF XSECTION 1
 OUTPUT HYDROGRAPH= 1 AREA= .12 SQ MI
 INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= .91 HOURS
 COMPUTED INTERNAL TIME INCREMENT = .0992 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
 12.33 103.6 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.32 WATERSHED INCHES; 182 CFS-HRS; 15.0 ACRE-FEET.

OPERATION REACH XSECTION 2
 INPUT HYDROGRAPH 1 OUTPUT HYDROGRAPH 2
 CHANNEL LENGTH 1500.00 FT
 INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
 MODIFIED ATT-KIN ROUTING COEFFICIENT = .57 PEAK TRAVEL TIME = .20 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
 12.50 99.5 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.32 WATERSHED INCHES; 182 CFS-HRS; 15.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
 OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
 INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
 COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
 12.20 76.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.49 WATERSHED INCHES; 118 CFS-HRS; 9.8 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
 INPUT HYDROGRAPHS 1,2 OUTPUT HYDROGRAPH 3

1

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
 12.35 162.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 300 CFS-HRS; 24.8 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 153.5 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 300 CFS-HRS; 24.8 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.45 117.5 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.29 WATERSHED INCHES; 232 CFS-HRS; 19.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.44 271.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.34 WATERSHED INCHES; 532 CFS-HRS; 44.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.24 161.3 (RUNOFF)

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38. PASS 1 PAGE 4

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.45 WATERSHED INCHES; 260 CFS-HRS; 21.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.35 418.8 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 792 CFS-HRS; 65.4 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.53 386.3 1374.66

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 791 CFS-HRS; 65.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 84. TIME OF CONCENTRATION= .81 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1082 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.28 33.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.96 WATERSHED INCHES; 55 CFS-HRS; 4.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.50 413.5 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.35 WATERSHED INCHES; 846 CFS-HRS; 69.9 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 1 PAGE 5

OPERATION RESVOR STRUCTURE 14
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.00

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.73 375.7 1372.44

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.34 WATERSHED INCHES; 846 CFS-HRS; 69.9 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .31 SQ MI
INPUT RUNOFF CURVE= 86. TIME OF CONCENTRATION= 1.43 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.64 183.2 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.13 WATERSHED INCHES; 422 CFS-HRS; 34.9 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.69 557.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.27 WATERSHED INCHES; 1268 CFS-HRS; 104.8 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.31 236.8 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.78 WATERSHED INCHES; 400 CFS-HRS; 33.1 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 1 PAGE 6

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.51 739.9 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.13 WATERSHED INCHES; 1668 CFS-HRS; 137.9 ACRE-FEET.

OPERATION RESVOR STRUCTURE 18
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1368.70

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
13.49 294.1 1370.20

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.13 WATERSHED INCHES; 1665 CFS-HRS; 137.6 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 1

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 2 PAGE 7

EXECUTIVE CONTROL COMPUT FROM XSECTION 1 TO STRUCTURE 18
STARTING TIME = .00 RAIN DEPTH = 4.55 RAIN DURATION = 1.00
ANT. MOIST. COND. = 2 MAIN TIME INCREMENT = .10 HOURS
ALTERNATE NO. = 12 STORM NO. = 2 RAIN TABLE NO. = 7

OPERATION RUNOFF XSECTION 1
OUTPUT HYDROGRAPH= 1 AREA= .12 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= .91 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0992 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.32 146.0 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.30 WATERSHED INCHES; 259 CFS-HRS; 21.4 ACRE-FEET.

OPERATION REACH XSECTION 2
INPUT HYDROGRAPH 1 OUTPUT HYDROGRAPH 2
CHANNEL LENGTH 1500.00 FT
INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
MODIFIED ATT-KIN ROUTING COEFFICIENT = .61 PEAK TRAVEL TIME = .20 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.49 141.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.30 WATERSHED INCHES; 259 CFS-HRS; 21.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.20 107.0 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.49 WATERSHED INCHES; 166 CFS-HRS; 13.7 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
INPUT HYDROGRAPHS 1,2 OUTPUT HYDROGRAPH 3

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.34 229.1 (NULL)

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 2 PAGE 8

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.37 WATERSHED INCHES; 425 CFS-HRS; 35.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.43 215.6 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.37 WATERSHED INCHES; 425 CFS-HRS; 35.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.44 | 167.0 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.27 WATERSHED INCHES; 331 CFS-HRS; 27.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.43 | 382.6 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.33 WATERSHED INCHES; 756 CFS-HRS; 62.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.24 | 220.9 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.45 WATERSHED INCHES; 365 CFS-HRS; 30.1 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 2 PAGE 9

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.35 | 586.5 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.37 WATERSHED INCHES; 1120 CFS-HRS; 92.6 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.53 | 539.6 | 1375.24 |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.37 WATERSHED INCHES; 1120 CFS-HRS; 92.6 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI

INPUT RUNOFF CURVE= 84. TIME OF CONCENTRATION= .81 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1082 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.27 48.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.89 WATERSHED INCHES; 81 CFS-HRS; 6.7 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.51 579.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.33 WATERSHED INCHES; 1201 CFS-HRS; 99.2 ACRE-FEET.

OPERATION RESVOR STRUCTURE 14
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.00

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 2 PAGE 10

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.83 477.5 1373.28

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.33 WATERSHED INCHES; 1200 CFS-HRS; 99.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .31 SQ MI
INPUT RUNOFF CURVE= 86. TIME OF CONCENTRATION= 1.43 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.63 264.7 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.09 WATERSHED INCHES; 612 CFS-HRS; 50.6 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.69 737.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.24 WATERSHED INCHES; 1812 CFS-HRS; 149.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
MODIFIED ATT-KIN ROUTING COEFFICIENT = .62 PEAK TRAVEL TIME = .20 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.48 169.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.97 WATERSHED INCHES; 311 CFS-HRS; 25.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.20 125.6 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.16 WATERSHED INCHES; 198 CFS-HRS; 16.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
INPUT HYDROGRAPHS 1,2 OUTPUT HYDROGRAPH 3

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.34 273.3 (NULL)

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 3 PAGE 13

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 509 CFS-HRS; 42.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 257.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 509 CFS-HRS; 42.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.44 199.7 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.94 WATERSHED INCHES; 398 CFS-HRS; 32.9 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.43 456.9 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.99 WATERSHED INCHES; 907 CFS-HRS; 75.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.24 261.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.12 WATERSHED INCHES; 436 CFS-HRS; 36.0 ACRE-FEET.

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 3 PAGE 14

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.35 699.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 1343 CFS-HRS; 111.0 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.56 624.5 1375.65

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 1343 CFS-HRS; 111.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 84. TIME OF CONCENTRATION= .81 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1082 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.27 59.4 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.54 WATERSHED INCHES; 99 CFS-HRS; 8.1 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.51 671.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.00 WATERSHED INCHES; 1442 CFS-HRS; 119.2 ACRE-FEET.

OPERATION RESVOR STRUCTURE 14
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.00

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 3 PAGE 15

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.93 | 518.4 | 1373.94 |

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.00 WATERSHED INCHES; 1441 CFS-HRS; 119.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .31 SQ MI
INPUT RUNOFF CURVE= 86. TIME OF CONCENTRATION= 1.43 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.63 | 319.7 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.74 WATERSHED INCHES; 742 CFS-HRS; 61.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.72 | 823.3 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.91 WATERSHED INCHES; 2183 CFS-HRS; 180.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.30 | 439.0 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.30 WATERSHED INCHES; 741 CFS-HRS; 61.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.44 | 1185.2 | (NULL) |

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION

09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 3 PAGE 16

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.73 WATERSHED INCHES; 2924 CFS-HRS; 241.7 ACRE-FEET.

OPERATION RESVOR STRUCTURE 18
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1368.70

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
13.58 606.6 1370.91

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.58 WATERSHED INCHES; 2809 CFS-HRS; 232.1 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 3

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 4 PAGE 17

EXECUTIVE CONTROL COMPUT FROM XSECTION 1 TO STRUCTURE 18
STARTING TIME = .00 RAIN DEPTH = 7.80 RAIN DURATION= 1.00
ANT. MOIST. COND. = 2 MAIN TIME INCREMENT = .10 HOURS
ALTERNATE NO.=14 STORM NO.= 4 RAIN TABLE NO.= 7

OPERATION RUNOFF XSECTION 1
OUTPUT HYDROGRAPH= 1 AREA= .12 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= .91 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0992 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.32 277.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.44 WATERSHED INCHES; 505 CFS-HRS; 41.8 ACRE-FEET.

OPERATION REACH XSECTION 2
INPUT HYDROGRAPH 1 OUTPUT HYDROGRAPH 2
CHANNEL LENGTH 1500.00 FT
INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
MODIFIED ATT-KIN ROUTING COEFFICIENT = .67 PEAK TRAVEL TIME = .20 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.47 270.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.44 WATERSHED INCHES; 505 CFS-HRS; 41.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.20 197.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.66 WATERSHED INCHES; 317 CFS-HRS; 26.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
INPUT HYDROGRAPHS 1,2 OUTPUT HYDROGRAPH 3

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.34 436.0 (NULL)

1

TR20

EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 4 PAGE 18

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 822 CFS-HRS; 67.9 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.42 408.2 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 822 CFS-HRS; 68.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 318.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.40 WATERSHED INCHES; 647 CFS-HRS; 53.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 726.2 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.47 WATERSHED INCHES; 1469 CFS-HRS; 121.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.24 416.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.62 WATERSHED INCHES; 700 CFS-HRS; 57.9 ACRE-FEET.

1

TR20

EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 4 PAGE 19

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.34 1110.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 2170 CFS-HRS; 179.3 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.63 909.2 1377.30

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 2169 CFS-HRS; 179.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 84. TIME OF CONCENTRATION= .81 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1082 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.27 98.5 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.95 WATERSHED INCHES; 166 CFS-HRS; 13.7 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.57 976.8 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.47 WATERSHED INCHES; 2335 CFS-HRS; 193.0 ACRE-FEET.

OPERATION RESVOR STRUCTURE 14
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.00

1

TR20

EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 4 PAGE 20

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.95 850.8 1375.26

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.47 WATERSHED INCHES; 2335 CFS-HRS; 193.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .31 SQ MI
INPUT RUNOFF CURVE= 86. TIME OF CONCENTRATION= 1.43 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.62 521.8 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.19 WATERSHED INCHES; 1226 CFS-HRS; 101.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.87 1312.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.37 WATERSHED INCHES; 3561 CFS-HRS; 294.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.30 .745.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.67 WATERSHED INCHES; 1273 CFS-HRS; 105.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.45 1736.1 (NULL)
12.77 1684.6 (NULL)

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
13:35:38 PASS 4 PAGE 21

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.17 WATERSHED INCHES; 4835 CFS-HRS; 399.5 ACRE-FEET.

OPERATION RESVOR STRUCTURE 18
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1368.70

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
13.36 1091.2 1371.62

RUNOFF ABOVE BASEFLOW OF .00 CFS
 5.99 WATERSHED INCHES; 4698 CFS-HRS; 388.2 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 4
 1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
 13:35:38 PAGE 22

SUMMARY TABLE 1

SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
 A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
 F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA (SQ MI) | RUNOFF AMOUNT (IN) | PEAK DISCHARGE | | | |
|------------------------------|----------------------------------|-----------------------------|--------------------------|-------------------|--------------|---------------|---------------|
| | | | | ELEVATION (FT) | TIME (HR) | RATE (CFS) | RATE (CSM) |

RAINFALL OF 3.50 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs.
 RAINFALL NUMBER 7, AMC 2
 MAIN TIME INCREMENT .10 HOURS

ALTERNATE 11 STORM 1

| | | | | | | | |
|--------------|--------|------|------|---------|-------|-----|--------|
| XSECTION 1 | RUNOFF | .12 | 2.32 | --- | 12.33 | 104 | 866.7 |
| XSECTION 2 | REACH | .12 | 2.32 | --- | 12.50 | 100 | 833.3 |
| XSECTION 2 | RUNOFF | .07 | 2.49 | --- | 12.20 | 77 | 1100.0 |
| XSECTION 2 | ADDHYD | .20 | 2.38 | --- | 12.35 | 162 | 810.0 |
| XSECTION 5 | RUNOFF | .20 | 2.38 | --- | 12.43 | 154 | 770.0 |
| XSECTION 6 | RUNOFF | .16 | 2.29 | --- | 12.45 | 118 | 737.5 |
| XSECTION 7 | ADDHYD | .35 | 2.34 | --- | 12.44 | 271 | 774.3 |
| XSECTION 10 | RUNOFF | .16 | 2.45 | --- | 12.24 | 161 | 1006.3 |
| XSECTION 10 | ADDHYD | .52 | 2.38 | --- | 12.35 | 419 | 805.8 |
| STRUCTURE 10 | RESVOR | .52 | 2.38 | 1374.66 | 12.53 | 386 | 742.3 |
| XSECTION 14 | RUNOFF | .04 | 1.96 | --- | 12.28 | 33 | 825.0 |
| XSECTION 14 | ADDHYD | .56 | 2.35 | --- | 12.50 | 414 | 739.3 |
| STRUCTURE 14 | RESVOR | .56 | 2.34 | 1372.44 | 12.73 | 376 | 671.4 |
| XSECTION 16 | RUNOFF | .31 | 2.13 | --- | 12.64 | 183 | 590.3 |
| XSECTION 16 | ADDHYD | .87 | 2.27 | --- | 12.69 | 558 | 641.4 |
| XSECTION 18 | RUNOFF | .35 | 1.78 | --- | 12.31 | 237 | 677.1 |
| XSECTION 18 | ADDHYD | 1.21 | 2.13 | --- | 12.51 | 740 | 611.6 |
| STRUCTURE 18 | RESVOR | 1.21 | 2.13 | 1370.20 | 13.49 | 294 | 243.0 |

RAINFALL OF 4.55 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs.

ALTERNATE 12 STORM 2

| | | | | | | | |
|------------|--------|-----|------|-----|-------|-----|--------|
| XSECTION 1 | RUNOFF | .12 | 3.30 | --- | 12.32 | 146 | 1216.7 |
| XSECTION 2 | REACH | .12 | 3.30 | --- | 12.49 | 141 | 1175.0 |
| XSECTION 2 | RUNOFF | .07 | 3.49 | --- | 12.20 | 107 | 1528.6 |
| XSECTION 2 | ADDHYD | .20 | 3.37 | --- | 12.34 | 229 | 1145.0 |
| XSECTION 5 | RUNOFF | .20 | 3.37 | --- | 12.43 | 216 | 1080.0 |

1
 TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION

SUMMARY TABLE 1

 SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
 A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
 F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA (SQ MI) | RUNOFF AMOUNT (IN) | PEAK DISCHARGE | | | | |
|------------------------------|----------------------------------|-----------------------------|--------------------------|-------------------|--------------|---------------|---------------|--|
| | | | | ELEVATION (FT) | TIME (HR) | RATE (CFS) | RATE (CSM) | |
| ALTERNATE 12 STORM 2 | | ----- | | | | | | |
| XSECTION 6 | RUNOFF | .16 | 3.27 | --- | 12.44 | 167 | 1043.8 | |
| XSECTION 7 | ADDHYD | .35 | 3.33 | --- | 12.43 | 383 | 1094.3 | |
| XSECTION 10 | RUNOFF | .16 | 3.45 | --- | 12.24 | 221 | 1381.3 | |
| XSECTION 10 | ADDHYD | .52 | 3.37 | --- | 12.35 | 586 | 1126.9 | |
| STRUCTURE 10 | RESVOR | .52 | 3.37 | 1375.24 | 12.53 | 540 | 1038.5 | |
| XSECTION 14 | RUNOFF | .04 | 2.89 | --- | 12.27 | 49 | 1225.0 | |
| XSECTION 14 | ADDHYD | .56 | 3.33 | --- | 12.51 | 579 | 1033.9 | |
| STRUCTURE 14 | RESVOR | .56 | 3.33 | 1373.28 | 12.83 | 477 | 851.8 | |
| XSECTION 16 | RUNOFF | .31 | 3.09 | --- | 12.63 | 265 | 854.8 | |
| XSECTION 16 | ADDHYD | .87 | 3.24 | --- | 12.69 | 737 | 847.1 | |
| XSECTION 18 | RUNOFF | .35 | 2.68 | --- | 12.30 | 359 | 1025.7 | |
| XSECTION 18 | ADDHYD | 1.21 | 3.08 | --- | 12.50 | 1030 | 851.2 | |
| STRUCTURE 18 | RESVOR | 1.21 | 2.94 | 1370.64 | 13.50 | 490 | 405.0 | |

RAINFALL OF 5.25 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs.

| | | | | | | | | |
|----------------------|--------|-------|------|---------|-------|-----|--------|--|
| ALTERNATE 13 STORM 3 | | ----- | | | | | | |
| XSECTION 1 | RUNOFF | .12 | 3.97 | --- | 12.32 | 174 | 1450.0 | |
| XSECTION 2 | REACH | .12 | 3.97 | --- | 12.48 | 169 | 1408.3 | |
| XSECTION 2 | RUNOFF | .07 | 4.16 | --- | 12.20 | 126 | 1800.0 | |
| XSECTION 2 | ADDHYD | .20 | 4.04 | --- | 12.34 | 273 | 1365.0 | |
| XSECTION 5 | RUNOFF | .20 | 4.04 | --- | 12.43 | 257 | 1285.0 | |
| XSECTION 6 | RUNOFF | .16 | 3.94 | --- | 12.44 | 200 | 1250.0 | |
| XSECTION 7 | ADDHYD | .35 | 3.99 | --- | 12.43 | 457 | 1305.7 | |
| XSECTION 10 | RUNOFF | .16 | 4.12 | --- | 12.24 | 262 | 1637.5 | |
| XSECTION 10 | ADDHYD | .52 | 4.04 | --- | 12.35 | 699 | 1344.2 | |
| STRUCTURE 10 | RESVOR | .52 | 4.04 | 1375.65 | 12.56 | 624 | 1200.0 | |
| XSECTION 14 | RUNOFF | .04 | 3.54 | --- | 12.27 | 59 | 1475.0 | |
| XSECTION 14 | ADDHYD | .56 | 4.00 | --- | 12.51 | 671 | 1198.2 | |
| STRUCTURE 14 | RESVOR | .56 | 4.00 | 1373.94 | 12.93 | 518 | 925.0 | |

1

SUMMARY TABLE 1

 SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.

BASEFLOW IS .0 CFS

| ALTERNATE | | STORM | | | | | | | | | |
|-----------|------|-------|------|-----|------|-----|------|------|------|------|--|
| 2 | 1500 | 103 | 12.3 | 100 | 12.5 | .85 | 1.30 | .045 | .963 | .57 | |
| 2 | 1500 | 146 | 12.3 | 141 | 12.5 | .85 | 1.30 | .040 | .968 | .61 | |
| 2 | 1500 | 174 | 12.3 | 169 | 12.5 | .85 | 1.30 | .038 | .970 | .62 | |
| 2 | 1500 | 277 | 12.3 | 270 | 12.5 | .85 | 1.30 | .032 | .973 | .67? | |

1

TR20

EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECH2- W/O 2X12 16 AUG 2002 2,5,10,100-YR 24-HR STORM ZONE 510/01/90
 13:35:38 PAGE 26

SUMMARY TABLE 3

STORM DISCHARGES (CFS) AT XSECTIONS AND STRUCTURES FOR ALL ALTERNATES

| XSECTION/ STRUCTURE ID | DRAINAGE AREA (SQ MI) | STORM NUMBERS..... | | | |
|------------------------------|-----------------------------|--------------------|-------|-------|-------|
| | | 1 | 2 | 3 | 4 |
| STRUCTURE 18 | 1.21 | | | | |
| ALTERNATE 11 | | 294 | ***** | ***** | ***** |
| ALTERNATE 12 | | ***** | 490 | ***** | ***** |
| ALTERNATE 13 | | ***** | ***** | 607 | ***** |
| ALTERNATE 14 | | ***** | ***** | ***** | 1091 |
| STRUCTURE 14 | .56 | | | | |
| ALTERNATE 11 | | 376 | ***** | ***** | ***** |
| ALTERNATE 12 | | ***** | 477 | ***** | ***** |
| ALTERNATE 13 | | ***** | ***** | 518 | ***** |
| ALTERNATE 14 | | ***** | ***** | ***** | 851 |
| STRUCTURE 10 | .52 | | | | |
| ALTERNATE 11 | | 386 | ***** | ***** | ***** |
| ALTERNATE 12 | | ***** | 540 | ***** | ***** |
| ALTERNATE 13 | | ***** | ***** | 624 | ***** |
| ALTERNATE 14 | | ***** | ***** | ***** | 909 |
| XSECTION 1 | .12 | | | | |
| ALTERNATE 11 | | 104 | ***** | ***** | ***** |
| ALTERNATE 12 | | ***** | 146 | ***** | ***** |
| ALTERNATE 13 | | ***** | ***** | 174 | ***** |
| ALTERNATE 14 | | ***** | ***** | ***** | 277 |
| XSECTION 2 | .20 | | | | |
| ALTERNATE 11 | | 162 | ***** | ***** | ***** |

ALTERNATE 12 ***** 1030 *****
ALTERNATE 13 ***** 1185 *****
ALTERNATE 14 ***** 1736 *****

*** WARNING - UNEXPECTED RECORD(S) ENCOUNTERED WHEN LOOKING FOR "JOB" RECORD.
IMAGES OF FIRST 10 RECORDS IGNORED FOLLOWS: ***

END OF 1 JOBS IN THIS RUN
1

SCS TR-20, VERSION 10/01/90
FILES

INPUT = beech2.t20
OUTPUT = beech2.out

, DATED 09/27/**,13:35:38

FILES GENERATED - DATED 09/27/**,13:35:38

NONE!

*** TR-20 RUN COMPLETED ***

Appendix E
Drainage and Utility Plan

Appendix F
Lot Grading Plan

Appendix G

Proposed TR-20 Output

*****80-80 LIST OF INPUT DATA FOR TR-20 HYDROLOGY*****

| JOB | TR-20 | FULLPRINT | SUMMARY | NOPLOTS |
|-------|--------------|---|---------------------------|-------------|
| TITLE | 001 | EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK | | |
| TITLE | BEECHPR2.T20 | 2-6'x3' 20 SEP 02 | 2,5,10,100-YR 24-HR STORM | ZONE 5 |
| 4 | DIMHYD | 0.02 | | 484 |
| 8 | .000 | .030 | .100 | .190 .310 |
| 8 | .470 | .660 | .820 | .930 .990 |
| 8 | 1.000 | .990 | .930 | .860 .780 |
| 8 | .680 | .560 | .460 | .390 .330 |
| 8 | .280 | .241 | .207 | .174 .147 |
| 8 | .126 | .107 | .091 | .077 .066 |
| 8 | .055 | .047 | .040 | .034 .029 |
| 8 | .025 | .021 | .018 | .015 .013 |
| 8 | .011 | .009 | .008 | .007 .006 |
| 8 | .005 | .004 | .003 | .002 .001 |
| 8 | .000 | .000 | .000 | .000 .000 |
| 9 | ENDTBL | | | |
| 5 | RAINFL 7 | 0.5 | | |
| 8 | .000 | .002 | .005 | .009 .013 |
| 8 | .018 | .023 | .029 | .035 .042 |
| 8 | .050 | .059 | .068 | .078 .089 |
| 8 | .101 | .114 | .128 | .144 .162 |
| 8 | .183 | .208 | .244 | .339 .723 |
| 8 | .773 | .802 | .825 | .844 .861 |
| 8 | .876 | .890 | .903 | .914 .924 |
| 8 | .934 | .943 | .951 | .959 .966 |
| 8 | .972 | .977 | .982 | .986 .990 |
| 8 | .993 | .996 | .998 | 1.000 1.000 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 10 | | |
| 8 | | 1369.4 | 0.0 | 0.0 |
| 8 | | 1370.4 | 6.0 | 0.279 |
| 8 | | 1371.4 | 14.0 | 1.093 |
| 8 | | 1372.4 | 30.0 | 2.269 |
| 8 | | 1373.4 | 60.0 | 3.606 |
| 8 | | 1374.4 | 320.0 | 7.212 |
| 8 | | 1375.4 | 580.0 | 11.361 |
| 8 | | 1376.4 | 760.0 | 16.450 |
| 8 | | 1377.4 | 925.0 | 23.036 |
| 8 | | 1378.4 | 1085.0 | 31.035 |
| 8 | | 1379.4 | 1240.0 | 40.834 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 16 | | |
| 8 | | 1372.0 | 0.0 | 0.0 |
| 8 | | 1373.0 | 36.5 | 2.98 |
| 8 | | 1374.0 | 75.9 | 6.12 |
| 8 | | 1375.0 | 158.7 | 9.44 |

*****80-80 LIST OF INPUT DATA (CONTINUED)*****

| | | | | |
|---|--------|--------|-------|-------|
| 8 | | 1376.0 | 231.5 | 12.94 |
| 8 | | 1377.0 | 356.0 | 16.61 |
| 8 | | 1378.0 | 380.5 | 20.47 |
| 9 | ENDTBL | | | |
| 3 | STRUCT | 20 | | |
| 8 | | 1368.7 | 0.0 | 0.0 |

| | | | | | | | | |
|---|----------|---|-----|--------|--------|--------|--------|-----------|
| 8 | | | | 1369.7 | 100.0 | 41.3 | | |
| 8 | | | | 1370.0 | 208.0 | 53.3 | | |
| 8 | | | | 1371.0 | 647.0 | 107.8 | | |
| 8 | | | | 1372.0 | 1365.0 | 171.3 | | |
| 9 | ENDTBL | | | | | | | |
| 6 | RUNOFF | 1 | 001 | 1 | 0.1216 | 88.6 | 0.9092 | 1 |
| 6 | REACH | 3 | 002 | 1 | 2 | 1500.0 | 0.85 | 1.3 |
| 6 | RUNOFF | 1 | 002 | 1 | 0.0737 | 90.5 | 0.7025 | 1 |
| 6 | ADDHYD | 4 | 002 | 1 | 2 | 3 | | 1 |
| 6 | RUNOFF | 1 | 005 | 5 | 0.1953 | 89.3 | 1.0958 | 1 |
| 6 | RUNOFF | 1 | 006 | 6 | 0.1566 | 88.3 | 1.1117 | 1 |
| 6 | ADDHYD | 4 | 007 | 5 | 6 | 7 | | 1 |
| 6 | RUNOFF | 1 | 010 | 6 | 0.1638 | 90.1 | 0.775 | 1 |
| 6 | ADDHYD | 4 | 010 | 7 | 6 | 5 | | 1 |
| 6 | RESVOR | 2 | | 10 | 5 | 7 | 1369.4 | 1 |
| 6 | RUNOFF | 1 | 014 | 6 | 0.0432 | 93.0 | 0.333 | 1 |
| 6 | ADDHYD | 4 | 014 | 7 | 6 | 5 | | 1 |
| 6 | RUNOFF | 1 | 015 | 4 | 0.0531 | 78.0 | 0.700 | 1 |
| 6 | RUNOFF | 1 | 016 | 6 | 0.0844 | 80.0 | 0.792 | 1 |
| 6 | ADDHYD | 4 | 016 | 4 | 6 | 7 | | 1 |
| 6 | RESVOR | 2 | | 16 | 7 | 6 | 1372.0 | 1 |
| 6 | RUNOFF | 1 | 017 | 4 | 0.0948 | 96.3 | 0.42 | 1 |
| 6 | ADDHYD | 4 | 017 | 4 | 6 | 7 | | 1 |
| 6 | RUNOFF | 1 | 018 | 6 | 0.0739 | 78.0 | 0.79 | 1 |
| 6 | ADDHYD | 4 | 018 | 6 | 7 | 4 | | 1 |
| 6 | ADDHYD | 4 | 019 | 4 | 5 | 6 | | 1 |
| 6 | RUNOFF | 1 | 020 | 5 | 0.3483 | 82.0 | 0.866 | 1 |
| 6 | ADDHYD | 4 | 020 | 6 | 5 | 7 | | 1 |
| 6 | RESVOR | 2 | | 20 | 7 | 5 | 1369.7 | 1 |
| | ENDATA | | | | | | | |
| 7 | INCREM | 6 | | | 0.10 | | | |
| 7 | COMPUT | 7 | 001 | 20 | 0.0 | 3.50 | 1.0 | 7 2 11 01 |
| | ENDCMP 1 | | | | | | | |
| 7 | COMPUT | 7 | 001 | 20 | 0.0 | 4.55 | 1.0 | 7 2 12 02 |
| | ENDCMP 1 | | | | | | | |
| 7 | COMPUT | 7 | 001 | 20 | 0.0 | 5.25 | 1.0 | 7 2 13 03 |
| | ENDCMP 1 | | | | | | | |
| 7 | COMPUT | 7 | 001 | 20 | 0.0 | 7.80 | 1.0 | 7 2 14 04 |
| | ENDCMP 1 | | | | | | | |
| | ENDJOB 2 | | | | | | | |

1

*****80-80 LIST OF INPUT DATA (CONTINUED)*****

*****END OF 80-80 LIST*****

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
 13:36:02 PASS 1 PAGE 1

| | DIMENSIONLESS HYDROGRAPH TABLE ENTERED | | | | | TIME INCREMENT = .02 |
|---|--|-------|-------|-------|-------|----------------------|
| 8 | .0000 | .0300 | .1000 | .1900 | .3100 | |
| 8 | .4700 | .6600 | .8200 | .9300 | .9900 | |
| 8 | 1.0000 | .9900 | .9300 | .8600 | .7800 | |
| 8 | .6800 | .5600 | .4600 | .3900 | .3300 | |
| 8 | .2800 | .2410 | .2070 | .1740 | .1470 | |

2.45 WATERSHED INCHES; 260 CFS-HRS; 21.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.35 418.8 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 792 CFS-HRS; 65.4 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.53 386.3 1374.66

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.38 WATERSHED INCHES; 791 CFS-HRS; 65.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 93. TIME OF CONCENTRATION= .33 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0444 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.01 63.4 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.73 WATERSHED INCHES; 76 CFS-HRS; 6.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.51 399.2 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.40 WATERSHED INCHES; 867 CFS-HRS; 71.7 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 1 PAGE 5

OPERATION RUNOFF XSECTION 15
OUTPUT HYDROGRAPH= 4 AREA= .05 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0933 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.21 33.7 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.49 WATERSHED INCHES; 51 CFS-HRS; 4.2 ACRE-FEET.

OPERATION RUNOFF XSECTION 16

OUTPUT HYDROGRAPH= 6 AREA= .08 SQ MI
INPUT RUNOFF CURVE= 80. TIME OF CONCENTRATION= .79 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1056 HOURS

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.27 | 55.1 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.64 WATERSHED INCHES; 89 CFS-HRS; 7.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 16

INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.24 | 88.5 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.58 WATERSHED INCHES; 140 CFS-HRS; 11.6 ACRE-FEET.

OPERATION RESVOR STRUCTURE 16

INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 6
SURFACE ELEVATION= 1372.00

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.74 | 44.1 | 1373.19 |

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.58 WATERSHED INCHES; 140 CFS-HRS; 11.6 ACRE-FEET.

OPERATION RUNOFF XSECTION 17

OUTPUT HYDROGRAPH= 4 AREA= .09 SQ MI
INPUT RUNOFF CURVE= 96. TIME OF CONCENTRATION= .42 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0560 HOURS

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 1 PAGE 6

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.05 | 141.8 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.07 WATERSHED INCHES; 188 CFS-HRS; 15.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 17

INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

| PEAK TIME(HRS) | PEAK DISCHARGE(CFS) | PEAK ELEVATION(FEET) |
|----------------|---------------------|----------------------|
| 12.08 | 160.4 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.19 WATERSHED INCHES; 329 CFS-HRS; 27.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 18

OUTPUT HYDROGRAPH= 6 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .79 HOURS

COMPUTED INTERNAL TIME INCREMENT = .1053 HOURS

| | | |
|-----------------|----------------------|-----------------------|
| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
| 12.27 | 43.3 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.50 WATERSHED INCHES; 71 CFS-HRS; 5.9 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 6,7 OUTPUT HYDROGRAPH 4

| | | |
|-----------------|----------------------|-----------------------|
| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
| 12.11 | 198.1 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.02 WATERSHED INCHES; 400 CFS-HRS; 33.0 ACRE-FEET.

OPERATION ADDHYD XSECTION 19
INPUT HYDROGRAPHS 4,5 OUTPUT HYDROGRAPH 6

| | | |
|-----------------|----------------------|-----------------------|
| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
| 12.29 | 532.6 | (NULL) |

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 1 PAGE 7

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.27 WATERSHED INCHES; 1267 CFS-HRS; 104.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 20
OUTPUT HYDROGRAPH= 5 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

| | | |
|-----------------|----------------------|-----------------------|
| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
| 12.31 | 236.8 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.78 WATERSHED INCHES; 400 CFS-HRS; 33.1 ACRE-FEET.

OPERATION ADDHYD XSECTION 20
INPUT HYDROGRAPHS 6,5 OUTPUT HYDROGRAPH 7

| | | |
|-----------------|----------------------|-----------------------|
| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
| 12.30 | 769.3 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.13 WATERSHED INCHES; 1667 CFS-HRS; 137.8 ACRE-FEET.

OPERATION RESVOR STRUCTURE 20
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1369.70

*** MESSAGE - STRUCTURE 20, USER ENTERED STARTING ELEVATION (1369.7 FEET)
WILL DECREASE OUTFLOW HYDROGRAPH VOLUME.

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
13.55 217.8 1370.02

RUNOFF ABOVE BASEFLOW OF .00 CFS
 .20 WATERSHED INCHES; 154 CFS-HRS; 12.7 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 1

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 2 PAGE 8

EXECUTIVE CONTROL COMPUT FROM XSECTION 1 TO STRUCTURE 20
STARTING TIME = .00 RAIN DEPTH = 4.55 RAIN DURATION= 1.00
ANT. MOIST. COND. = 2 MAIN TIME INCREMENT = .10 HOURS
ALTERNATE NO.=12 STORM NO.= 2 RAIN TABLE NO.= 7

OPERATION RUNOFF XSECTION 1
OUTPUT HYDROGRAPH= 1 AREA= .12 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= .91 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0992 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.32 146.0 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 3.30 WATERSHED INCHES; 259 CFS-HRS; 21.4 ACRE-FEET.

OPERATION REACH XSECTION 2
INPUT HYDROGRAPH 1 OUTPUT HYDROGRAPH 2
CHANNEL LENGTH 1500.00 FT
INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
MODIFIED ATT-KIN ROUTING COEFFICIENT = .61 PEAK TRAVEL TIME = .20 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.49 141.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 3.30 WATERSHED INCHES; 259 CFS-HRS; 21.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.20 107.0 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 3.49 WATERSHED INCHES; 166 CFS-HRS; 13.7 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
 INPUT HYDROGRAPHS 1, 2 OUTPUT HYDROGRAPH 3

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.34 229.1 (NULL)

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.27 83.8 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.50 WATERSHED INCHES; 136 CFS-HRS; 11.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
 INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.24 136.8 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.44 WATERSHED INCHES; 216 CFS-HRS; 17.9 ACRE-FEET.

OPERATION RESVOR STRUCTURE 16
 INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 6
 SURFACE ELEVATION= 1372.00

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.72 69.6 1373.84

RUNOFF ABOVE BASEFLOW OF .00 CFS
 2.44 WATERSHED INCHES; 216 CFS-HRS; 17.9 ACRE-FEET.

OPERATION RUNOFF XSECTION 17
 OUTPUT HYDROGRAPH= 4 AREA= .09 SQ MI
 INPUT RUNOFF CURVE= 96. TIME OF CONCENTRATION= .42 HOURS
 COMPUTED INTERNAL TIME INCREMENT = .0560 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.05 186.8 (RUNOFF)

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 2 PAGE 12

RUNOFF ABOVE BASEFLOW OF .00 CFS
 4.12 WATERSHED INCHES; 252 CFS-HRS; 20.8 ACRE-FEET.

OPERATION ADDHYD XSECTION 17
 INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.09 218.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
 3.12 WATERSHED INCHES; 468 CFS-HRS; 38.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
 OUTPUT HYDROGRAPH= 6 AREA= .07 SQ MI
 INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .79 HOURS
 COMPUTED INTERNAL TIME INCREMENT = .1053 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.26 69.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.33 WATERSHED INCHES; 111 CFS-HRS; 9.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 6,7 OUTPUT HYDROGRAPH 4

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.12 279.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.93 WATERSHED INCHES; 579 CFS-HRS; 47.9 ACRE-FEET.

OPERATION ADDHYD XSECTION 19
INPUT HYDROGRAPHS 4,5 OUTPUT HYDROGRAPH 6

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.31 747.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.23 WATERSHED INCHES; 1804 CFS-HRS; 149.1 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 2 PAGE 13

OPERATION RUNOFF XSECTION 20
OUTPUT HYDROGRAPH= 5 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.30 359.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.68 WATERSHED INCHES; 602 CFS-HRS; 49.8 ACRE-FEET.

OPERATION ADDHYD XSECTION 20
INPUT HYDROGRAPHS 6,5 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.31 1106.7 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.07 WATERSHED INCHES; 2406 CFS-HRS; 198.9 ACRE-FEET.

OPERATION RESVOR STRUCTURE 20
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1369.70

*** MESSAGE - STRUCTURE 20, USER ENTERED STARTING ELEVATION (1369.7 FEET)
WILL DECREASE OUTFLOW HYDROGRAPH VOLUME. ***

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
13.32 405.0 1370.45

RUNOFF ABOVE BASEFLOW OF .00 CFS

1.12 WATERSHED INCHES; 880 CFS-HRS; 72.7 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 2

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 3 PAGE 14

EXECUTIVE CONTROL COMPUT FROM XSECTION 1 TO STRUCTURE 20
STARTING TIME = .00 RAIN DEPTH = 5.25 RAIN DURATION= 1.00
ANT. MOIST. COND. = 2 MAIN TIME INCREMENT = .10 HOURS
ALTERNATE NO.=13 STORM NO.= 3 RAIN TABLE NO.= 7

OPERATION RUNOFF XSECTION 1
OUTPUT HYDROGRAPH= 1 AREA= .12 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= .91 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0992 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.32 | 174.3 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.97 WATERSHED INCHES; 311 CFS-HRS; 25.7 ACRE-FEET.

OPERATION REACH XSECTION 2
INPUT HYDROGRAPH 1 OUTPUT HYDROGRAPH 2
CHANNEL LENGTH 1500.00 FT
INPUT = COEFFICIENTS RELATED TO XSECTION AREA, X= .85, M= 1.30
MODIFIED ATT-KIN ROUTING COEFFICIENT = .62 PEAK TRAVEL TIME = .20 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.48 | 169.0 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.97 WATERSHED INCHES; 311 CFS-HRS; 25.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 2
OUTPUT HYDROGRAPH= 1 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 91. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0937 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.20 | 125.6 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.16 WATERSHED INCHES; 198 CFS-HRS; 16.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 2
INPUT HYDROGRAPHS 1,2 OUTPUT HYDROGRAPH 3

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.34 | 273.3 | (NULL) |

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90

13:36:02

PASS 3

PAGE 15

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 509 CFS-HRS; 42.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 257.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 509 CFS-HRS; 42.1 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.44 199.7 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.94 WATERSHED INCHES; 398 CFS-HRS; 32.9 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 456.9 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.99 WATERSHED INCHES; 907 CFS-HRS; 75.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.24 261.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.12 WATERSHED INCHES; 436 CFS-HRS; 36.0 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 3 PAGE 16

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.35 699.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 1343 CFS-HRS; 111.0 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.56 624.5 1375.65

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.04 WATERSHED INCHES; 1343 CFS-HRS; 111.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 93. TIME OF CONCENTRATION= .33 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0444 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.01 99.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.44 WATERSHED INCHES; 124 CFS-HRS; 10.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.53 643.2 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.07 WATERSHED INCHES; 1467 CFS-HRS; 121.2 ACRE-FEET.

OPERATION RUNOFF XSECTION 15
OUTPUT HYDROGRAPH= 4 AREA= .05 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0933 HOURS

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 3 PAGE 17

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.21 66.4 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.92 WATERSHED INCHES; 100 CFS-HRS; 8.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .08 SQ MI
INPUT RUNOFF CURVE= 80. TIME OF CONCENTRATION= .79 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1056 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.26 104.3 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.11 WATERSHED INCHES; 169 CFS-HRS; 14.0 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.24 170.1 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.04 WATERSHED INCHES; 269 CFS-HRS; 22.3 ACRE-FEET.

OPERATION RESVOR STRUCTURE 16
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 6
SURFACE ELEVATION= 1372.00

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.68 95.1 1374.23

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.04 WATERSHED INCHES; 269 CFS-HRS; 22.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 17
OUTPUT HYDROGRAPH= 4 AREA= .09 SQ MI
INPUT RUNOFF CURVE= 96. TIME OF CONCENTRATION= .42 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0560 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.05 216.7 (RUNOFF)

1.

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 3 PAGE 18

RUNOFF ABOVE BASEFLOW OF .00 CFS
4.81 WATERSHED INCHES; 294 CFS-HRS; 24.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 17
INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.09 257.4 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.76 WATERSHED INCHES; 564 CFS-HRS; 46.6 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .79 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1053 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.26 36.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
2.92 WATERSHED INCHES; 139 CFS-HRS; 11.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 6,7 OUTPUT HYDROGRAPH 4

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.12 334.5 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.56 WATERSHED INCHES; 703 CFS-HRS; 58.1 ACRE-FEET.

OPERATION ADDHYD XSECTION 19
INPUT HYDROGRAPHS 4,5 OUTPUT HYDROGRAPH 6

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.29 894.0 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.89 WATERSHED INCHES; 2170 CFS-HRS; 179.3 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 3 PAGE 19

OPERATION RUNOFF XSECTION 20
OUTPUT HYDROGRAPH= 5 AREA= .35 SQ MI
INPUT RUNOFF CURVE= 82. TIME OF CONCENTRATION= .87 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0945 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.30 438.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.30 WATERSHED INCHES; 741 CFS-HRS; 61.3 ACRE-FEET.

OPERATION ADDHYD XSECTION 20
INPUT HYDROGRAPHS 6,5 OUTPUT HYDROGRAPH 7

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.30 1332.7 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
3.72 WATERSHED INCHES; 2911 CFS-HRS; 240.6 ACRE-FEET.

OPERATION RESVOR STRUCTURE 20
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 5
SURFACE ELEVATION= 1369.70

*** MESSAGE - STRUCTURE 20, USER ENTERED STARTING ELEVATION (1369.7 FEET)
WILL DECREASE OUTFLOW HYDROGRAPH VOLUME. ***

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
13.25 532.3 1370.74

RUNOFF ABOVE BASEFLOW OF .00 CFS
1.76 WATERSHED INCHES; 1378 CFS-HRS; 113.9 ACRE-FEET.

EXECUTIVE CONTROL ENDCMP COMPUTATIONS COMPLETED FOR PASS 3

6.52 WATERSHED INCHES; 822 CFS-HRS; 67.9 ACRE-FEET.

OPERATION RUNOFF XSECTION 5
OUTPUT HYDROGRAPH= 5 AREA= .20 SQ MI
INPUT RUNOFF CURVE= 89. TIME OF CONCENTRATION= 1.10 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1012 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.42 408.2 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 822 CFS-HRS; 68.0 ACRE-FEET.

OPERATION RUNOFF XSECTION 6
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 88. TIME OF CONCENTRATION= 1.11 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1026 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 318.1 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.40 WATERSHED INCHES; 647 CFS-HRS; 53.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 7
INPUT HYDROGRAPHS 5,6 OUTPUT HYDROGRAPH 7

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.43 726.2 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.47 WATERSHED INCHES; 1469 CFS-HRS; 121.4 ACRE-FEET.

OPERATION RUNOFF XSECTION 10
OUTPUT HYDROGRAPH= 6 AREA= .16 SQ MI
INPUT RUNOFF CURVE= 90. TIME OF CONCENTRATION= .77 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1033 HOURS

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.24 416.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.62 WATERSHED INCHES; 700 CFS-HRS; 57.9 ACRE-FEET.

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 4 PAGE 22

OPERATION ADDHYD XSECTION 10
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME (HRS) PEAK DISCHARGE (CFS) PEAK ELEVATION (FEET)
12.34 1110.6 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 2170 CFS-HRS; 179.3 ACRE-FEET.

OPERATION RESVOR STRUCTURE 10
INPUT HYDROGRAPH 5 OUTPUT HYDROGRAPH 7
SURFACE ELEVATION= 1369.40

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.63 909.2 1377.30

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.52 WATERSHED INCHES; 2169 CFS-HRS; 179.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 14
OUTPUT HYDROGRAPH= 6 AREA= .04 SQ MI
INPUT RUNOFF CURVE= 93. TIME OF CONCENTRATION= .33 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0444 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.01 153.2 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.95 WATERSHED INCHES; 194 CFS-HRS; 16.0 ACRE-FEET.

OPERATION ADDHYD XSECTION 14
INPUT HYDROGRAPHS 7,6 OUTPUT HYDROGRAPH 5

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.60 933.7 (NULL)

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.55 WATERSHED INCHES; 2363 CFS-HRS; 195.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 15
OUTPUT HYDROGRAPH= 4 AREA= .05 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .70 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0933 HOURS

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 4 PAGE 23

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.20 116.9 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.19 WATERSHED INCHES; 178 CFS-HRS; 14.7 ACRE-FEET.

OPERATION RUNOFF XSECTION 16
OUTPUT HYDROGRAPH= 6 AREA= .08 SQ MI
INPUT RUNOFF CURVE= 80. TIME OF CONCENTRATION= .79 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1056 HOURS

PEAK TIME(HRS) PEAK DISCHARGE(CFS) PEAK ELEVATION(FEET)
12.26 179.5 (RUNOFF)

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.43 WATERSHED INCHES; 296 CFS-HRS; 24.4 ACRE-FEET.

OPERATION ADDHYD XSECTION 16
INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.23 | 295.6 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.34 WATERSHED INCHES; 474 CFS-HRS; 39.1 ACRE-FEET.

OPERATION RESVOR STRUCTURE 16
INPUT HYDROGRAPH 7 OUTPUT HYDROGRAPH 6
SURFACE ELEVATION= 1372.00

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.60 | 189.6 | 1375.42 |

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.34 WATERSHED INCHES; 474 CFS-HRS; 39.2 ACRE-FEET.

OPERATION RUNOFF XSECTION 17
OUTPUT HYDROGRAPH= 4 AREA= .09 SQ MI
INPUT RUNOFF CURVE= 96. TIME OF CONCENTRATION= .42 HOURS
COMPUTED INTERNAL TIME INCREMENT = .0560 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.05 | 325.0 | (RUNOFF) |

1

TR20 -----
EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PASS 4 PAGE 24

RUNOFF ABOVE BASEFLOW OF .00 CFS
7.35 WATERSHED INCHES; 450 CFS-HRS; 37.2 ACRE-FEET.

OPERATION ADDHYD XSECTION 17
INPUT HYDROGRAPHS 4,6 OUTPUT HYDROGRAPH 7

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.12 | 408.8 | (NULL) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
6.16 WATERSHED INCHES; 924 CFS-HRS; 76.3 ACRE-FEET.

OPERATION RUNOFF XSECTION 18
OUTPUT HYDROGRAPH= 6 AREA= .07 SQ MI
INPUT RUNOFF CURVE= 78. TIME OF CONCENTRATION= .79 HOURS
COMPUTED INTERNAL TIME INCREMENT = .1053 HOURS

| PEAK TIME (HRS) | PEAK DISCHARGE (CFS) | PEAK ELEVATION (FEET) |
|-----------------|----------------------|-----------------------|
| 12.25 | 153.1 | (RUNOFF) |

RUNOFF ABOVE BASEFLOW OF .00 CFS
5.20 WATERSHED INCHES; 248 CFS-HRS; 20.5 ACRE-FEET.

OPERATION ADDHYD XSECTION 18
INPUT HYDROGRAPHS 6,7 OUTPUT HYDROGRAPH 4

SUMMARY TABLE 1

SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
 A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
 F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA (SQ MI) | RUNOFF AMOUNT (IN) | PEAK DISCHARGE | | | | |
|------------------------------|----------------------------------|-----------------------------|--------------------------|-------------------|---------------------|---------------|---------------|--------|
| | | | | ELEVATION (FT) | TIME (HR) | RATE (CFS) | RATE (CSM) | |
| RAINFALL OF | | 3.50 inches | AND | 24.00 hr | DURATION, BEGINS AT | .0 hrs. | | |
| RAINTABLE NUMBER | | 7, | AMC 2 | | | | | |
| MAIN TIME INCREMENT | | .10 HOURS | | | | | | |
| ALTERNATE | | 11 | STORM | 1 | | | | |
| XSECTION | 1 | RUNOFF | .12 | 2.32 | --- | 12.33 | 104 | 866.7 |
| XSECTION | 2 | REACH | .12 | 2.32 | --- | 12.50 | 100 | 833.3 |
| XSECTION | 2 | RUNOFF | .07 | 2.49 | --- | 12.20 | 77 | 1100.0 |
| XSECTION | 2 | ADDHYD | .20 | 2.38 | --- | 12.35 | 162 | 810.0 |
| XSECTION | 5 | RUNOFF | .20 | 2.38 | --- | 12.43 | 154 | 770.0 |
| XSECTION | 6 | RUNOFF | .16 | 2.29 | --- | 12.45 | 118 | 737.5 |
| XSECTION | 7 | ADDHYD | .35 | 2.34 | --- | 12.44 | 271 | 774.3 |
| XSECTION | 10 | RUNOFF | .16 | 2.45 | --- | 12.24 | 161 | 1006.3 |
| XSECTION | 10 | ADDHYD | .52 | 2.38 | --- | 12.35 | 419 | 805.8 |
| STRUCTURE | 10 | RESVOR | .52 | 2.38 | 1374.66 | 12.53 | 386 | 742.3 |
| XSECTION | 14 | RUNOFF | .04 | 2.73 | --- | 12.01 | 63 | 1575.0 |
| XSECTION | 14 | ADDHYD | .56 | 2.40 | --- | 12.51 | 399 | 712.5 |
| XSECTION | 15 | RUNOFF | .05 | 1.49 | --- | 12.21 | 34 | 680.0 |
| XSECTION | 16 | RUNOFF | .08 | 1.64 | --- | 12.27 | 55 | 687.5 |
| XSECTION | 16 | ADDHYD | .14 | 1.58 | --- | 12.24 | 89 | 635.7 |
| STRUCTURE | 16 | RESVOR | .14 | 1.58 | 1373.19 | 12.74 | 44 | 314.3 |
| XSECTION | 17 | RUNOFF | .09 | 3.07 | --- | 12.05 | 142 | 1577.8 |
| XSECTION | 17 | ADDHYD | .23 | 2.19 | --- | 12.08 | 160 | 695.7 |
| XSECTION | 18 | RUNOFF | .07 | 1.50 | --- | 12.27 | 43 | 614.3 |
| XSECTION | 18 | ADDHYD | .31 | 2.02 | --- | 12.11 | 198 | 638.7 |
| XSECTION | 19 | ADDHYD | .87 | 2.27 | --- | 12.29 | 533 | 612.6 |
| XSECTION | 20 | RUNOFF | .35 | 1.78 | --- | 12.31 | 237 | 677.1 |
| XSECTION | 20 | ADDHYD | 1.21 | 2.13 | --- | 12.30 | 769 | 635.5 |
| STRUCTURE | 20 | RESVOR | 1.21 | .20 | 1370.02 | 13.55 | 218 | 180.2 |

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
 13:36:02 PAGE 27

SUMMARY TABLE 1

SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
 A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
 F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA | RUNOFF AMOUNT | PEAK DISCHARGE | | | |
|------------------------------|----------------------------------|------------------|------------------|----------------|------|------|------|
| | | | | ELEVATION | TIME | RATE | RATE |

(SQ MI) (IN) (FT) (HR) (CFS) (CSM)

RAINFALL OF 4.55 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs.

| ALTERNATE | | 12 | STORM | 2 | | | | |
|-----------|----|--------|-------|------|---------|-------|------|--------|
| XSECTION | 1 | RUNOFF | .12 | 3.30 | --- | 12.32 | 146 | 1216.7 |
| XSECTION | 2 | REACH | .12 | 3.30 | --- | 12.49 | 141 | 1175.0 |
| XSECTION | 2 | RUNOFF | .07 | 3.49 | --- | 12.20 | 107 | 1528.6 |
| XSECTION | 2 | ADDHYD | .20 | 3.37 | --- | 12.34 | 229 | 1145.0 |
| XSECTION | 5 | RUNOFF | .20 | 3.37 | --- | 12.43 | 216 | 1080.0 |
| XSECTION | 6 | RUNOFF | .16 | 3.27 | --- | 12.44 | 167 | 1043.8 |
| XSECTION | 7 | ADDHYD | .35 | 3.33 | --- | 12.43 | 383 | 1094.3 |
| XSECTION | 10 | RUNOFF | .16 | 3.45 | --- | 12.24 | 221 | 1381.3 |
| XSECTION | 10 | ADDHYD | .52 | 3.37 | --- | 12.35 | 586 | 1126.9 |
| STRUCTURE | 10 | RESVOR | .52 | 3.37 | 1375.24 | 12.53 | 540 | 1038.5 |
| XSECTION | 14 | RUNOFF | .04 | 3.75 | --- | 12.01 | 85 | 2125.0 |
| XSECTION | 14 | ADDHYD | .56 | 3.40 | --- | 12.51 | 557 | 994.6 |
| XSECTION | 15 | RUNOFF | .05 | 2.34 | --- | 12.21 | 53 | 1060.0 |
| XSECTION | 16 | RUNOFF | .08 | 2.50 | --- | 12.27 | 84 | 1050.0 |
| XSECTION | 16 | ADDHYD | .14 | 2.44 | --- | 12.24 | 137 | 978.6 |
| STRUCTURE | 16 | RESVOR | .14 | 2.44 | 1373.84 | 12.72 | 70 | 500.0 |
| XSECTION | 17 | RUNOFF | .09 | 4.12 | --- | 12.05 | 187 | 2077.8 |
| XSECTION | 17 | ADDHYD | .23 | 3.12 | --- | 12.09 | 218 | 947.8 |
| XSECTION | 18 | RUNOFF | .07 | 2.33 | --- | 12.26 | 69 | 985.7 |
| XSECTION | 18 | ADDHYD | .31 | 2.93 | --- | 12.12 | 280 | 903.2 |
| XSECTION | 19 | ADDHYD | .87 | 3.23 | --- | 12.31 | 748 | 859.8 |
| XSECTION | 20 | RUNOFF | .35 | 2.68 | --- | 12.30 | 359 | 1025.7 |
| XSECTION | 20 | ADDHYD | 1.21 | 3.07 | --- | 12.31 | 1107 | 914.9 |
| STRUCTURE | 20 | RESVOR | 1.21 | 1.12 | 1370.45 | 13.32 | 405 | 334.7 |

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
 13:36:02 PAGE 28

SUMMARY TABLE 1

 SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
 A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
 F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA (SQ MI) | RUNOFF AMOUNT (IN) | PEAK DISCHARGE | | | |
|------------------------------|----------------------------------|-----------------------------|--------------------------|-------------------|--------------|---------------|---------------|
| | | | | ELEVATION (FT) | TIME (HR) | RATE (CFS) | RATE (CSM) |

RAINFALL OF 5.25 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs.

| ALTERNATE | | 13 | STORM | 3 | | | | |
|-----------|---|--------|-------|------|-----|-------|-----|--------|
| XSECTION | 1 | RUNOFF | .12 | 3.97 | --- | 12.32 | 174 | 1450.0 |
| XSECTION | 2 | REACH | .12 | 3.97 | --- | 12.48 | 169 | 1408.3 |
| XSECTION | 2 | RUNOFF | .07 | 4.16 | --- | 12.20 | 126 | 1800.0 |
| XSECTION | 2 | ADDHYD | .20 | 4.04 | --- | 12.34 | 273 | 1365.0 |
| XSECTION | 5 | RUNOFF | .20 | 4.04 | --- | 12.43 | 257 | 1285.0 |

| | | | | | | | | |
|-----------|----|--------|------|------|---------|-------|------|--------|
| XSECTION | 6 | RUNOFF | .16 | 3.94 | --- | 12.44 | 200 | 1250.0 |
| XSECTION | 7 | ADDHYD | .35 | 3.99 | --- | 12.43 | 457 | 1305.7 |
| XSECTION | 10 | RUNOFF | .16 | 4.12 | --- | 12.24 | 262 | 1637.5 |
| XSECTION | 10 | ADDHYD | .52 | 4.04 | --- | 12.35 | 699 | 1344.2 |
| STRUCTURE | 10 | RESVOR | .52 | 4.04 | 1375.65 | 12.56 | 624 | 1200.0 |
| XSECTION | 14 | RUNOFF | .04 | 4.44 | --- | 12.01 | 100 | 2500.0 |
| XSECTION | 14 | ADDHYD | .56 | 4.07 | --- | 12.53 | 643 | 1148.2 |
| XSECTION | 15 | RUNOFF | .05 | 2.92 | --- | 12.21 | 66 | 1320.0 |
| XSECTION | 16 | RUNOFF | .08 | 3.11 | --- | 12.26 | 104 | 1300.0 |
| XSECTION | 16 | ADDHYD | .14 | 3.04 | --- | 12.24 | 170 | 1214.3 |
| STRUCTURE | 16 | RESVOR | .14 | 3.04 | 1374.23 | 12.68 | 95 | 678.6 |
| XSECTION | 17 | RUNOFF | .09 | 4.81 | --- | 12.05 | 217 | 2411.1 |
| XSECTION | 17 | ADDHYD | .23 | 3.76 | --- | 12.09 | 257 | 1117.4 |
| XSECTION | 18 | RUNOFF | .07 | 2.92 | --- | 12.26 | 86 | 1228.6 |
| XSECTION | 18 | ADDHYD | .31 | 3.56 | --- | 12.12 | 335 | 1080.6 |
| XSECTION | 19 | ADDHYD | .87 | 3.89 | --- | 12.29 | 894 | 1027.6 |
| XSECTION | 20 | RUNOFF | .35 | 3.30 | --- | 12.30 | 439 | 1254.3 |
| XSECTION | 20 | ADDHYD | 1.21 | 3.72 | --- | 12.30 | 1333 | 1101.7 |
| STRUCTURE | 20 | RESVOR | 1.21 | 1.76 | 1370.74 | 13.25 | 532 | 439.7 |

1

TR20

EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
13:36:02 PAGE 29

SUMMARY TABLE 1

SELECTED RESULTS OF STANDARD AND EXECUTIVE CONTROL IN ORDER PERFORMED.
A CHARACTER FOLLOWING THE PEAK DISCHARGE TIME AND RATE (CFS) INDICATES:
F-FLAT TOP HYDROGRAPH T-TRUNCATED HYDROGRAPH R-RISING TRUNCATED HYDROGRAPH

| XSECTION/ STRUCTURE ID | STANDARD CONTROL OPERATION | DRAINAGE AREA (SQ MI) | RUNOFF AMOUNT (IN) | PEAK DISCHARGE | | | | |
|--|----------------------------------|-----------------------------|--------------------------|-------------------|--------------|---------------|---------------|--------|
| | | | | ELEVATION (FT) | TIME (HR) | RATE (CFS) | RATE (CSM) | |
| RAINFALL OF 7.80 inches AND 24.00 hr DURATION, BEGINS AT .0 hrs. | | | | | | | | |
| ALTERNATE | 14 | STORM | 4 | | | | | |
| XSECTION | 1 | RUNOFF | .12 | 6.44 | --- | 12.32 | 277 | 2308.3 |
| XSECTION | 2 | REACH | .12 | 6.44 | --- | 12.47 | 271 | 2258.3 |
| XSECTION | 2 | RUNOFF | .07 | 6.66 | --- | 12.20 | 197 | 2814.3 |
| XSECTION | 2 | ADDHYD | .20 | 6.52 | --- | 12.34 | 436 | 2180.0 |
| XSECTION | 5 | RUNOFF | .20 | 6.52 | --- | 12.42 | 408 | 2040.0 |
| XSECTION | 6 | RUNOFF | .16 | 6.40 | --- | 12.43 | 318 | 1987.5 |
| XSECTION | 7 | ADDHYD | .35 | 6.47 | --- | 12.43 | 726 | 2074.3 |
| XSECTION | 10 | RUNOFF | .16 | 6.62 | --- | 12.24 | 417 | 2606.3 |
| XSECTION | 10 | ADDHYD | .52 | 6.52 | --- | 12.34 | 1111 | 2136.5 |
| STRUCTURE | 10 | RESVOR | .52 | 6.52 | 1377.30 | 12.63 | 909 | 1748.1 |
| XSECTION | 14 | RUNOFF | .04 | 6.95 | --- | 12.01 | 153 | 3825.0 |
| XSECTION | 14 | ADDHYD | .56 | 6.55 | --- | 12.60 | 934 | 1667.9 |
| XSECTION | 15 | RUNOFF | .05 | 5.19 | --- | 12.20 | 117 | 2340.0 |
| XSECTION | 16 | RUNOFF | .08 | 5.43 | --- | 12.26 | 180 | 2250.0 |
| XSECTION | 16 | ADDHYD | .14 | 5.34 | --- | 12.23 | 296 | 2114.3 |
| STRUCTURE | 16 | RESVOR | .14 | 5.34 | 1375.42 | 12.60 | 190 | 1357.1 |

| | | | | | |
|-----------|----|-------|-------|-------|-------|
| ALTERNATE | 11 | 218 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 405 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 532 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 1098 |
| ----- | | | | | |
| STRUCTURE | 16 | .14 | | | |
| ALTERNATE | 11 | 44 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 70 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 95 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 190 |
| ----- | | | | | |
| STRUCTURE | 10 | .52 | | | |
| ALTERNATE | 11 | 386 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 540 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 624 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 909 |
| ----- | | | | | |
| XSECTION | 1 | .12 | | | |
| ALTERNATE | 11 | 104 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 146 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 174 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 277 |
| ----- | | | | | |
| XSECTION | 2 | .20 | | | |
| ALTERNATE | 11 | 162 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 229 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 273 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 436 |
| ----- | | | | | |
| XSECTION | 5 | .20 | | | |
| ALTERNATE | 11 | 154 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 216 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 257 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 408 |
| ----- | | | | | |
| XSECTION | 6 | .16 | | | |
| ALTERNATE | 11 | 118 | ***** | ***** | ***** |
| ALTERNATE | 12 | ***** | 167 | ***** | ***** |
| ALTERNATE | 13 | ***** | ***** | 200 | ***** |
| ALTERNATE | 14 | ***** | ***** | ***** | 318 |

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
 13:36:02 PAGE 32

SUMMARY TABLE 3

STORM DISCHARGES (CFS) AT XSECTIONS AND STRUCTURES FOR ALL ALTERNATES

| XSECTION/ STRUCTURE ID | DRAINAGE AREA (SQ MI) | STORM NUMBERS | | | |
|------------------------------|-----------------------------|---------------|---|---|---|
| | | 1 | 2 | 3 | 4 |
| XSECTION | 7 | .35 | | | |

| | | | | |
|-----------|----|-------|-------|-------|
| ----- | | | | |
| ALTERNATE | 11 | 271 | ***** | ***** |
| ALTERNATE | 12 | ***** | 383 | ***** |
| ALTERNATE | 13 | ***** | ***** | 457 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 10 | .52 | | |
| ----- | | | | |
| ALTERNATE | 11 | 419 | ***** | ***** |
| ALTERNATE | 12 | ***** | 586 | ***** |
| ALTERNATE | 13 | ***** | ***** | 699 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 14 | .56 | | |
| ----- | | | | |
| ALTERNATE | 11 | 399 | ***** | ***** |
| ALTERNATE | 12 | ***** | 557 | ***** |
| ALTERNATE | 13 | ***** | ***** | 643 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 15 | .05 | | |
| ----- | | | | |
| ALTERNATE | 11 | 34 | ***** | ***** |
| ALTERNATE | 12 | ***** | 53 | ***** |
| ALTERNATE | 13 | ***** | ***** | 66 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 16 | .14 | | |
| ----- | | | | |
| ALTERNATE | 11 | 89 | ***** | ***** |
| ALTERNATE | 12 | ***** | 137 | ***** |
| ALTERNATE | 13 | ***** | ***** | 170 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 17 | .23 | | |
| ----- | | | | |
| ALTERNATE | 11 | 160 | ***** | ***** |
| ALTERNATE | 12 | ***** | 218 | ***** |
| ALTERNATE | 13 | ***** | ***** | 257 |
| ALTERNATE | 14 | ***** | ***** | ***** |
| ----- | | | | |
| XSECTION | 18 | .31 | | |
| ----- | | | | |
| ALTERNATE | 11 | 198 | ***** | ***** |
| ALTERNATE | 12 | ***** | 280 | ***** |
| ALTERNATE | 13 | ***** | ***** | 335 |

1

TR20 -----
 EASTMINSTER - BEECH LAKE - EAST BRANCH GYPSUM CREEK VERSION
 09/27/** BEECHPR2.T20 2-6'x3'20 SEP 2002 2,5,10,100-YR 24-HR STORM ZON10/01/90
 13:36:02 PAGE 33

SUMMARY TABLE 3

STORM DISCHARGES (CFS) AT XSECTIONS AND STRUCTURES FOR ALL ALTERNATES

| XSECTION/ STRUCTURE ID | DRAINAGE AREA (SQ MI) | STORM NUMBERS..... | | | |
|------------------------------|-----------------------------|--------------------|---|---|---|
| | | 1 | 2 | 3 | 4 |

XSECTION 18 .31

```

ALTERNATE 14 ***** 554
XSECTION 19 .87
-----
ALTERNATE 11 533 *****
ALTERNATE 12 ***** 748 *****
ALTERNATE 13 ***** 894 *****
ALTERNATE 14 ***** 1373

```

```

XSECTION 20 1.21
-----
ALTERNATE 11 769 *****
ALTERNATE 12 ***** 1107 *****
ALTERNATE 13 ***** 1333 *****
ALTERNATE 14 ***** 2109

```

*** WARNING - UNEXPECTED RECORD(S) ENCOUNTERED WHEN LOOKING FOR "JOB" RECORD.
 IMAGES OF FIRST 10 RECORDS IGNORED FOLLOWS: ***

END OF 1 JOBS IN THIS RUN
 1

SCS TR-20, VERSION 10/01/90
 FILES

INPUT = beechpr2.t20
 OUTPUT = beechpr2.out , DATED 09/27/**,13:36:02

FILES GENERATED - DATED 09/27/**,13:36:02

NONE!

*** TR-20 RUN COMPLETED ***

Appendix H
Pipe Sizing Calculations

9/8/03

DRAINAGE ANALYSIS SUMMARY
Waterfront Second Addition

| Area ID | Area ac | Accum. Area ac | C2 | C5 | C10 | C100 | Elev Max | Elev Min | Flow Length | Tc100 Calc | Tc2 min | Tc5 min | Tc10 min | Tc100 min | I2 in/hr | I5 in/hr | I10 in/hr | I100 in/hr | Q2 cfs | Q5 cfs | Q10 cfs | Q100 cfs | Q3 | | |
|---------|------------|-------------------|------|------|------|------|-------------|-------------|----------------|---------------|------------|------------|-------------|--------------|-------------|-------------|--------------|---------------|-----------|-----------|------------|-------------|------------------|-----------------------------|-----------------|
| | | | | | | | | | | | | | | | | | | | | | | | Inlet Size ft | Pipe Size Min Slope in % | Design Storm |
| O | 2.6 | | 0.68 | 0.69 | 0.73 | 0.80 | 81.0 | 76.0 | 550 | 13.07 | 18 | 18 | 16 | 15 | 3.51 | 4.31 | 5.08 | 7.37 | 6.21 | 7.73 | 9.64 | 15.33 | 24 | 0.21% | 5 |
| P | 5.3 | | 0.68 | 0.69 | 0.73 | 0.80 | 74.5 | 72.5 | 400 | 13.61 | 19 | 19 | 17 | 15 | 3.42 | 4.20 | 5.08 | 7.37 | 12.42 | 15.48 | 19.80 | 31.48 | 30 | 0.16% | 5 |
| Q | 5.2 | | 0.68 | 0.69 | 0.73 | 0.80 | 80.5 | 72.5 | 600 | 12.02 | 17 | 16 | 15 | 15 | 3.72 | 4.43 | 5.22 | 7.37 | 13.20 | 15.96 | 19.89 | 30.78 | 30 | 0.16% | 5 |
| R | 0.5 | | 0.68 | 0.69 | 0.73 | 0.80 | 73.5 | 72.0 | 200 | 8.41 | 15 | 15 | 15 | 15 | 3.83 | 4.56 | 5.22 | 7.37 | 1.30 | 1.57 | 1.91 | 2.95 | 12 | 0.40% | 5 |
| Q+R | 5.7 | | 0.68 | 0.69 | 0.73 | 0.80 | 80.5 | 72.0 | 660 | 12.75 | 18 | 17 | 16 | 15 | 3.61 | 4.31 | 5.22 | 7.37 | 14.04 | 17.01 | 21.80 | 33.73 | 36 | 0.12% | 5 |
| S | 0.5 | | 0.68 | 0.69 | 0.73 | 0.80 | 75.0 | 71.5 | 250 | 7.63 | 15 | 15 | 15 | 15 | 3.83 | 4.56 | 5.22 | 7.37 | 1.38 | 1.67 | 2.02 | 3.12 | 12 | 0.40% | 5 |
| Q+R+S | 6.3 | | 0.68 | 0.69 | 0.73 | 0.80 | 80.5 | 71.5 | 710 | 13.30 | 19 | 18 | 16 | 15 | 3.51 | 4.20 | 5.08 | 7.37 | 14.92 | 18.11 | 23.18 | 36.85 | 36 | 0.12% | 5 |
| T | 3.7 | | 0.68 | 0.69 | 0.73 | 0.80 | 75.0 | 72.5 | 500 | 15.21 | 21 | 21 | 19 | 15 | 3.25 | 4.00 | 4.83 | 7.37 | 8.27 | 10.32 | 13.19 | 22.05 | 24 | 0.21% | 5 |
| Q+R+S+T | 10.0 | | 0.68 | 0.69 | 0.73 | 0.80 | 80.5 | 72.5 | 1100 | 19.15 | 27 | 26 | 24 | 19 | 2.90 | 3.50 | 4.31 | 6.68 | 19.70 | 24.13 | 31.43 | 53.99 | 42 | 0.12% | 5 |
| U | 0.2 | | 0.68 | 0.69 | 0.73 | 0.80 | 75.5 | 73.5 | 200 | 7.64 | 15 | 15 | 15 | 15 | 3.83 | 4.56 | 5.22 | 7.37 | 0.63 | 0.76 | 0.91 | 1.42 | 12 | 0.40% | 5 |
| V | 0.3 | | 0.68 | 0.69 | 0.73 | 0.80 | 75.5 | 74.0 | 250.0 | 10.12 | 15 | 15 | 15 | 15 | 3.83 | 4.56 | 5.22 | 7.37 | 0.81 | 0.98 | 1.18 | 1.83 | 12 | 0.40% | 5 |
| O+V | 2.9 | | 0.68 | 0.69 | 0.73 | 0.80 | 81.0 | 74.0 | 600 | 12.56 | 18 | 17 | 15 | 15 | 3.61 | 4.31 | 5.22 | 7.37 | 7.14 | 8.65 | 11.09 | 17.16 | 24 | 0.21% | 5 |
| O+V+U | 3.2 | | 0.68 | 0.69 | 0.73 | 0.80 | 81.0 | 73.5 | 650.0 | 13.13 | 18 | 18 | 16 | 15 | 3.51 | 4.31 | 5.08 | 7.37 | 7.52 | 9.37 | 11.68 | 18.57 | 24 | 0.21% | 5 |
| O+V+U+P | 8.5 | | 0.68 | 0.69 | 0.73 | 0.80 | 81.0 | 72.5 | 1100 | 19.52 | 27 | 27 | 24 | 20 | 2.84 | 3.50 | 4.22 | 6.68 | 16.40 | 20.50 | 26.15 | 45.37 | 36 | 0.12% | 5 |
| 2A | 4.4 | | 0.68 | 0.69 | 0.73 | 0.80 | 85.0 | 76.0 | 750.0 | 13.92 | 19 | 19 | 17 | 15 | 3.42 | 4.10 | 4.95 | 7.37 | 10.12 | 12.31 | 15.72 | 25.65 | 30 | 0.16% | 5 |

