

STAFF REPORT
(One-Step Final Plat)

CASE NUMBER: SUB 2000-20 -- BAHAI' ADDITION

OWNER/APPLICANT: The Spiritual Assembly of the Bahai's of Wichita, Attn: Richard Vore, 4926 Port West Ct., Wichita, KS 67204

SURVEYOR/ENGINEER: Savoy, Ruggles and Bohm, 924 N. Main, Wichita, KS 67203

LOCATION: West side of Amidon, North of 32nd St. North

SITE SIZE: .87 Acres

NUMBER OF LOTS

Residential:	1
Office:	
Commercial:	
Industrial:	
Total:	1


Need to ext. S.S.

MINIMUM LOT AREA: .84 Acres

CURRENT ZONING: SF-6, Single-Family Residential

PROPOSED ZONING: Same

VICINITY MAP



Note: This is a replat of a portion of Lot 12, Russell Tracts Addition.

STAFF COMMENTS:

- A. Municipal services appear to be available to serve the site. City Engineering needs to comment on the need for any guarantees or easements.
- B. If improvements are guaranteed by petition, a notarized certificate listing the petitions shall be submitted to the Planning department for recording.
- C. City Engineering needs to comment on the status of the applicant's drainage plan.
- D. The applicant is reminded that a platting binder is required with the final plat. Approval of this plat will be subject to submittal of this binder and any relevant conditions found by such a review.
- E. The platting text shall include language that a drainage plan has been developed for the plat and that all drainage easements, rights-of-way, or reserves shall remain at established grades or as modified with the approval of the applicable City or County Engineer, and unobstructed to allow for the conveyance of stormwater.
- F. The applicant shall install or guarantee the installation of all utilities and facilities which are applicable and described in Article 8 of the MAPC Subdivision Regulations. (Water service and fire hydrants required by Article 8 for fire protection shall be as per the direction and approval of the Chief of the Fire Department.)
- G. The applicant's engineer is advised that the Register of Deeds is requiring the name(s) of the notary public, who acknowledges the signatures on this plat, to be printed beneath the notary's signature.
- H. To receive mail delivery without delay, and to avoid unnecessary expense, the applicant is advised of the necessity to meet with the U.S. Postal Service Growth Management Coordinator (Phone 316-729-0102) prior to development of the plat so that the type of delivery, and the tentative mailbox locations can be determined.
- I. The applicant is advised that various State and Federal requirements (specifically but not limited to the Army Corps of Engineers, Kanopolis Project Office, Rt. 1, Box 317, Valley Center, KS 67147) for the control of soil and wind erosion and the protection of wetlands may impact how this site can be developed. It is the applicant's responsibility to contact all appropriate agencies to determine any such requirements.
- J. The owner of the subdivision should be aware of the fact that the development of any subdivision greater than five (5) acres in size may require an NPDES Storm Water Discharge Permit from the Kansas Department of Health and Environment in Topeka. Further, on all construction sites, the City of Wichita requires that best management practices be used to reduce pollutant loadings in storm water runoffs.
- K. Perimeter closure computations shall be submitted with the final plat tracing.
- L. Recording of the plat within thirty (30) days after approval by the City Council and/or County Commission.
- M. The representatives from the utility companies should be prepared to comment on the need for any additional utility easements to be platted on this property.

SUB 2000-20 -- One-Step Final Plat of BAHAI ADDITION
April 6, 2000 - Page 3

- N. The applicant is reminded that a disk shall be submitted with the final plat tracing to the Planning Department detailing this plat in digital format in AutoCAD. This will be used by the City and County GIS Department.



924 NORTH MAIN
WICHITA, KANSAS 67203
<http://www.feist.com/~srb>

316-264-8008
FAX 264-4621
srb@feist.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

April 4, 2000

Ms. Vicky Huang
City of Wichita
Engineering – 8th Flor
455 N. Main
Wichita, KS 67202

Dear Ms. Huang,

Enclosed, please find the drainage plan for Baha'I Addition, Wichita, Sedgwick County, Kansas.
Please review this plan and advise.

If you have any questions or comments, please do not hesitate to contact me.

Regards,

Christopher M. Bohm, P.E.
Encl.

BOUNDARY CLOSURE:
BAHA'I ADDITION
WICHITA, SEDGWICK COUNTY, KANSAS

North: 19588.182	East : 20000.000
Line Course: N 89-55-30 W Length: 317.48	
North: 19588.598	East : 19682.520
Line Course: N 00-02-30 E Length: 137.23	
North: 19725.828	East : 19682.620
Line Course: S 89-55-30 E Length: 317.38	
North: 19725.412	East : 20000.000
Line Course: S 00-00-00 W Length: 137.23	
North: 19588.182	East : 20000.000

Perimeter: 909.31 Area: 43,560 sq.ft. 1.00 acres

Mapcheck Closure - (Uses listed courses and chords)
Error Closure: 0.000 Course: N 65-03-35 W
Error North: 0.0001 East : -0.0002
Precision 1: 909,320,000.00