

STAFF REPORT
(One-Step Final Plat)

CASE NUMBER: S/D 99-68 -- MAPLE STREET MINI-MALL ADDITION

OWNER/APPLICANT: Donna L. Schroeder, 641 N. Woodlawn, #53, Wichita, KS 67208;
Gregg A. Vance (contract purchaser), 1317 Pine Grove Ct.,
Wichita, KS 67212

SURVEYOR/ENGINEER: Reiss & Goodness Engineers, 2160 W. 21st Street, Wichita, KS
67203

LOCATION: North side of Maple, east of West Street

SITE SIZE: .52 Acres

NUMBER OF LOTS

Residential: _____
Office: _____
Commercial: 1
Industrial: _____
Total: 1


10' x E
Knight St Contingent Red?

MINIMUM LOT AREA: 22,800 Sq. Ft.

CURRENT ZONING: LC, Limited Commercial

PROPOSED ZONING: Same

VICINITY MAP



Note: This is an unplatted site located within the City.

STAFF COMMENTS:

- A. Existing municipal services appear to be available to serve this site. City Engineering needs to verify if any guarantees are required.
- B. If improvements are guaranteed by petition, a notarized certificate listing the petitions shall be submitted to the Planning department for recording.
- C. City Engineering needs to comment on the status of the applicant's drainage plan.
- D. Traffic Engineering needs to comment on the access controls. The plat proposes two access openings along Maple. Distances should be shown for all segments of access control. The plat's text shall note that the access controls are being dedicated to the City of Wichita.
- E. The distance from the tie point to the plat shall be indicated.
- F. The MAPC signature block should be revised to reference "Frank Garofalo" as the MAPC Chairman.
- G. The plat's text shall include language that a drainage plan has been developed for the plat and that all drainage easements, rights-of-way, or reserves shall remain at established grades or as modified with the approval of the applicable City or County Engineer, and unobstructed to allow for the conveyance of stormwater.
- H. The applicant shall install or guarantee the installation of all utilities and facilities which are applicable and described in Article 8 of the MAPC Subdivision Regulations. (Water service and fire hydrants required by Article 8 for fire protection shall be as per the direction and approval of the Chief of the Fire Department.)
- I. The applicant's engineer is advised that the Register of Deeds is requiring the name(s) of the notary public, who acknowledges the signatures on this plat, to be printed beneath the notary's signature.
- J. To receive mail delivery without delay, and to avoid unnecessary expense, the applicant is advised of the necessity to meet with the U.S. Postal Service Growth Management Coordinator (phone 316-729-0102) prior to development of the plat so that the type of delivery, and the tentative mailbox locations can be determined.
- K. The applicant is advised that various State and Federal requirements [specifically but not limited to the Army Corps of Engineers, Kanopolis Project Office, Rt. 1, Box 317, Valley Center, KS 67147] for the control of soil and wind erosion and the protection of wetlands may impact how this site can be developed. It is the applicant's responsibility to contact all appropriate agencies to determine any such requirements.

- L. The owner of the subdivision should be aware of the fact that the development of any subdivision greater than five (5) acres in size may require an NPDES Storm Water Discharge Permit from the Kansas Department of Health and Environment in Topeka. Further, on all construction sites, the City of Wichita requires that best management practices be used to reduce pollutant loadings in storm water runoffs.
- M. Perimeter closure computations shall be submitted with the final plat tracing.
- N. Recording of the plat within thirty (30) days after approval by the City Council and/or County Commission.
- O. The representatives from the utility companies should be prepared to comment on the need for any additional utility easements to be platted on this property.
- P. The applicant is reminded that a disk shall be submitted with the final plat tracing to the Planning Department detailing this plat in digital format in Release 13 version of AutoCAD. This will be used by the City and County GIS Department.

MAPLE STREET MINI-MALL ADDITION
CLOSURE COMPUTATIONS

Beginning Point		<u>Northing</u>	<u>Easting</u>
		500.0000	500.0000
<u>Direction</u>	<u>Distance</u>		
N 90°00'00" E	151.83	500.0000	651.8300
N 0°45'48" E	149.88	649.8667	653.8268
N 90°00'00" W	151.83	649.8667	501.9968
S 0°45'48" W	149.88	500.0000	500.0000
Closure 0°00'00"	0.000		
Perimeter	603.42 Feet	0.0000 N	0.0000 E