

October 12, 2009

City Hall  
City Engineer's Office  
455 N. Main, 8<sup>th</sup> Floor  
Wichita, KS 67202

OCT 15 2009


Attention: Scott Lindebak, P.E.

Reference: Center for Health and Wellness *addition*  
2707 E. 21<sup>st</sup> Street

The purpose of this letter is to provide you with information regarding the referenced project near 21<sup>st</sup> Street North and Grove in Wichita, Kansas. The site is currently undeveloped and generally drains from east to west. All runoff leaves the site along the south property line and eventually flows to the intersection of Stadium and Grove, which frequently floods. We are proposing to expand the current facility to the west with the required parking spaces (See the attached plan sheets). We intend to construct a detention area on the west end of the property to account for the increase in runoff. We will extend the existing 12" RCP from 21<sup>st</sup> and Grove to our detention area. This pipe is the control for our detention basin and can only carry 3 cfs, assuming that the pipe is running full. We are providing enough detention to detain the 100-Yr event with 1 foot of freeboard on our berm, assuming that 3 cfs is flowing through the 12" RCP continuously during the storm event. I have included a HEC-1 printout and other calculations for your review. As you can see, we will decrease runoff leaving the site and help reduce storm water that flows to the intersection of Stadium and Grove.

If you have any questions, please feel free to contact me by phone at (316) 778-2215 or e-mail at [bbarkus@awirr.com](mailto:bbarkus@awirr.com). Thank you for your time and consideration of this work.

Sincerely,



Bryce L. Barkus, P.E.

Cc: Cheri Hulse, Gordon &amp; Associates

Project: Center for Health & Wellness  
 Date: 10/9/2009  
 Prep. By: BLB

Manual Input

**BASIN**

Total Area 1.40 Acres

Soil Group	A (% of Total Area)	B (% of Total Area)	C (% of Total Area)	D (% of Total Area)	Total
	0%	0%	0%	100%	100%
Acres	0.00	0.00	0.00	1.40	1.40

Land Use	Commercial (% of Total Area)	Industrial (% of Total Area)	Multi-Family (% of Total Area)	Public (% of Total Area)	Single Family (% of Total Area)	Vacant/Agriculture (% of Total Area)
Existing	0%	0%	0%	100%	0%	0%
Acres	0.00	0.00	0.00	1.40	0.00	0.00
Future	100%	0%	0%	0%	0%	0%
Acres	1.40	0.00	0.00	0.00	0.00	0.00

Length of Flow	Existing		Future	
	715 ft	715 ft		
Slope	2.80 %	2.80 %		
Waterflow Desc	bare / short grass	pavement/grass		
Avg Velocity	2.50 ft/sec	4.50 ft/sec		
Tc	0.08 hours	0.04 hours		

5 min <= Tc <= 24 hrs

Runoff Coefficients \* Used Soil Group D To Be Conservative

Return Period (Years)	Commercial	Industrial	Multi-Family	Public	Single Family	Vacant/Agriculture
2	0.68	0.68	0.70	0.49	0.50	0.54
5	0.69	0.69	0.73	0.51	0.54	0.56
10	0.73	0.73	0.79	0.56	0.62	0.61
25	0.75	0.75	0.81	0.59	0.66	0.64
50	0.77	0.77	0.83	0.62	0.70	0.67
100	0.80	0.80	0.86	0.66	0.76	0.70

**Existing Conditions**

Return Period (Years)	Runoff Coefficient *	Rainfall Intensity (in/hr)	Area (Acres)	Runoff (cfs)
2	0.49	5.64	1.40	3.87
5	0.51	6.64	1.40	4.74
10	0.56	7.38	1.40	5.79
25	0.59	8.48	1.40	7.00
50	0.62	9.34	1.40	8.11
100	0.66	10.20	1.40	9.42

**Future Conditions**

Return Period (Years)	Runoff Coefficient *	Rainfall Intensity (in/hr)	Area (Acres)	Runoff (cfs)
2	0.68	5.64	1.40	5.37
5	0.69	6.64	1.40	6.41
10	0.73	7.38	1.40	7.54
25	0.75	8.48	1.40	8.90
50	0.77	9.34	1.40	10.07
100	0.80	10.20	1.40	11.42

# MCCA Construction, Inc.

12469 SW 15th Benton, KS 67017 PH: (316) 778-2268 FAX: (316) 778-1204

PROJECT: Center for Health & Wellness

DATE: 9-2-09

ITEM: Total Runoff from Site Improvements

BY: BLB

Total Runoff for 6hr Storm (Proposed Condition)

CN = 95 (Proposed Condition)  
CN = 80 (Existing Condition)

$$P_5 = (0.55 \text{ in/hr})(6 \text{ hr}) = 3.3 \text{ in}$$

$$P_{100} = (0.98 \text{ in/hr})(6 \text{ hr}) = 5.9 \text{ in}$$

$$S = \frac{1000}{\text{CN}} - 10 = \frac{1000}{95} - 10 = 0.526$$

$$P_{e5} = \frac{(P - 0.2S)^2}{P + 0.8S} = \frac{(3.3 - 0.2(0.526))^2}{3.3 + 0.8(0.526)} = 2.74 \text{ in}$$

$$P_{e100} = \frac{(5.9 - 0.2(0.526))^2}{5.9 + 0.8(0.526)} = 5.31 \text{ in}$$

Total Runoff for 6hr Storm (Existing Condition)

$$P_5 = 3.3 \text{ in}$$

$$P_{100} = 5.9 \text{ in}$$

$$S = \frac{1000}{80} - 10 = 2.50$$

$$P_{e5} = \frac{(3.3 - 0.2(2.50))^2}{3.3 + 0.8(2.50)} = 1.48 \text{ in}$$

$$P_{e100} = \frac{(5.9 - 0.2(2.50))^2}{5.9 + 0.8(2.50)} = 3.69 \text{ in}$$

Increase in Runoff due to development

$$5 \text{ Yr Storm} = 2.74 - 1.48 = 1.26 \text{ in}$$

$$100 \text{ Yr Storm} = 5.31 - 3.69 = 1.62 \text{ in}$$

Detention required on site

$$(1.62 \text{ in}) \left( \frac{1 \text{ ft}}{12 \text{ in}} \right) (60,984 \text{ sq ft}) = 8,232.84 \text{ cf}$$

Actual Storage Provided = 8,802 cf at Elevation of Top of Berm 1325.50

10-9-09 BLB

\*\*\*\*\*  
 \* U.S. ARMY CORPS OF ENGINEERS  
 \* HYDROLOGIC ENGINEERING CENTER  
 \* 609 SECOND STREET  
 \* DAVIS, CALIFORNIA 95616  
 \* (916) 756-1104  
 \* \*\*\*\*\*

\*\*\*\*\*  
 \* FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 \* JUN 1998  
 \* VERSION 4.1  
 \* RUN DATE 09OCT09 TIME 08:16:28  
 \* \*\*\*\*\*

```

X X XXXXXXXX XXXXX X
X X X X XXXX X
X X X X X X
XXXXXXXX XXXX
X X X X X X
X X X X X X
X X XXXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.  
 THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.  
 THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION  
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,  
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION  
 KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

HEC-1 INPUT

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

1 Center for Health & Wellness - Wichita, Kansas  
 2 Proposed Conditions through Detention Pond  
 3 5 & 100-YR 24-HR STORM EVENTS  
 4 ID By: BLB Date: 10/09/09

\*DIAGRAM

\*  
 IT 15 02JUL08 1200 0 06JUL08 2000  
 IN 15 02JUL08 1200  
 IO 0 5  
 JR PREC 4.56 7.68  
 \*  
 \*

\*\*\* LIST \*\*\*  
 \*\*\* FREE \*\*\*

KKProposed Conditions

9	KKProposed Conditions																			
10	KO	5																		
11	BA	0.002																		
12	PB	1.00																		
13	PC	0.000	0.003	0.006	0.008	0.011	0.014	0.017	0.019	0.022	0.025									
14	PC	0.029	0.032	0.035	0.038	0.042	0.045	0.048	0.052	0.056	0.060									

LINE	PC	0.064	0.068	0.072	0.076	0.080	0.085	0.090	0.095	0.100	0.105
15	PC	0.110	0.115	0.120	0.127	0.134	0.140	0.147	0.155	0.163	0.172
16	PC	0.181	0.193	0.204	0.220	0.235	0.259	0.283	0.387	0.663	0.699
17	PC	0.735	0.754	0.772	0.786	0.799	0.810	0.820	0.828	0.835	0.843
18	PC	0.850	0.858	0.865	0.873	0.880	0.885	0.889	0.894	0.898	0.903
19	PC	0.907	0.912	0.916	0.921	0.925	0.929	0.934	0.938	0.943	0.947
20	PC	0.952	0.955	0.958	0.961	0.964	0.967	0.970	0.973	0.976	0.979
21	PC	0.982	0.985	0.988	0.991	0.994	0.997	1.000			
22	LS	0	94	0							
23	UD	0.040									
24	*										
25	*										
26	*										
27	KK	POND	Control	Structure = 2'x2'	Drop Inlet Top Elevation at 1321.00						
28	KO	5									
29	RS	1	ELEV	1321.0							
30	SA	0.00	0.12								
31	SE	1321.0	1325.5								
32	SQ	0.0	2.8								
33	SE	1321.0	1321.25	1325.50							
34	*										
35	*										
36	*										
37	ZZ										

1 INPUT LINE (V) ROUTING (--->) DIVERSION OR PUMP FLOW  
 NO. (.) CONNECTOR (<---) RETURN OF DIVERTED OR PUMPED FLOW

9 Proposed V  
 25 POND V

(\*\*\*) RUNOFF ALSO COMPUTED AT THIS LOCATION  
 \*\*\*\*\*  
 \* FLOOD HYDROGRAPH PACKAGE (HEC-1) \*  
 \* JUN 1998 \*  
 \* VERSION 4.1 \*  
 \* RUN DATE 09OCT09 TIME 08:16:28 \*  
 \*\*\*\*\*

\*\*\*\*\*  
 \* U.S. ARMY CORPS OF ENGINEERS \*  
 \* HYDROLOGIC ENGINEERING CENTER \*  
 \* 609 SECOND STREET \*  
 \* DAVIS, CALIFORNIA 95616 \*  
 \* (916) 756-1104 \*  
 \*\*\*\*\*

7 IO OUTPUT CONTROL VARIABLES  
 IPRINT 0 PRINT CONTROL  
 IPLOT 5 PLOT CONTROL  
 Center for Health & Wellness - Wichita, Kansas  
 Proposed Conditions through Detention Pond  
 5 & 100-YR 24-HR STORM EVENTS  
 By: BLB Date: 10/09/09  
 Page 2

QSCAL 0. HYDROGRAPH PLOT SCALE

IT HYDROGRAPH TIME DATA 15 MINUTES IN COMPUTATION INTERVAL  
 NMIN 2JUL 8 STARTING DATE  
 IDATE 1200 STARTING TIME  
 ITIME 417 NUMBER OF HYDROGRAPH ORDINATES  
 NQ 6JUL 8 ENDING DATE  
 NDDATE 2000 ENDING TIME  
 NDTIME 19 CENTURY MARK  
 ICENT

COMPUTATION INTERVAL .25 HOURS  
 TOTAL TIME BASE 104.00 HOURS

ENGLISH UNITS  
 DRAINAGE AREA SQUARE MILES  
 PRECIPITATION DEPTH INCHES  
 LENGTH, ELEVATION FEET  
 FLOW CUBIC FEET PER SECOND  
 STORAGE VOLUME ACRE-Feet  
 SURFACE AREA ACRES  
 TEMPERATURE DEGREES FAHRENHEIT

JP MULTI-PLAN OPTION 1 NUMBER OF PLANS  
 NPLAN

JR MULTI-RATIO OPTION  
 RATIOS OF PRECIPITATION  
 4.56 7.68

\*\*\* \*\*

\*\*\*\*\*  
 \* Proposed \*  
 \*\*\*\*\*

9 KK Conditions

10 KO OUTPUT CONTROL VARIABLES  
 IPRNT 5 PRINT CONTROL  
 IPLOT 5 PLOT CONTROL  
 QSCAL 0. HYDROGRAPH PLOT SCALE

\*\*\* \*\*

\*\*\*\*\*  
 \* POND \*  
 \*\*\*\*\*

25 KK

26 KO OUTPUT CONTROL VARIABLES  
 IPRNT 5 PRINT CONTROL  
 IPLOT 5 PLOT CONTROL  
 QSCAL 0. HYDROGRAPH PLOT SCALE

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE MILES  
 TIME TO PEAK IN HOURS

RATIOS APPLIED TO PRECIPITATION

RATIO 1 4.56  
 RATIO 2 7.68

OPERATION STATION AREA PLAN

+ HYDROGRAPH AT Proposed .00 1 FLOW TIME 5.9. 12.00 12.00

+ ROUTED TO POND .00 1 FLOW TIME 3.3. 12.00 11.75

\*\* PEAK STAGES IN FEET \*\*  
 1 STAGE 1322.16 1324.52  
 TIME 12.25 12.25

\*\*\* NORMAL END OF HEC-1 \*\*\*

DATE: 09-30-09

Architectural Innovations, LLC  
1271 E. Kenda, Suite 200  
P.O. Box 548,933  
Channahon, IL 61023  
www.a-i-innov.com  
Phone: 815-421-1100  
Fax: 815-421-1101



project no. 0819




CONSTRUCTION DOCUMENTS - 75%  
ADDITION AND ALTERATIONS TO:  
CENTER FOR HEALTH AND WELLNESS  
2707 E. 21ST STREET  
WICHITA, KANSAS

sheet

CV 1.0  
SITE PLAN

Ameritrack  
W.I.S.T.  
13469 SW 18th  
Benton, MS 39217  
O: 316-778-2233  
F: 316-778-1204  
Ameritrack West, Inc.

PRELIMINARY  
NOT FOR CONSTRUCTION



21st St. N.

Stadium Drive

Grove Ave.



