


State of Kansas) SS We, Baughman Company, P.A., Surveyors Sedgwick County and state do hereby certify that we have surveyed and plotted "NORTHGATE 4TH ADDITION", Wichita, Sedgwick County, Kansas and that the accompanying plat is a true and correct exhibit of the property surveyed, described as and being a replat of all of Lots 1, 2, 3, 4, 5, 6, 7, 8, 9 and 10, Block A, TOGETHER with all of Lot 21, 22, 23, 24, 25, 26, and 27, Block B, TOGETHER with all of Lot 1, Block D, TOGETHER with all of Reserves "A", "C", and "D", TOGETHER with all of Edwards Ct, Edwards St, and the most easterly 55th Ct N, TOGETHER with that part of Reserve "B" described as follows: Beginning at the northwest corner of Lot 21 in said Block B; thence S00°02'41"W coincident with the west line of said Lot 21, 17.73 feet to a point on a non-tangent curve to the right; thence westerly and northwesterly coincident with said curve, through a central angle of 56°11'01" and having a radius of 50.00 feet, an arc distance of 49.03 feet, (having a chord length of 47.09 feet bearing N67°02'06"W), to the intersection with the south right-of-way line of W 55th St N; thence S89°09'05"E coincident with the south right-of-way line of said W 55th St N, 43.38 feet to the point of beginning, and TOGETHER with that part of said W 55th St N lying west of and abutting the following described line: Beginning at the northeast corner of Lot 21 in said Block B; thence N00°02'41"E coincident with the northerly prolongation of the east line of said Lot 21, 64.01 feet to the intersection with the north right-of-way line of said W 55th St N, and for a point of termination, (said point of termination being N89°09'05"W, 23.35 feet from the southeast corner of Lot 21 in said Block A), and lying east of and abutting the following described curve: Commencing at the northwest corner of Lot 21 in said Block B; thence N89°09'05"W coincident with the south right-of-way line of said W 55th St N, 43.38 feet to a point on a non-tangent curve to the right; thence northwesterly, northerly, and northeasterly coincident with said curve, through a central angle of 79°35'01" and having a radius of 50.00 feet, an arc distance of 69.45 feet, (having a chord length of 64.00 feet bearing N00°02'41"E), to the intersection with the north right-of-way line of said W 55th St N, and for a point of termination, (said point of termination being N89°09'05"W, 6.84 feet from the southeast corner of said Reserve "D"), all of the above being platted and dedicated in Northgate 3rd Addition, Wichita, Sedgwick County, Kansas, TOGETHER with a replat of all of Lots 1, 2, 3, 4, 5, 6, 7, 8, and 9, Block A, TOGETHER with all of Reserve "A", and TOGETHER with 55th St N, all as platted and dedicated in Northgate 2nd Addition, Wichita, Sedgwick County, Kansas, EXCEPT that part of said 55th St N lying east of and abutting the east line of that part of said 55th St N replatted and dedicated in said Northgate 3rd Addition, and TOGETHER with the south 135.00 feet of the South Seven (7) Acres of the Northeast Quarter of the Northeast Quarter of the Southeast Quarter (NE1/4 NE1/4 SE1/4) except the East 50 feet for road, all in Section 13, Township Twenty-six (26) Range One (1) West of the Sixth Principal Meridian, Sedgwick County, Kansas.

Existing public easements, building setback lines, dedications, and access controls, if any, being vacated by virtue of K.S.A. 12-512b, as amended. All being situated in the Southeast Quarter of Section 13, Township 26 South, Range 1 West of the Sixth Principal Meridian, Sedgwick County, Kansas. Baughman Company, P.A.



Michael G. Conroy, P.S. #971 Surveyor

NORTHGATE 4TH ADDITION WICHITA, SEDGWICK COUNTY, KANSAS

Know all men by these presents that we, the undersigned, have caused the land in the surveyors certificate to be platted into Lots, Blocks, Streets, and Reserves, to be known as "NORTHGATE 4TH ADDITION", Wichita, Sedgwick County, Kansas. The utility easements are hereby granted to the public as indicated for the construction and maintenance of all public utilities. The drainage easements are hereby granted to the public as indicated for drainage purposes. The drainage and utility easements are hereby granted to the public as indicated for drainage purposes and for the construction and maintenance of all public utilities. No private drainage systems shall be located within public drainage easements unless a Residential Drainage Relief Permit is obtained from the City of Wichita Public Works & Utilities Department. The water line easement is hereby granted to the public as indicated for the construction and maintenance of public water lines and related appurtenances. The streets are hereby dedicated to and for the use of the public. Reserve "A" is hereby reserved for open space, an emergency access drive as confined to easement, a gate or bollards, pedestrian access, drainage purposes, water lines and related appurtenances as confined to easement, and utilities as confined to easement. Reserve "B" is hereby reserved for open space, landscaping, berms, sidewalks, recreational areas including swimming pools and related facilities, parking, gazebos, drainage purposes, and utilities as confined to easements. Reserve "C" is hereby reserved for open space, landscaping, berms, lakes, drainage purposes, and utilities as confined to easements. Reserves "A", "B", and "C", shall be owned and maintained by the homeowners association for the addition. FEMA floodplain and regulatory roadway boundaries are subject to periodic change and such change may affect the intended land use within the subdivision. All abutters rights of access shall be as depicted on the face of the plat and are hereby granted to the City of Wichita, Kansas. The Minimum Building Pad Elevations for the lowest opening to the structures shall be as indicated on the face of the plat.

R&R Realty, LLC, a Kansas limited liability company


Jay W. Russell, Manager

Kevin M. Mullen, President of Ritchie Associates, Inc.

State of Kansas) SS The foregoing instrument acknowledged before me, this 28th day of July, 2020, by Jay W. Russell, Manager of R&R Realty, LLC, a Kansas limited liability company, on behalf of the limited liability company.

LUNETTE A. SAUBER, Notary Public

My App't. Exp. 09-20-22



State of Kansas) SS The foregoing instrument acknowledged before me, this 5th day of August, 2020, by Kevin M. Mullen, President of Ritchie Associates, Inc., as Manager of R&R Realty, LLC, a Kansas limited liability company, on behalf of the limited liability company.

Heidi Jeffries, Notary Public

My App't. Exp. 4-14-2023






We, the undersigned holders of mortgages on the above described property, do hereby consent to this plat of "NORTHGATE 4TH ADDITION", Wichita, Sedgwick County, Kansas.

Legacy Bank

State of Kansas) SS The foregoing instrument acknowledged before me, this 5th day of August, 2020, by REX REYNOLDS, SVP of Legacy Bank, on behalf of the bank.

LUNETTE A. SAUBER, Notary Public

My App't. Exp. 09-20-22



NOTE: ALL LOTS WITHIN NORTHGATE 4TH ADDITION SHALL HAVE A 5 FOOT INTERIOR SIDEYARD SETBACK.

- = #4 REBAR W/ "BAUGHMAN" CAP (SET)
 - = #4 REBAR W/ "BAUGHMAN" CAP (FOUND)
 - = #6 REBAR W/ ALLEGIBLE YELLOW CAP (FOUND) (ORIGIN UNKNOWN)
 - × = CHISELED CROSS (FOUND) (ORIGIN UNKNOWN)
- (M) = MEASURED
(D) = DESCRIBED
(P) = PLATTED
(CM) = CALCULATED FROM DESCRIBED INFO.
(CD) = CALCULATED FROM DESCRIBED INFO.
(CF) = CALCULATED FROM PLATTED INFO.

MINIMUM BUILDING PAD ELEVATIONS FOR LOWEST OPENING TO THE STRUCTURES		
LOT	BLOCK	ELEVATION NAVD88
12-20	A	1,336.0
3-7	B	1,335.8

BENCHMARK:
BENCHMARK #1
CHISELED SQUARE, CENTER OF STORM WATER SEWER VAULT, WEST SIDE OF MERIDIAN, 22.4' S & 30.5' E OF THE SE COR., LOT 1, BLOCK D, NORTHGATE 4TH ADDITION. ELEV. = 1,334.49 (NAVD88)
BENCHMARK #2
BENCHMARK DISK, TOP OF CURB, 14.8' W & 0.7' N OF THE SW COR., LOT 10, BLOCK D, NORTHGATE 4TH ADDITION. ELEV. = 1,337.35 (NAVD 88)

This plat of "NORTHGATE 4TH ADDITION", Wichita, Sedgwick County, Kansas has been submitted to and approved by the Wichita-Sedgwick County Metropolitan Area Planning Commission, Wichita, Kansas.


Dated this 4th day of August, 2020, Wichita-Sedgwick County Metropolitan Area Planning Commission

Charles A. Warren, Chair
Scott A. Wadle, Secretary

This plat approved and all dedications shown hereon accepted by the City Council of the City of Wichita, Kansas, this 4th day of August, 2020.

Brandon J. Whipple, Mayor, City of Wichita
Karen Sublett, City Clerk

Reviewed in accordance with K.S.A. 58-2005 on this 4th day of August, 2020.



Tricia L. Robello, P.S. #1246, Deputy County Surveyor, Sedgwick County, Kansas

Entered on transfer record this 4th day of August, 2020.

Kelly B. Arnold, County Clerk

State of Kansas) SS This is to certify that this plat has been filed for record in the office of the Register of Deeds, this 4th day of August, 2020 at 10:00 a.m., and is duly recorded.

Tonya Buckingham, Register of Deeds
Kenly Zehring, Deputy

CITY HALL - ENGINEERING
MAIL STOP 1-71
Arceli Rosas
FOR YOUR FILES

Baughman Company, P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
Baughman ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

W 53RD ST N FINAL TRACING REC'D 8-19-20

DRAINAGE PLAN NOTE:
A master drainage plan has been developed for this plat. All drainage easements, rights-of-way, and reserves shall remain at established grades (unless modified with the approval of the City Engineer) and shall be unobstructed to allow for the conveyance of stormwater in accordance with the Stormwater Manual. The maintenance of all drainage and drainage facilities in backyard drainage easements and reserves shall be the responsibility of the property owner, and shall be enforced by the Homeowners' Association and be provided for in the Homeowners' Association covenants.