

Saved 10-12-2004 10:14:58 AM by BJB
 Plot Scale 1:200 4656 12-27-2005 2:15:49 PM by BJB
 CA 2002 0221A 001 C300

GENERAL NOTES - SITE GRADING

STRIP 4" TO 6" TOPSOIL FROM AREA TO BE GRADED AND STOCKPILED ON-SITE AS INDICATED. STOCKPILED TOPSOIL SHALL BE CLEAN AND FREE OF LARGE QUANTITIES OF SUBSOIL, ROCKS, VEGETATION OR OTHER UNSUITABLE MATERIALS


HORIZONTAL CONTROL FOR SITE GRADING MAY BE SCALED FROM THIS DRAWING

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL STAKING NECESSARY TO COMPLETE THE SITE GRADING

ALL FILL MATERIAL AND STOCKPILES SHALL BE BLADED SMOOTH AND SLOPED TO DRAIN

ADEQUATE EROSION/SILTATION CONTROLS SHALL BE INSTALLED TO PREVENT SEDIMENT FROM LEAVING THE PROJECT SITE. ALL EROSION CONTROL ITEMS MUST BE REGULARLY AND PROPERLY MAINTAINED BY THE CONTRACTOR. EXISTING ROADWAYS SHALL BE KEPT FREE OF DIRT AND SEDIMENT

CONTRACTOR IS TO STOCKPILE APPROXIMATELY 12,625 CUBIC YARDS OF TOPSOIL. THIS TOPSOIL VOLUME IS INCLUDED IN THE QUANTITY FOR "EXCAVATION". ALL OTHER FILL MATERIAL IS TO BE STOCKPILED ON-SITE AS INDICATED AND KEPT SEPARATELY FROM TOPSOIL



STOCKPILE AREA

3- 30" x 19" RCPHE

See sheet C5.0 for Additional information

EXCEPTION

QUANTITIES FOR INFORMATION ONLY

Grading, Paving and Drainage Quantities

Item No.	Description	Unit	Quantity
1	5" A.C. Pvmnt. (3" Bituminous Base)	S.Y.	3767
2	6" Reinf. Crushed Rock Base	S.Y.	4334
3	Comb. Curb & Gutter	L.F.	1348
4	4" Concrete Sidewalk	S.F.	2195
5	Concrete Pavers	S.F.	570
6	Remove Existing Comb. Curb & Gutter	L.F.	218
7	Wheelchair Ramps	Each	2
8	ADA Symbols	Each	3
9	R7-8 Signs	Each	2
10	R7-8A Signs	Each	1
11	4" White Striping	L.F.	1167
12	30" x 19" RCPHE	L.F.	127.5
13	30" x 19" RCPHE End Sections	Each	6
14	Light Stone Rip Rap	S.Y.	176
15	Excavation	C.Y.	30028
16	Temporary Project Sealing	Acres	27

Add Alternate #1 Quantities

Item No.	Description	Unit	Quantity
1	6" A.C. Pvmnt. (3" Bituminous Base)	S.Y.	3740
2	6" Reinf. Crushed Rock Base	S.Y.	4219
3	Comb. Curb & Gutter	L.F.	1230
4	4" Concrete Sidewalk	S.F.	1076
5	Remove Existing Comb. Curb & Gutter	L.F.	113
6	Wheelchair Ramps	Each	2
7	ADA Symbols	Each	3
8	R7-8 Signs	Each	1
9	R7-8A Signs	Each	2
10	4" White Striping	L.F.	1242

Add Alternate #2 Quantities

Item No.	Description	Unit	Quantity
1	5" A.C. Pvmnt. (3" Bituminous Base)	S.Y.	374
2	6" Reinf. Crushed Rock Base	S.Y.	398
3	4" White Striping	L.F.	268

BENCH MARKS

Datum B.M. B. Step Spike in West side 4th Power Pole North of 29th St. N. on East Side Greenwich Road. Elev=204 23

Datum B.M. D. Spike in West Face High Line Pole, East Side Greenwich Rd., 1st Pole North of K96 Highway. Elev=184 45

B.M. A Railroad Spike in West face of 2nd power pole North of 29th St N. on East side of Greenwich road. Elev=201 53

B.M. C. Railroad Spike in West Side Power Pole East Side Greenwich Road North Side Drive to House #3150 Elev=210 98


B.M. E Railroad Spike in West face of 5th power pole South of 29th St N. on East side of Greenwich road. Elev=192 55

B.M. F Chiseled "b" on concrete curb at East end island in 29th St N. on West side of Greenwich road. Elev=202 65

B.M. G. Chiseled "a" on North Curb Asphalt Drive (29th St N.) at East Side of Soccer Complex Fence to South Elev=204 55

B.M. H. Chiseled "b" on Curb at midpoint of curve, West Side of West Entrance to Soccer Complex off 29th St N. North of North Fence to Soccer Complex. Elev=203 36

SITE GRADING



MCCULLAGE VAN SICKLE & PERRY

ARCHITECTS • PLANNERS • LANDSCAPE ARCHITECTS
 125 S. WASHINGTON WICHITA, KANSAS 67202
 P.O. BOX 948 WICHITA, KANSAS 67201
 TEL 316.262.6400 • FAX 316.262.6406

**NORTHEAST BASEBALL COMPLEX
 29TH STREET NORTH AND GREENWICH ROAD
 WICHITA, KANSAS**

PROJECT NO. 10005
 DATE: 01-11-03
 REVISED:

SHEET
C3.0
 OF 21 SHEETS

Professional Engineering Consultants, P.A.
 303 S. WICKA - WICHITA, KANSAS 67202 • 316-262-2401 • FAX 316-262-3803
 www.pcc.com • en@pcc.com