

**OAK CREEK 2ND ADDITION
PRE VS. POST DISCHARGE TABLE**

Name	Stage, Elev.	Storage, Ac.- Ft.	Pre-Dev. Discharge Rate, CFS	Post-Dev. Discharge, CFS
Basin Offsite			6.00	
Pond #1	1370.50	0.00		Static Level
Q100	1373.51	2.00		60.00
Basin A			63.00	
Pond #2	1362.00	0.00		Static
Q100	1366.60	8.61		42.00
Basin B			43.00	
Pond #3	1375.00	0.00		Static
Q100	1377.10	1.21		47.00
Basin C			47.00	
Pond #4	1373.00	0.00		Static
Q100	1374.90	1.23		16.50
Basin D			17.00	
Pond #5	1388.00	0.00		Static
Q100	1389.50	1.38		40.00
Basin E			8.00	
Basin F			59.00	
Basin A-F			243.00	
Total Discharge Leaving Site =			243.00	205.50