



KEYED PLAN NOTES:

- (1) 400 PAIR, CATEGORY 3, DIRECT BURIED TELEPHONE CABLE. DELIVER CABLE TO OWNER.
4" C WITH PULL ROPE AND CAPS.
 ADD. #3
 (2) 100 PAIR, CATEGORY 3, DIRECT BURIED TELEPHONE CABLE.
 ADD. #3
 (3) PROVIDE ~~400~~ ⁸⁰⁰ PAIR, DIRECT BURIED SPlice ENCLOSURE. SPlice 400 PAIR TELEPHONE CABLE TO EXISTING ~~400~~ ⁸⁰⁰ PAIR TELEPHONE CABLE.
 (4) PROVIDE 400 PAIR, DIRECT BURIED SPlice ENCLOSURE. ~~SPlice 100 PAIR TELEPHONE CABLE TO 400 PAIR TELEPHONE CABLE.~~ DO NOT INSTALL. DELIVER TO OWNER.
 (5) PROVIDE 400 PAIR, DIRECT BURIED SPlice ENCLOSURE.
 (6) PROVIDE 100 PAIR, DIRECT BURIED SPlice ENCLOSURE. DO NOT INSTALL. DELIVER TO OWNER.
 (7) UTILITY COMPANY 3 PHASE PRIMARY PEDESTAL. FIELD VERIFY EXACT LOCATION.
 (8) 4" C. WITH PULL ROPE FOR UTILITY COMPANY PRIMARY ELECTRICAL SERVICE PER UTILITY COMPANY REQUIREMENTS. PROVIDE 36" RADIUS PVC COATED RGS SWEEPS.
 (9) CAP CONDUIT AND PROVIDE UTILITY MARKER TO MARK END OF CONDUIT. ONE MARKER WHERE CONDUITS MEET
 (10) PROVIDE UTILITY MARKER TO MARK DIRECT BURIED SPlice ENCLOSURE LOCATION. PLACE DIRECTLY ABOVE SPlice ENCLOSURE. (11) 2" C WITH PULL ROPE.

SEE SHEET CU1.1 FOR DIRECT
BURIED TELEPHONE CABLE
COORDINATE LAYOUT.

THE WICHITA AIRPORT AUTHORITY
COLONEL JAMES JABARA AIRPORT

SANITARY SEWER AND WATER DISTRIBUTION SYSTEM
SOUTHWEST AREA SITE DEVELOPMENT IMPROVEMENTS

Professional Engineering Consultants, P.A.
303 S. TOPEKA • WICHITA, KANSAS 67202
316-262-2691 • FAX 316-262-3003

Job No. 05471-019