Existing Lift Sta. Col. 7 S.W. Interceptor

HENDRYX

Sta. Drop Construct Type 'A' or 'C' Manhole

Existing 4" S.S., Plastic Line, Under Pressure

Existing 6" Force Line, S.S.

Sta. Construct Type 'A' or 'C' Manhole w/6" Stub-West

Construct 8" Sanitary Sewer 9% @ Ft.

TYLER ROAD

100 R.o.w.

Existing 8" Clay Sub Dist. Sewer

LOT NO. 10

LOT NO. 11

LOT NO. 12

LOT NO. 3

LOT NO. 2

LOT NO. 1

CALLAHAN ADDITION

BYRON AVE.

133.5'

B.M. - 141.55 - CITY STANDARD DISC - 31.± west of ℄ of Tyler Rd. and 88.2' S.E. of ℄ of U.S.54 Pavement.

B.M. - 140.06 - R.R. Spike East Face of Power Pole @ N.W. Corner of Belmeu and Tyler Rd.

B.M. - 141.05 - R.R. Spike, East Face of Power Pole @ Westside of Tyler Rd. on Northside of Hendryx extended.

SCALE: Plan : 1"=40'
Profile : Vertical : 1"=5'
Horizontal : 1"=40'

Set Line

CAUTION: 4" Force Main Sanitary Sewer

CAUTION: 6" Force Main Sanitary Sewer

Ground Elev.

Caution 4" Gas Main (Approx. location, approx. 2' east of West Lt. on TH4

Existing 8" SDR 26 (DIP) 134.45

Fly. 131.35

+1.0% Gr.

95'

8" CLAY PIPE or ALT. 8" A.B.S. COMPOSITE PIPE

Fly. 131.80

0+00

0+50

0+96.4 W
0+93.7 P

DONALD E. SCHMIDT
LICENSED
6311
PROFESSIONAL ENGINEER

As Built 2-16-76

LAT. 82 SOUTHWEST INTERCEPTOR
8" SANITARY SEWER
CITY OF WICHITA, KANSAS
R. W. LINN — CITY ENGINEER
DATE: PROJ. NO. DBWL 573084

14 8 4 1/1 8