



Decker Electric, Inc

4500 W Harry Wichita, KS 67209

T: 316-265-8182

**Change Request**

To: Tyler Dehn  
Wildcat Construction Co Inc  
3219 W May  
Wichita, KS 67213  
Ph: 316-945-9408

Number: 11  
Date: 4/6/17  
Job: 1606-037 Wildcat Const-Pump Station

Description: Bulk Bag Feed Skid Connections

Source: Other

**This change is being sent for the following modifications to this project:**

The following is included in this Change Order Request:

- Provide and install power cord with strain relief connectors from control panel to Scew Conveyor.
- Provide and install power cord with strain relief and twist lock connector for connection to skid mounted cord feeding Vibrator.
- Provide and install control cord with strain relief connectors from control panel to Low Level Switch.
- Provide and install control cord with strain relief connector to Pneumatic Butterfly Valve for valve positioning.
- Provide and install control cord with strain relief and twist lock connector for connection to skid mounted Door Switch.
- Extend 480V 3-phase conduit and wiring around to the East wall of the Chlorine room and over to Feed System Local Control Panel.
- Provide and install 120V 20A single receptacle in MCC room for compressor.

The following is excluded in this Change Order Request:

- Overtime & Doubletime
- System Commissioning
- Pneumatic air lines
- Mounting or calibrating of feed system equipment.

Description	Labor	Material	Equipment	Subcontract	Other	Price
Bulk Bag System Skid Connections					\$3,300.00	\$3,300.00
Extension of circuit to Bulk Bag System					\$920.00	\$920.00
Bulk Bag System Air Compressor Wiring					\$460.00	\$460.00
					Subtotal:	\$4,680.00
					<b>Total:</b>	<b>\$4,680.00</b>

If you have any questions, please contact me at 316-491-5174.

Submitted by: Jarret Bergkamp  
Decker Electric Inc.

Approved by: \_\_\_\_\_  
Date: \_\_\_\_\_