




**COMMERCIAL
PRODUCT SPECIFICATIONS**




SEER up to 14.50

3 to 5 Tons


Cooling Capacity - 32,800 to 92,000 Btuh

MODEL NUMBER IDENTIFICATION



FEATURE HIGHLIGHTS

1. Outdoor Coil Fan
2. Copper Tube/Enhanced Fin Coil
3. Scroll Compressor
4. Heavy Gauge Steel Cabinet
5. Corrosion Resistant Base
6. Refrigerant Line Connections and Access



CONTENTS

Approvals And Warranty	3
Dimensions	8
Electrical Data	7
Features	3
Installation Clearances	9
Optional Accessories - Order Separately	7
Sound Data	9
Specifications	7

APPROVALS AND WARRANTY

APPROVALS

- AHRI Standard 210/240 certified
- AHRI Certified system match-ups and expanded ratings, visit www.ahridirectory.org
- Sound rated to AHRI Standard 270-2008 test conditions
- Tested in an environmental test room
- Rated According to U.S. Department of Energy (DOE) test procedures
- Unit and components ETL, NEC and CEC bonded for grounding to meet safety standards for servicing
- ETL certified (U.S. and Canada)
- ISO 9001 Registered Manufacturing Quality System

WARRANTY

- Compressor:
 - Limited five years in non-residential installations
- All other covered components:
 - Limited one year in non-residential installations

NOTE - Refer to Limited Warranty certificate included with unit for specific details.

FEATURES

APPLICATIONS

- 3 through 5 tons
- Three-phase power supply
- Sound levels as low as 76 dBA
- Vertical air discharge
- Applicable to indoor air handlers or gas furnaces with indoor add-on coils
- Shipped completely factory assembled, piped and wired
- Factory test operated

REFRIGERATION SYSTEM

R-410A Refrigerant

- Non-chlorine, ozone friendly
- Unit is factory pre-charged

1 Outdoor Coil Fan

- Direct drive fan
- Vertical air discharge
- Louvered steel top fan guard
- Totally enclosed fan motor
- Rain shield
- Ball bearings
- Inherently protected

High Capacity Liquid Line Drier

- Factory installed in the liquid line
- Drier traps moisture or dirt
- 100% molecular-sieve, bead type

High Pressure Switch

- Protects the system from high pressure conditions
- Manual reset

2 Copper Tube/Enhanced Fin Coil

- Ripple-edged aluminum fins
- Copper tube construction
- Lanced fins for maximum fin surface exposure
- Fin collars grip tubing for maximum contact area
- Flared shoulder tubing connections
- Silver soldering construction.
- Factory tested under high pressure
- Entire coil is accessible for cleaning.
- PVC coated steel wire coil guard with mesh covering furnished

Optional Accessories

Expansion Valve Kits

- Field installed on certain indoor units
- See TXV Usage table
- Chatleff-style fitting

Refrigerant Line Kits

- Refrigerant lines are shipped refrigeration clean
- Lines are cleaned, dried, pressurized and sealed at factory
- Suction line fully insulated
- Lines are stubbed at both ends


NOTE - Not available for 060 models. Must be field fabricated.

FEATURES

COMPRESSOR

3 Scroll Compressor

- High efficiency with uniform suction flow
- Constant discharge flow, high volumetric efficiency and quiet operation
- Low gas pulses during compression reduces operational sound levels
- Compressor motor is internally protected from excessive current and temperature
- Muffler in discharge line reduces operating sound levels
- Compressor is installed in the unit on resilient rubber mounts for vibration free operation



Scroll Compressor Operation

- Two involute spiral scrolls matched together generate a series of crescent-shaped gas pockets between them
- During compression, one scroll remains stationary while the other scroll orbits around it
- Gas is drawn into the outer pocket, the pocket is sealed as the scroll rotates
- As the spiral movement continues, gas pockets are pushed to the center of the scrolls. Volume between the pockets is simultaneously reduced
- When the pocket reaches the center, gas is now at high pressure and is forced out of a port located in the center of the fixed scrolls
- During compression, several pockets are compressed simultaneously resulting in a smooth continuous compression cycle
- Continuous flank contact, maintained by centrifugal force, minimizes gas leakage and maximizes efficiency
- Compressor is tolerant to the effects of slugging and contaminants. If this occurs, scrolls separate, allowing liquid or contaminants to be worked toward the center and discharged

Compressor Crankcase Heater

- Protects against refrigerant migration that can occur during low ambient operation

Optional Accessories

Compressor Sound Cover

- A reinforced vinyl compressor cover containing a 1-1/2 inch thick batt of fiberglass insulation.
- All open edges are sealed with a one-inch wide hook and loop fastening tape.

CABINET

- 4 • Heavy gauge steel cabinet
- Five station metal wash process
- Powder paint finish for superior rust and corrosion protection
- Control box is conveniently located with all controls factory wired
- Corner patch plate allows compressor access
- Drainage holes provided in base section

Unit Base

- Durable zinc-coated base section resists rust and corrosion

6 Refrigerant Line Connections, Electrical Inlets, Service Valves

- Sweat connection suction and liquid lines
- Located on corner of unit cabinet
- Suction valve can be fully shut off, while liquid valve may be front seated to manage refrigerant charge while servicing system
- Refrigerant line connections and field wiring inlets are located in one central area of cabinet for easy access
- See dimension drawing

Optional Accessories

Hail Guards

- Heavy-gauge steel construction
- Painted to match cabinet
- Surrounds unit on all four sides
- Prevent damage to the coil

Unit Stand-Off Kit

- Black high density polyethylene feet
- Raises unit off mounting surface
- Four feet furnished per order number

FEATURES

CONTROLS

Optional Accessories

Compressor Low Ambient Cut-Off Switch

- Non-adjustable switch (low ambient cut-out)
- Prevents compressor operation when outdoor temperature is below 35°F

Compressor Time-Off Control

- Kit prevents compressor short-cycling
- Allows time for suction and discharge pressure to equalize
- Permits compressor start-up in an unloaded condition
- Automatic reset
- Five minute delay between compressor shut-off and start-up

Indoor Blower Off Delay Relay Kit

- Delays indoor blower-off time during the cooling cycle

Low Ambient Kit

- Heat pump can operate in the cooling mode down to 45°F outdoor air temperature without additional controls
- Two low ambient control options are available for field installation:
 1. Low Ambient Control Kit (30°F)
 2. Low Ambient Control (0°F)
Requires Speed Control and Weatherproof Kit (ordered separately). Available for 208/230V models only.

NOTE - Freezestat should be installed on compressors equipped with a low ambient kit.

Freezestat

- Installs on or near the vapor line of the indoor coil or on the suction line
- Senses suction line temperature and cycles the compressor off when suction line temperature falls below it's setpoint
- Opens at 29°F and closes at 58°F

Thermostat

- For thermostat options, see Optional Conventional Temperature Control Systems on page 6

THIS PAGE INTENTIONALLY LEFT BLANK

SPECIFICATIONS

General Data		Model No.	TSA036S4	TSA042S4	TSA048S4	TSA060S4
Nominal Tonnage			3	3.5	4	5
Connections (sweat)	Liquid line o.d. - in.		3/8	3/8	3/8	3/8
	Suction line o.d. - in.		7/8	7/8	7/8	1-1/8
¹ Refrigerant (R-410A) furnished			5 lbs. 9 oz.	6 lbs. 6 oz.	7 lbs. 8 oz.	10 lbs. 0 oz.
Outdoor Coil	Net face area sq. ft.	Outer coil	13.22	16.33	21.00	18.67
		Inner coil	---	---	---	17.96
	Tube diameter - in.	5/16	5/16	5/16	5/16	
	Number of rows	1	1	1	2	
	Fins per inch	26	26	26	22	
Outdoor Fan	Diameter - in.		18	22	22	22
	Number of blades		4	4	4	4
	Motor hp		208/230V - 1/5 460/575V - 1/6	1/4	1/4	1/4
	Cfm		2400	3500	3670	3600
	Rpm		1090	825	825	830
	Watts		185	310	295	285
	Shipping Data - lbs. 1 package			135	178	194

ELECTRICAL DATA

Line voltage data - 60 hz - 3ph		208/230V	460V	575V	208/230V	460V	208/230V	460V	575V	208/230V	460V	575V
² Maximum overcurrent protection (amps)		20	15	15	30	15	30	15	15	35	15	15
³ Minimum circuit ampacity		14.2	7.8	5.3	18.6	8.4	18.8	8.8	7.0	21.3	10.7	8.3
Compressor	Rated load amps	10.4	5.8	3.8	13.5	6	13.7	6.2	4.8	15.6	7.8	5.8
	Locked rotor amps	73	38	36.5	88	44	83.1	41	30.4	110	52	35.5
	Power factor	.85	.84	.83	.88	.83	.90	.92	.88	.90	.91	.90
Condenser Fan Motor	Full load amps	1.1	.55	.55	1.7	1.0	1.7	1.0	1.0	1.7	1.0	1.0
	Locked rotor amps	1.9	1.1	1.1	3.1	2.3	3.1	2.3	2.3	3.1	2.3	2.3

OPTIONAL ACCESSORIES - ORDER SEPARATELY

Compressor Low Ambient Cut-Off Switch	45F08		•		•		•		•
Compressor Sound Cover	69J03		•		•		•		•
Compressor Time-Off Control	47J27		•		•		•		•
Freezestat	3/8 in. tubing	93G35		•		•		•	
	5/8 in. tubing	50A93		•		•		•	
Hail Guards	24 x 24 x 28 in.	14X09		•					
	28 x 28 x 28 in.	14X16			•				
	28 x 28 x 36 in.	14X14				•			
	28 x 28 x 32 in.	14X19						•	
Indoor Blower Off Delay Relay	58M81		•		•		•		•
Loss of Charge Switch	84M23		•		•		•		•
⁴ Low Ambient Kit (Fan Cycling) (30°F)	34M72		•		•		•		•
⁴ Low Ambient Control (0°F) 208/230V only	Speed Control	X5867		•		•		•	
	Weatherproof Kit	56N41		•		•		•	
Refrigerant Line Sets	L15-65-30, L15-65-40, L15-65-50			•			•		
	Field Fabricate								•
Unit Stand-Off Kit	94J45		•		•		•		•

NOTE - Extremes of operating range are plus 10% and minus 5% of line voltage.





¹ Refrigerant charge sufficient for 15 ft. length of refrigerant lines.

² HACR type circuit breaker or fuse.

³ Refer to National or Canadian Electrical Code manual to determine wire, fuse and disconnect size requirements.


⁴ Freezestat is recommended with Low Ambient Control.

DIMENSIONS



Model No.	A		B		C	
	inches	mm	inches	mm	inches	mm
TSA036S4	24-1/4	616	29-1/4	743	28-1/2	724
TSA042S4	28-1/4	718	29-1/4	743	28-1/2	724
TSA048S4	28-1/4	718	37-1/4	946	36-1/2	927
TSA060S4	28-1/4	718	33-1/4	845	32-1/2	826

INSTALLATION CLEARANCES



NOTES:

Service clearance of 30 in. (762 mm) must be maintained on one of the sides adjacent to the control box.

Clearance to one of the other three sides must be 36 in. (914 mm)

Clearance to one of the remaining two sides may be 12 in. (305 mm) and the final side may be 6 in. (152 mm).

A clearance of 24 in. must be maintained between two units.
48 in. (1219 mm) clearance required on top of unit.

SOUND DATA

¹ Unit Model	Octave Band Sound Power Levels dBA, re 10 ⁻¹² Watts Center Frequency - HZ							¹ Sound Rating Number (dBA)	² Estimated Sound Pressure Level at Distance From Unit (dBA at distance in ft.)				
	125	250	500	1000	2000	4000	8000		3	5	10	15	50
TSA036S4	70.5	67.5	69.5	72.5	69.5	63	59	76	69	64	58	55	44
TSA042S4	74	76.5	76.5	75.5	72	68	63.5	80	73	68	62	59	48
TSA048S4	73.5	76	76	76.5	72.5	69.5	64.5	80	73	68	62	59	48
TSA060S4	73.5	74.5	77	75	72	69	64.5	80	73	68	62	59	48

NOTE - the octave sound power data does not include tonal correction.

¹ Tested according to AHRI Standard 270-2008 test conditions.

² Estimated sound pressure level at distance based on AHRI Standard 275-2010 method for equipment located on the ground, roof, or on side of building wall with no adjacent reflective surface within 9.8 feet. Sound pressure levels will increase based on changes to assumptions. For other applications, refer to AHRI Standard 275.

REVISIONS

Sections	Description of Change
Sound Data	Added data for Estimated Sound Pressure Level at Distance From Unit.



Visit us at www.allied-commercial.com

For the latest technical information, visit us at www.allied-commercial.com

Contact us at 1-800-448-5872

NOTE - Due to Allied Commercial ongoing commitment to quality, Specifications, Ratings and Dimensions subject to change without notice and without incurring liability. Improper installation, adjustment, alteration, service or maintenance can cause property damage or personal injury. Installation and service must be performed by a qualified installer and servicing agency.