



287 Hills Storage
 WA 12-11-93
 WA 2-9-94
 APPROVED CUP
 212-00



GENERAL PROVISIONS


1. THIS DEVELOPMENT CONTAINS APPROXIMATELY 3.2 NET ACRES.
2. THE PROPOSED DEVELOPMENT CONTAINS ONE (1) PARCEL WITH COMMERCIAL USES. FOR SPECIFIC USES SEE DESCRIPTION.
3. SETBACKS ARE AS INDICATED ON PLAN VIEW.
4. ALL UTILITIES SHALL BE INSTALLED UNDERGROUND.
5. A DRAINAGE PLAN SHALL BE PROVIDED AT THE TIME OF PLATTING.
6. SIGNS:
SIGNS SHALL BE LIMITED TO 3 AS INDICATED ON THE PLAN IN ACORDANCE WITH THE SECTION 24.04 OF THE CODE OF THE CITY OF WICHITA. SIGNS WITH ROTATING OR FLASHING LIGHTS, OFF-SITE AND PORTABLE SIGNS ARE PROHIBITED.
7. FINAL DETERMINATION OF STREET RIGHT-OF-WAY SHALL BE RESOLVED AT THE TIME OF PLATTING.
8. PARKING:
A. PARKING SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 28.04.140 ET. SEQ. OF THE CODE OF THE CITY OF WICHITA UNLESS SPECIFIED IN THE PARCEL DESCRIPTIONS.
9. THE TRANSFER OF TITLE ON ALL OR ANY PORTION OF THE LAND INCLUDED IN THE C.U.P. DOES NOT CONSTITUTE A TERMINATION OF THE PLAN OR ANY PORTION THEREOF, BUT SAID PLAN SHALL RUN WITH THE LAND FOR DEVELOPMENT AND BE BINDING UPON THE PRESENT OWNERS, THEIR SUCCESSORS AND ASSIGNS AND THEIR LESSEES UNLESS AMENDED.
10. ALL LIGHTS SHALL BE SHIELDED TO REFLECT LIGHT DOWNWARD OR DIRECT LIGHT AWAY FROM RESIDENTIAL AREAS.
11. FIRE LANES:
A. FIRE LANES SHALL BE IN ACCORDANCE WITH THE FIRE CODE OF THE CITY OF WICHITA. NO PARKING SHALL BE ALLOWED IN SAID FIRE LANES, ALTHOUGH THEY MAY BE USED FOR PASSENGER LOADING AND UNLOADING.
B. DURING THE BUILDING PERMIT REVIEW, THE FIRE CHIEF, OR HIS DESIGNATED REPRESENTATIVE SHALL APPROVE THE SITE PLAN REGARDING THE DESIGN OF THE FIRE LANES PRIOR TO ISSUANCE OF A BUILDING PERMIT.
12. ACCESS CONTROL:
A. ACCESS TO GEORGE WASHINGTON BLVD. AND HILLSIDE ARE INDICATED ON C.U.P.
13. LANDSCAPE BUFFERS/SCREENING:
A. A LANDSCAPE PLAN PREPARED BY A LANDSCAPE ARCHITECT FOR THE LANDSCAPE BUFFERS AS INDICATED ON THE PLAN AND SUBMITTED AS A PART OF THE C.U.P. IDENTIFYING THE TYPE, LOCATION, AND SPECIFICATION OF PLANT MATERIALS AND METHOD OF PROVIDING WATER TO THE PLANT MATERIALS, SHALL BE SUBMITTED TO THE PLANNING DEPARTMENT FOR THEIR REVIEW AND APPROVAL PRIOR TO THE ISSUANCE OF A BUILDING PERMIT. THE LANDSCAPE BUFFERS, AS INDICATED ON THE PLAN, SHALL CONSIST OF TREES, TURF AND LOW SHRUBBERY AND ALL BE OF SUCH TYPE AND MAINTAINED IN SUCH A MANNER AS NOT CONSTITUTE A TRAFFIC HAZARD.
B. A FINANCIAL GUARANTEE FOR THE PLANT MATERIALS APPROVED IN THE LANDSCAPE PLAN SHALL BE REQUIRED PRIOR TO THE ISSUANCE OF ANY OCCUPANCY PERMIT IF THE REQUIRED LANDSCAPING HAS NOT BEEN PLANTED.
14. FAILURE TO PROPERLY MAINTAIN THE LANDSCAPE BUFFERS MENTIONED ABOVE SHALL BE CONSIDERED A VIOLATION OF THE C.U.P. AFTER A JOINT DETERMINATION BY THE DIRECTOR OF PLANNING AND THE SUPERINTENDANT OF CENTRAL INSPECTION.
15. PARCEL DESCRIPTION:
PARCEL NUMBER 1:
PROPOSED USES: SELF STORAGE UNITS WITH ASSOCIATED OFFICE, COMMUNICATIONS TOWER (with conditions) - see Admin Ord dated 9-12-95
16. IF THE ABUTTING PROPERTY TO THE NORTH OF THE C.U.P. COMES INTO THE SAME OWNERSHIP, POSSESSION, OR CONTROL, THEN THAT PROPERTY SHALL ONLY BE USED FOR LANDSCAPED AREA, UNLESS THE PROPOSED USE IS APPROVED BY THE CITY COUNCIL THROUGH AN AMENDMENT OF THE C.U.P.

GROSS AREA - 3.06 ACRES (139,392 SQ. FT.)
MAXIMUM BUILDING COVERAGE - 63,536 SQ. FT.
MAXIMUM GROSS FLOOR AREA - 63,536 SQ. FT.
MAXIMUM BUILDING HEIGHT - 35'
PARKING - SEE PROVISIONS NUMBER 8
SETBACKS - SEE PLAN



30' 1/2 STREET R.O.W. 20' CONTINGENT STREET DEDICATION

HILLSIDE STORAGE C.U.P.




BILL G. YUNG DESIGN
 4912 E. 29TH STREET NORTH
 WICHITA, KS. 67220
 316-865-5567 FAX 316-865-9266

DATE: SEPTEMBER 1, 1993
 REV. NOV. 22, 1993
 DEC. 22, 1993

SHEET TITLE

PROJECT HILLSIDE STORAGE CUP

SHEET OF







PLANT LIST:

QUANT.	COMMON NAME / BOTANICAL NAME	SIZE	COND.	REMARKS
2	SPRING SNOW CRABAPPLE <i>Malus 'Spring Snow'</i>	2"	BB	
3	AUTUMN PURPLE ASH <i>Fraxinus americana 'Autumn Purple'</i>	2"	BB	
3	SUMMIT ASH <i>Fraxinus pennsylvanica 'Summit'</i>	2"	BB	
6	GOLDENRAINTREE <i>Koelreuteria paniculata</i>	2"	BB	
30	CANAERT JUNIPER <i>Juniperus virginiana 'Canaertii'</i>	4 - 5'	BB	
16	CHANTICLEER PEAR <i>Pyrus calleryana 'Chanticleer'</i>	2"	BB	
125	MINT JULEP JUNIPER <i>Juniperus chinensis 'Mint Julep'</i>	1 GAL.	CONT.	(REFER TO PLAN)
24	MINT JULEP JUNIPER <i>Juniperus chinensis 'Mint Julep'</i>	2 GAL.	CONT.	(REFER TO PLAN)


NOTES:

- LANDSCAPE CONTRACTOR IS TO VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES (INCLUDING THOSE INDICATED ON THE PLAN) PRIOR TO INSTALLATION OF PLANT MATERIAL AND IRRIGATION SYSTEM. UTILITIES CAN BE FLAGGED BY CALLING 687-2470.
- AREAS DENOTED AS 'SEEDED WITH FESCUE' ARE TO BE SEEDED WITH REBEL II FESCUE AS CONSTRUCTION SCHEDULE PERMITS.
- THE PROPOSED LANDSCAPE PLAN IS TO BE IRRIGATED BY AN AUTOMATIC IRRIGATION SYSTEM. THE AREAS TO BE IRRIGATED INCLUDE ALL SHRUB BEDS AND ALL SEEDED AREAS INDICATED AS FESCUE ON THIS PLAN.
- THE LANDSCAPE CONTRACTOR AND/OR IRRIGATION CONTRACTOR IS RESPONSIBLE FOR OBTAINING A MINOR STREET PRIVILEGE PERMIT FROM THE CITY ENGINEER'S OFFICE PRIOR TO ANY CONSTRUCTION OF IRRIGATION SYSTEM, TREE PLANTING, OR ANY OTHER PERMANENT STRUCTURE IN THE PUBLIC RIGHT-OF-WAY.
- THE PLANTING SOIL MIXTURE FOR TREE AND SHRUB PLANTINGS SHALL BE EXCAVATED TOPSOIL. NO EXCAVATED SUBSOIL SHALL BE ALLOWED AS BACKFILL.
- ALL SHRUB BEDS AND CONIFER TREE PLANTINGS ARE TO BE MULCHED WITH SHREDDED CYPRESS MULCH TO A MINIMUM DEPTH OF AT LEAST 2". MINIMUM DEPTH FOR DECIDUOUS TREE PLANTINGS IS TO BE 4".
- AS INDICATED ON THE PLAN, ALL PROPOSED TREES ADJACENT TO GEORGE WASHINGTON BLVD. ARE TO BE LOCATED A MINIMUM OF 6' (SIX FEET) WITHIN THE EAST PROPERTY LINE.



CITY LANDSCAPE ORDINANCE TABULATION:
 LANDSCAPED STREET YARD = 9104 S.F.
 # REQUIRED SHADE TREES = 19
 # PROPOSED SHADE TREES = 12
 # PROPOSED ORNAMENTAL TREES = 18 (EQUIVALENT TO 9 SHADE TREES)

 EQUIVALENT TOTAL # TREES = 21



DP-212
LANDSCAPE PLAN
 APPROVED 1/18/95 BY *[Signature]*

PLANT SCHEDULE

Qty.	Symbol	Common Name	Botanical Name	Size	Root
185	NBT	NEW BLUE TAMMY	JUNIPERUS SABINA 'TAMARISCIFOLIA'	5-GAL	CONT.
11	VRD	VARIEGATED DOGWOOD	CORNUS ALBA 'ELEGANTISSIMA'	5-GAL	CONT.
82	CPB	CRIMSON PYGMY BARBERRY	BERBERIS THUNBERGII ATROPURPUREA	1-GAL	CONT.
174	BB	BIG BLUE LIRIOPE	LIRIOPE MUSCARI	1-GAL	CONT.
133	LFP	GNOME PYRACANTHA	PYRACANTHA COCCINEA 'GNOME'	5-GAL	CONT.
174	SA	SEASONAL ANNUALS	SEASONAL ANNUALS	1-GAL	CONT.
185	AWS	ANTHONY WATERER SPIREA	SPIRAEA X BUMALDA	1-GAL	CONT.
275	BCJ	BLUE CHIP JUNIPER	JUNIPERUS HORIZONTALIS 'BLUE CHIP'	1-GAL	CONT.
4	DBB	DWARF BURNING BUSH	EUONYMUS ALATUS	1-GAL	CONT.
32	AJ	ARCADIA JUNIPER	JUNIPERUS SABINA 'ARCADIA'	1-GAL	CONT.
31	WGB	WINTERGEM BOXWOOD	BUXUS MICROPHYLLA 'WINTERGEM'	1-GAL	CONT.
11	DHG	DWARF HAMELN GRASS	PENNISETUM ALOPECUROIDES	1-GAL	CONT.
13	PCR	PINK CARPET ROSE	ROSA X 'NOATRAUM'	1-GAL	CONT.
		RED FLOWER CARPET ROSE	ROSA X 'NOATRAUM'	1-GAL	CONT.
11	CHP	CHANTICLEER PEAR	PYRUS CALLERYANA	1-GAL	CONT.
6	APA	AUTUMN PURPLE ASH	FRAXINUS PENNSYLVANICA	1-GAL	CONT.
200	CP	CAPITAL PEAR	PYRUS CALLERYANA 'CAPITAL'	1-GAL	CONT.
29	LBE	LACEBARK ELM	ULMUS PARVIFOLIA	1-GAL	CONT.
4	NRO	NORTHERN RED OAK	QUERCUS RUBRA	1-GAL	CONT.
4	ERC	EASTERN RED CEDAR	CEDRUS	1-GAL	CONT.
4	ABM	AUTUMN BLAZE MAPLE	ACER X FREEMANI	1-GAL	CONT.
3	CIP	CHINESE PISTACHE	PISTACIA CHINENSIS	1-GAL	CONT.

Landscape Ordinance Calculations


539 (Total Lin. Ft. of Street Frontage)
 X 20 (Square Ft. Factor)
 10,780 (Total Sq. Ft. of Landscaped Street Yard Required)

Landscaped Street Yard Provided 21,121.00 Sq. Ft.
 Shade Trees Required 22
 Shade Trees Provided 39 Shade
 36 Ornamental


Parking Lot Trees Required: 13.30
 Parking Lot Trees Provided: 29 SHADE
 29 SHADE

Buffer Required: 405' Divided by 40 = 10 Shade Trees Required
 Buffer Provided: 10 Shade Trees
 4 Conifer

Irrigation- Water for plant establishment to be provided by automatic underground sprinkler system with rain sensor



TREE TOP
 NURSERY & LANDSCAPING INC.
 5910 E. 37th NORTH
 WICHITA, KS 67220




Revised 12-10-04
 Revised 4-28-05

DP-213 PARCEL 1 & 2
LANDSCAPE PLAN
 APPROVED 05/14/05 BY JDS
 SUPERSEDES PLANS APPROVED 04/10/02 & 10/23/01
 M.A.P. Copy 1 of 2

A LANDSCAPE PLAN FOR:
CAMBRIDGE MARKET
 21ST. AND WEBB ROAD

SCALE: 1" = 40'-0"



**SPANGENBERG PHILLIPS
ARCHITECTURE**
121 N. Mead, Suite 201, Wichita, KS 67202
TEL: 316.267.4002 FAX: 316.267.1509
www.spangenbergphillips.com

**MKEC
ENGINEERING
CONSULTANTS, INC.**
1101 N. WEBB ROAD
WICHITA, KS 67202
316.267.9600

Baskin BR Robbins.
CAMBRIDGE MARKET RETAIL CENTER
9747 EAST 21ST STREET NORTH WICHITA, KANSAS

LANDSCAPE NOTES


- ALL PAVEMENT, SIDEWALKS, CURB & GUTTER SHALL BE CONSTRUCTED IN ACCORDANCE WITH CITY OF WICHITA SPECIFICATIONS.
- WHEELCHAIR RAMP LOCATIONS TO SERVE THE PROPOSED BUILDINGS SHALL BE COORDINATED WITH THE BUILDING PLANS PRIOR TO CONSTRUCTION.
- EDGING SHALL BE CURV-RITE ALUMINUM, 14 GAUGE X 4". INSTALL TOP FLUSH WITH TOP OF ADJOINING WALKS OR BACKS OF CURBS.
- MULCH SHALL BE 3" DEPTH SHREDDED HARDWOOD BARK. MULCH 36" DIAMETER RING X 6" DEPTH AROUND EACH TREE PLANTED IN TURF AREA.
- PLANTING SOIL AMENDMENTS SHALL BE BACK-TO-EARTH BRAND COTTON BUR COMPOST AND MILORGANITE MIXED INTO BACKFILL SOIL. PLUS NEW LAWN STARTER FERTILIZER (INCORPORATED INTO THE TOP 1-2" OF BACKFILL SOIL).
- ALL PLANTS SHALL CONFORM TO ANSI Z601 FOR SIZE AND QUALITY STANDARDS.
- ALL TURF AREAS SHOWN ON PLAN SHALL BE SODDED WITH FINE-BLADED TALL FESCUE SOD.
- ALL LAWN AND PLANTING BED AREAS WITHIN LIMITS OF LANDSCAPE AND IRRIGATION LINE SHOWN ON PLAN SHALL BE WATERED WITH AN AUTOMATIC UNDERGROUND IRRIGATION SYSTEM USING SPRAY HEADS. DRIP IRRIGATION WILL NOT BE PERMITTED. SYSTEM SHALL HAVE A RAIN-SENSING AUTOMATIC SHUT-OFF DEVICE WHICH WILL TURN OFF SYSTEM DURING PERIODS OF ADEQUATE RAIN.
- IN THE EVENT OF A DISCREPANCY BETWEEN THE PLAN AND THE QUANTITIES ON THE PLANT LIST, THE PLAN SHALL GOVERN.
- PROVIDE AND INSTALL ATTRACTIVE LIMESTONE BOULDERS IN SIZES AND LOCATIONS AS SHOWN ON THE PLAN.

LANDSCAPE ORDINANCE CALCULATIONS:

FRONTAGE OF SITE = 110', AVERAGE DEPTH OF LOT = 200'
 SQUARE FOOTAGE FACTOR = 10
 REQUIRED L.S. STREET YARD = 110' x 10 = 1100 SF
 LANDSCAPED STREET YARD PROVIDED = 2672 SF
 STREET YARD TREES REQUIRED = 1100/300 = 3.4 ROUNDS UP TO 4 SHADE TREES EQUIV.
 TREES PROVIDED = 5 SHADE TREES (2 EXIST. 'CHANTICLEER' PEAR 2 EXIST. SAWTOOTH OAK, 1 EXIST. SCOTCH PINE)
 PARKING STALLS PROVIDED = 51
 PARKING LOT TREES REQUIRED = 255 ROUNDS UP TO 3
 PARKING LOT TREES PROVIDED = 11 (8 ARE LOCATED WITHIN PARKING LOT ISLANDS)
 ALL PARKING STALLS ARE SCREENED FROM 'STREET NAME' BY CONTINUOUS SHRUB PLANTINGS.

MASTER PLANT LIST


QTY.	COMMON NAME	BOTANICAL NAME	SIZE	CONDITION/REMARKS
TREES				
1	'BLUE ATLAS' CEDAR	<i>Cedrus atlantica 'Glauca'</i>	6-7' Ht.	Balled and Burlapped or Container
SHRUBS AND ORNAMENTAL GRASSES				
3	'BERRI-MAGIC KIDS' HOLLY	<i>Ilex x meserveae 'Blue Boy/Blue Girl'</i>	5 gal	Container
24	'ARMSTRONG' JUNIPER	<i>Juniperus chinensis 'Armstrong'</i>	5 gal	Container
16	'BRESSINGHAM' CORAL BELLS	<i>Heuchera 'Bressingham Hybrids'</i>	1 gal	Container
9	'CHICA RED' DWARF CRAPEMYRTLE	<i>Lagerstroemia indica 'Monred'</i>	2 gal	Container
7	CHINESE FOUNTAIN GRASS (NOT 'Hameln')	<i>Pennisetum alopecuroides</i>	3 gal	Container
4	'DAUB'S FROSTED' JUNIPER	<i>Juniperus chinensis 'Daub's Frosted'</i>	5 gal	Container
17	DAYLILIES	<i>Hemerocallis sp.</i>	1 gal	Container
43	'FIREPOWER' DWARF NANDINA	<i>Nandina domestica 'Firepower'</i>	2 gal	Container
3	'GOLDEN SWORD' YUCCA	<i>Yucca filamentosa 'Golden Sword'</i>	5 gal	Container
20	'ROSY RETURNS' DAYLILY	<i>Hemerocallis 'Rosy Returns'</i>	1 gal	Container
5	'YAKUSHIMA' GRASS	<i>Miscanthus sinensis 'Yakushima'</i>	5 gal	Container




N. WEBB ROAD

N. WEBB ROAD


LANDSCAPE PLAN AT BLDG



DP-213 PORTION OF PARCEL 1
LANDSCAPE PLAN
 APPROVED 04-22-09 BY [Signature]
 MAP D Copy 1 of 2



4-8-09 REVISED PER PLANNING COMMENTS



DP-213 PORTION OF PARCEL 1-ADDENDUM
LANDSCAPE PLAN

APPROVED 08-04-09 BY DG
 MAPD Copy 1 of 2



REVISED LANDSCAPE PLAN


1/8"=1'-0"
 0 8'

Prepared By:


David R. Wells
 Kansas State University
 Bachelors of Landscape Architecture

08-04-2009





LEGEND



PLANT SCHEDULE

QTY.	COMMON NAME	BOTANICAL NAME	SIZE	COND.	REMARKS	
SHADE TREE						
2	CADDIS MAPLE	<i>Acer saccharum 'Caddis'</i>	2' CAL.	B 4 B		
5	PATHMORE ASH	<i>Fraxinus pennsylvanica 'Pathmore'</i>	2' CAL.	B 4 B		
EVERGREEN TREE						
5	AUSTRIAN PINE	<i>Pinus nigra</i>	5-6' HT.	B 4 B		
3	CANAERT JUNIPER	<i>Juniperus virginiana 'Canaert'</i>	5-6'	B 4 B		
ORNAMENTAL TREE						
3	THORNLESS COCKSFOUR HAWTHORN	<i>Crataegus crusgalli</i>	1 1/2' CAL.	B 4 B	MULTI-TRUNK	
2	THORNLESS COCKSFOUR HAWTHORN (M)	<i>Crataegus crusgalli</i>	1 1/2' CAL.	B 4 B		
2	REDBUD	<i>Cercis canadensis</i>	1 1/2' CAL.	B 4 B		
1	PRAIRIFIRE CRAB	<i>Malus 'Prairifire'</i>	1 1/2' CAL.	B 4 B		
8	CHANTICLEER PEAR	<i>Pyrus calleryana 'Chanticleer'</i>	1 1/2' CAL.	B 4 B		
DECIDUOUS SHRUBS						
35	PYRACANTHA COCCINEA	<i>Pyracantha coccinea 'Gnome'</i>	3 GAL.	CONT.	ESPALIER	
3	PYRACANTHA LALANDEI	<i>Pyracantha coccinea 'Lalandei'</i>	5 GAL.	CONT.		
1	SNOWMOUND SPIREA	<i>Spiraea nipponica 'Snowmound'</i>	5 GAL.	CONT.		
3	ANTHONY WATERER SPIREA	<i>Spiraea bumalda 'Anthony Waterer'</i>	2 GAL.	CONT.		
5	CRIMSON PIGMY BARBERRY	<i>Berberis thunbergii atropurpurea</i>	3 GAL.	CONT.		
16	COMPACT BURNING BUSH	<i>Euonymus alatus compacta</i>	3 GAL.	CONT.		
6	LITTLE PRINCESS SPIREA	<i>Spiraea japonica 'Little Princess'</i>	2 GAL.	CONT.		
10	CHENAULT CORALBERRY	<i>Symphoricarpos x chenaaulti</i>	3 GAL.	CONT.		
EVERGREEN SHRUBS						
3	MINT JULIP JUNIPER	<i>Juniperus chinensis 'Mint Julip'</i>	5 GAL.	CONT.		
16	DENSIFORM YEW	<i>Taxus x media 'Densifolia'</i>	5 GAL.	CONT.		
10	WINTER GEM BOXWOOD	<i>Buxus microphylla 'Koreana'</i>	5 GAL.	CONT.		
GROUND COVER						
8	(J) BLUE RUG JUNIPER	<i>Juniperus horizontalis 'Wilton'</i>	1 GAL.	CONT.	36' O.C.	
355	(W) WINTERCREEPER	<i>Euonymus fortunei 'Coloratus'</i>	4' POT.	CONT.	15' O.C.	
10	(P) PERIWINKLE	<i>Vinca minor</i>	4' POT.	CONT.	15' O.C.	
VINE						
5	WISTERIA	Wisteria, Purple	5 GAL.	CONT.	SECURE VINE TO TRELLIS	
PERENNIALS						
35	HOSTA	Hosta 'Honeybell's'	1 GAL.	CONT.	18' O.C.	
15	DAYLILY	<i>Hemerocallis 'Stella de Oro'</i>	1 GAL.	CONT.		
LAWN						
	FESCUE	-----	----	SOD		

* MULTI-TRUNK TREE

GENERAL NOTES:

- ALL TREE/SHRUB PLANT HOLES AND GROUND COVER BEDS ARE TO HAVE A SOIL MIX CONSISTING OF 60% EXCAVATED SOIL AND 40% "BACK TO EARTH" ACCIDIFIED SOIL CONDITIONER.
- ALL TREES TO BE STAKED, PRUNED AND MULCHED. REFER TO DTL. 1/8L-11 FOR TREE PLANTING DETAIL.
- ALL TREE AND SHRUB PLANTER BEDS ARE TO HAVE 3" OF SHREADEDED CEDAR MULCH.
- USE TRIANGULAR SPACING FOR GROUND COVER PLANTINGS. REFER TO DTL. 2/8L-11.
- ALL TREES WITH BROKEN LEADERS WILL NOT ACCEPTABLE.
- GUY WIRES AND TREE WRAPPING TO REMAIN A MINIMUM OF ONE YEAR. OWNER TO REMOVE.
- ALL TREE LOCATIONS ARE TO BE STAKED FOR APPROVAL PRIOR TO PLANTING OPERATIONS.
- EDGE BETWEEN LAWN AND PLANTER BEDS ARE TO BE HAND SPADED, NO MAN MADE EDGES. REFER TO DTL. 3/8L-11.
- BRANCHING HEIGHT FOR SHADE TREES ARE TO BE 6' (1/2-6'). BRANCHING HEIGHT FOR SINGLE TRUNK ORNAMENTAL TREES ARE TO BE 4' (1/2-6').
- PROVIDE A COLORFUL ANNUAL DISPLAY FOR FLOWER VASES SUCH AS DRACENA (CENTER PLANT FOR VASE) W/ RED GERANIUMS, VARIEGATED VINCA MAJOR, ETC.
- CONTRACTOR TO VERIFY ALL QUANTITIES LISTED IN PLANT SCHEDULE.
- CONTRACTOR TO SUPPLY WOODEN FAN TRELLIS FOR EACH LALANDEI PYRACANTHA (ESPALIER).

LANDSCAPE ORDINANCE CALCULATIONS

LANDSCAPE STREET YARD
 150 total lf. of st. front. (N. Prop. Line)
 x 12
 1,800 (total sq. ft. of landscape street yard required)
 PROVIDED: 4,240 sq. ft.
 1,900 sq. ft.
 = 500 (1 tree per 500 sq. ft.)
 3.8 or say 4 trees req'd.
 6.5 trees provided

PARKING LOT SCREENING AND LANDSCAPING
 Parking lots are screened w/ shrubs

Parking lot trees
 56 parking lot stalls
 = 20 (one tree per 20 parking stalls)
 2.9 or say 3 trees req'd. (1/2 must be interior)
 8 trees provided

SIDE AND REAR YARD BUFFERS
 No buffers required

LANDSCAPE PLAN

1" = 16' - 0"



Wilson Darnell Mann P.A.
 105 N. Washington - Wichita, Kansas 67202
 ph 316.262.4700 fx 316.262.0002
 www.wdmdesign.com

DP-213 Parcel 3
 LANDSCAPE PLAN
 APPROVED [Signature]
 SHEET 1 of 3
 MAPD Cmp. 1 of 2



Ground Round of Kansas
 Prototype #4600

21st & Webb
 Wichita, Kansas

PRINTS ISSUED
 Nov. 4, 2002

WDM No. 02140
 draw: BWH
 checked: BWH






1 DECID. TREE PLANTING DETAIL
NOT TO SCALE

2 SHRUB PLANTING DETAIL AT EDGING/BED AREAS
NOT TO SCALE

GENERAL LANDSCAPE NOTES

- All work shall be done in accordance with these Landscape Specifications and Local Industry Standards.
- Landscape Contractor shall submit bid with unit prices for all plants which include mulch, installation, guarantee, etc...
- Prior to any excavation for landscaping purposes, the location of underground utilities shall be determined by calling the local utility companies. Contractor shall be responsible for any damage done to existing utilities.
- The landscape contractor is to be responsible for all permits required and is to see that all work is performed in accordance with state and local codes.
- Report any discrepancies in the planting plan to the Owner's representative prior to starting construction.
- Topsoil hauled onto site shall be fertile, friable, natural loam topsoil, of uniform quality characteristic representing local soils which produce heavy growth of crops, grass or other vegetation. It shall be free of subsoil, clay lumps, brush, weeds, roots, stones, trash, or other matter toxic to plant growth.
- Topsoil shall be delivered in an unfrozen and non-muddy condition and shall be subject to approval by the Owner's representative.
- Plastic edging shall be used to separate all turf areas from planting beds. Edging shall be "Cobra Commercial Heavy Duty Grade" from Old Dutch Materials Co. or approved equal.
- All planting beds shall be prepared by killing off existing vegetation with Round-Up (or-equal) according to label directions. A pre-emergent herbicide shall be applied per label directions.
- Mulch 4" deep around trees and 4" deep in all shrub planting beds with shredded cypress mulch.
- All grass areas called out as "Seed/Sod" are to be planted and fertilized as follows:
SEEDING: Kansas Premium Fescue
FERTILIZER: Per Manufacturer's Specifications
- Rough grading shall be by the general contractor. This includes rough grading for berms. The Landscape Contractor shall be responsible for finished grading prior to grass installation and planting operations
- Fall planting season shall be September 1 thru end of October. Spring planting season shall be April 1 thru end of June. For grass seeding, fall season shall be September 1 thru mid of October. Spring season for seeding shall be from March 15 thru mid May.
- Materials shall be approved by the Owner's Representative before start of work. Materials and seeding may be rejected at any time during the installation.
- Prior to acceptance, the plantings and grass areas shall be maintained watered and kept clean and weed free by the Landscape Contractor.
- Guarantee for spring planted plants shall be thru mid August. Guarantee for fall planted plants shall be thru mid May.
- At the end of the guarantee period the Owner's Representative and Landscape Contractor shall meet to review for replacements. Dead plants and those not in a vigorous, thriving condition shall be replaced as originally specified in the following planting season. There shall be no additional cost to the Owner for replacements except due to vandalism. Grass areas not acceptable shall be reseeded or resodded immediately in the same planting season or if weather conditions require the following season



IRRIGATION SYSTEM

—Irrigation - Water for establishment and maintenance of plant materials on this project will be provided by an irrigation system. It is intended that the Irrigation Contractor provide the design, all labor, materials and equipment required to construct a complete and operational automatic irrigation system.

—Then irrigation bid is to be included in the base bid of the landscape bid.

—The automatic irrigation system shall be designed to irrigate all new grass and planted areas. Care should be taken in the irrigation design to ensure that no water is sprayed on the building, fences, walls, walkways or paved areas.

—Water for irrigation to come from main water supply to building with new meter.

—Prior to installation, the General Contractor shall submit for approval to the Architect an irrigation layout plan, irrigation equipment details, and a booklet containing catalog cuts, performance charts and technical information in sufficient detail to determine system suitability for this project.

—The irrigation system shall be equipped with moisture-sensing devices or automatic rain shut-off devices as well as a freeze detector.

PLANT LIST


KEY	QTY.	COMMON NAME	BOTANICAL NAME	SIZE	CONDITION
TREES					
RSM	1	RED SUNSET MAPLE	Acer rubrum 'Red Sunset'	3" to 3 1/2" cal.	Balled-in-Burlap
LE	2	LACEBARK ELM	Ulmus parvifolia	3" to 3 1/2" cal.	Balled-in-Burlap
ZEL	4	ZELKOVA	Zelkova serrata	3" to 3 1/2" cal.	Balled-in-Burlap
RDB	2	REDBUD	Cercis canadensis	1 1/2" to 2" cal.	Balled-in-Burlap
SSC	2	SPRING SNOW CRAB	Malus species (fruitless)	2" to 2 1/2" cal.	
SHRUBS					
MJJ	8	MINT JULEP JUNIPER	Juniperus chinensis	5 gal.	Container
CPR	41	CARPET ROSE	Rosa 'Carpet' (Red)	5 gal.	Container
WGB	19	WINTERGEM BOXWOOD	Microphylla koreana	5 gal.	Container
OTHER					
DAY	30	DAYLILLY	Heemerocallis Sp.	1 gal.	Container

***IF THERE ARE ANY DISCREPANCIES IN PLANT QUANTITIES, THE PLANTING PLAN WILL DICTATE.

LANDSCAPE CALC'S

LANDSCAPE YARD REQUIRED: 348' X 10' = 3,480 S.F.
 LANDSCAPE YARD SHOWN: 3480 S.F.
 STREET YARD TREES REQUIRED: 3480/500 = 7 SHADE TREES
 STREET YARD TREES PROVIDED: 5 NEW SHADE TREES
 4 ORNAMENTAL TREES
 PARKING LOT TREE REQUIRED: 3520 = 2 TREES
 PARKING LOT TREES SHOWN: 2 TREES
 PARKING LOT SCREENING: AS SHOWN
 LANDSCAPE BUFFERS REQUIRED: NONE

MAPP 09/2/12
 DP-23





Wichita-Sedgwick County Metropolitan Area Planning Department

November 8, 2013

Cambridge Market, LLC
Attn: Fred L. Hanley
439 N. Belmont
Wichita, KS 67208

Lauren Irwin
9747 East 21st Street North, #101
Wichita, KS 67206

RE: CUP2013-00035 – Amendment to Parcel 2 of the Hanley Commercial Community Unit Plan (CUP), DP-213 to permit a “nightclub in the city” on property generally located on the southeast corner of East 21st Street North and North Webb Road (9747 East 21st Street North).

Dear Ladies and Gentlemen:

At its regular meeting on November 7, 2013, the Wichita - Sedgwick County Metropolitan Area Planning Commission (MAPC) considered the above captioned request. The action of the MAPC was to APPROVE the request subject to the following conditions:

1. The language contained in General Provision 20, Parcel Number 2 shall be amended as follows: Proposed uses: same as Parcel Number 1 except that the prohibition against a “drinking establishment” is removed and a “nightclub in the city” or “entertainment establishment in the city” is permitted; and those buildings on the eastern portion of the parcel with exposure to the drainage way will be designed in such a way that the side facing the drainage way is finished in a similar manner as the front of the building. No outside loudspeakers or outdoor entertainment associated with the “nightclub in the city” or “entertainment establishment in the city” is permitted.
2. The number of off-street parking spaces provided by the CUP DP-213 shall comply with Code required minimums.
3. The “nightclub in the city” or “entertainment establishment in the city” shall be operated in compliance with all applicable codes, licenses or regulations, including, but not limited to: building, fire, health or zoning codes.
4. The transfer of title of all or of any portion of the land located within CUP DP-213 does not constitute a termination of the plan or any portion thereof, but said plan shall run with the land and be binding upon the present owners, their successors and assigns, unless amended.
5. The applicant shall submit four revised copies of the CUP to the Metropolitan Area Planning Department within 60 days after final approval of this case, or the request shall be considered

denied and closed.


Property owners opposed to the application may file with the City Clerk signed written protest of the MAPC's recommendation. (Unsigned e-mails are not considered to be legal protests.) To be effective, the protest must be filed within 14 days of the MAPC's action or by 5:00 p.m. on November 21, 2013. Property owners may file written protest petitions on land use related items heard by the MAPC. In order to be considered a "valid" petition towards a three-quarters majority vote requirement, the signatures must reflect the correct and entire ownership of the property, the property must be at least partially located within 200 feet of the property for which the application was filed, and must be submitted to the City Clerk within 14 days of the conclusion of the MAPC hearing, by November 21, 2013, at 5:00 p.m.

If there are not any protests for this application, the action of the MAPC will be final. If there protests, this application will be scheduled to be forwarded to the City Council for consideration at its regular meeting on Tuesday, December 10, 2013. If necessary, this meeting will be held in the City Council Chambers, First Floor, City Hall, 455 N. Main, Wichita, Kansas.

NOTICE: The public hearing on planning items is conducted by the MAPC under provisions of State Law. Adopted policy is that the City Council will not take additional testimony on zoning related applications and other issues for which the MAPC has held a public hearing. However, interested parties may file a written statement with the City Clerk by 5:00 p.m. on the Wednesday preceding this meeting, providing new facts on the issue or alleging an unfair hearing. The Council will determine from such statements whether to return the issue to the MAPC for reconsideration or to reverse their recommendation.

This is a reminder that the zoning notification signs should now be removed from the property. If you have any questions concerning this application, please contact our office at 268-4421.

Sincerely,



Dale Miller
Current Plans Manager
Current Plans Division

Copies to: WCC II, Pete Meitzner, Mail Stop 1-13
N.A. II, Megan Buckmaster, Mail Stop 1-135
Cambridge/Lexington HOA, Darlene Morrow, P.O. Box 75511, Wichita, KS 67275
Bent Tree HOA, Melissa Mathes, P.O. Box 9306 Bent Tree, Wichita, KS 67226
Greenleaf HOA, Chuck Bair, P.O. Box 780151, Wichita, KS 67278
Legacy Park Master HOA, 150 N. Market, Wichita, KS 67202
Peppertree HOA, Harvey Menehan, 9006 Peppertree Cir., Wichita, KS 67226
Plumthicket HOA, Bill Lee, 2542 Plumthicket Ct., Wichita, KS 67226
Remington Place Master HOA, Terry Fry, 414 Gateway Street, Wichita, KS 67230
Wilson Estates Master HOA, 150 North Market, Wichita, KS 67202
Tallgrass East HOA, 2530 N. Fox Run Ct., Wichita, KS 67226
Jeff Van Zandt, City Law, Mailstop 1-134
Julianne Kallman, Engineering, Mail Stop 1-71