


VIA CHRISTI-WEST CAMPUS

PLANNED UNIT DEVELOPMENT PUD #27



LEGAL DESCRIPTION:

Via Christi - West Campus Addition, Sedgwick County, Kansas.

GENERAL PROVISIONS:

- Total Net Land Area: 4,803,513 sq. ft. or 110.27± acres
- Maximum Building Coverage: 1,441,054 sq. ft. or 30 percent
- Maximum Gross Floor Area: 1,921,405 sq. ft. or 40 percent
- Parking shall be provided in accordance with Article IV of the Unified Zoning Code, unless otherwise specified in the parcel descriptions.
- Setbacks are as indicated on the P.U.D. drawing, or as specified in the parcel descriptions. If contiguous parcels are to be developed under the same ownership, setbacks between those parcels will not be required.
- A Drainage Plan shall be submitted to City Engineering for approval at the time of platting, along with any required guarantees.
- Improvements and Guarantees for arterial street improvements shall be determined at the time of platting.
- Access Controls shall follow the guidelines of the access management policy. All final access control locations shall be determined at the time of platting.
- Signs shall be in accordance with the Sign Code of the City of Wichita for the "LC" district with the following conditions:
 - Two signs shall be allowed along 21st St. N. with a maximum area of 600 sq. ft. with no single sign exceeding 300 sq. ft. Seven signs shall be allowed along 151st St. W. with a maximum area of 1,800 sq. ft. with no single sign exceeding 300 sq. ft.
 - All freestanding signs must be monument type signs. Hospital signage along either 21st St. N. or 151st St. W. shall have a maximum height of 30 feet. Multi-tenant signs shall have a maximum height of 20 feet. Single tenant signs shall have a maximum height of 15 feet.
 - As the frontage develops along the arterial roadways, monument type signs shall be spaced a minimum of 150 feet apart, irrespective of how land is leased or sold.
 - Electronic message signs shall be permitted. This sign shall not permit animated flashing or moving images, and graphics changes will be restricted to one change per second or slower.
 - Portable or off-site signs are not permitted.
 - Window display signs are limited to 25% of the window area.
 - Within this development unlimited 24 square-foot directional signage, limited to six feet in height, and consistent with submitted elevations, shall be permitted. Also, five internal monument signs shall be permitted within the development. The five internal monument signs shall be limited to 50 square feet in area, shall be limited to 10 feet in height, shall not be within 200 feet of an arterial right-of-way, and shall be consistent with submitted elevations.
- All exterior lighting shall be shielded to direct light disbursement in a downward direction.
- All parcels shall share similar or consistent parking lot lighting elements (i.e., fixtures, poles, and lamps, etc.).
 - Light poles for the hospital and MOB parking lots shall not exceed 30 feet in height, excluding the base. No light pole for the hospital or MOB parking lot shall exceed a 20 foot height when located within 300 feet of residential zoned property. Light poles for all other buildings shall not exceed 24 feet in height, excluding the base. Base height for light poles shall not exceed a maximum height of 3 feet.
- Utilities shall be installed underground on all parcels.
- Landscape for this site shall be required as follows:
 - Development of all parcels within the P.U.D. shall comply with the Landscape Ordinance of the City of Wichita.
 - A landscape plan shall be prepared by a Kansas Landscape Architect for the above referenced parcels, indicating the type, location, and specifications of all plant material. This plan shall be submitted to the Planning Department for their review and approval prior to issuance of a building permit.
 - A financial guarantee for the plant material approved on the landscape plan for that portion of the P.U.D. being developed shall be required prior to issuance of an occupancy permit, if the required landscape has not been planted.
- Screening to adjacent residentially zoned property shall be a combination of the landscape ordinance and/or maintaining the existing vegetation.
 - Any portion of this P.U.D. that is developed adjacent to residentially zoned property shall have a 30 foot screening buffer for screening purposes.
 - If the adjacent property is rezoned to a use greater than residential, the 30 foot screening buffer shall be waived.
 - All screening within the 30 foot buffer shall be maintained by the owner of the property.
- Rooftop mechanical equipment shall be screened from ground level view per Unified Zoning Code.
- Trash receptacles shall be appropriately screened with walls that are of a pattern and color consistent with the building walls to reasonably screen them from ground view.
- Site plans and building elevations for all parcels shall be submitted and approved by the Director of Planning prior to the issuance of building permits.
- Cross-lot circulation agreements shall be required at the time of platting to assure internal vehicular movement between parcels within the P.U.D.
- A plan for a pedestrian walk system shall be submitted and approved by the Director of Planning prior to the issuance of building permits. Said sidewalk system shall link proposed buildings within the subject property to future sidewalks along the arterial streets. Said walk system shall be reinforced by landscaping, lighting, and seating areas.
- Fire lanes shall be in accordance with the Fire Code of the City of Wichita. No parking shall be allowed in said fire lanes, although they may be used for passenger loading and unloading. The Fire Chief or his designated representative shall review and approve the location and design of all fire lanes. Fire hydrant installation and paved access to all building sites shall be provided for each phase of construction per City standards.
- No parcel within this P.U.D. shall allow the use of adult entertainment establishments, correctional placement residences, private clubs, taverns, and drinking establishments. Restaurants that serve liquor can be developed for passenger loading and unloading. The Fire Chief or his designated representative shall review and approve the location and design of all fire lanes. Nightclub in the County may be allowed only as an accessory use to a restaurant, subject to the Supplemental Use Regulations in Article III-D.5.f.
- Amendments, adjustments or interpretations to this P.U.D. shall be done in accordance with the Unified Zoning Code.
- The Transfer of title of all or any portion of land included within the P.U.D. (or any amendments thereto) does not constitute a termination of the plan or any portion thereof, but said plan shall run with the land and be binding upon present owners, their successors and assigns.
- The development of this property shall proceed in accordance with the development plan as recommended for approval by the Planning Commission and approved by the Governing Body, and any substantial deviation of the plan, as determined by the Zoning Administrator and the Director of Planning, shall constitute a violation of the building permit authorizing construction of the proposed development.
- Any major changes in this development plan shall be submitted to the Planning Commission and to the Governing Body for their consideration.
- All property included within the P.U.D. shall be platted within one year after approval of this P.U.D. by the Governing Body, or the case shall be considered denied and closed.
- Prior to publishing the ordinance establishing the zone change, the applicant(s) shall record a document with the Register of Deeds indicating that this tract (referenced as PUD2007-04) includes special conditions for development on this property.

APPROVED PUD
9/11/25 PUD2025-00018
1 of 4

BENCHMARK:

SW 1/4 CORNER, 3/4" IRON WITH SEDGWICK COUNTY CAP SET IN CONCRETE, ELEV. 1367.00 (NAVD 88) W 1/4 CORNER, 3/4" IRON WITH SEDGWICK COUNTY CAP SET IN CONCRETE, ELEV. 1365.39 (NAVD 88)

PARCEL 1

- Net Area: 3,266,615 sq. ft. or 75.04 acres
- Maximum Building Coverage: 979,985 sq. ft. or 30 percent
- Maximum Gross Floor Area: 1,306,646 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall allow the Hospital Structures to be a maximum of 100 feet in height, the Medical Office Building (associated with the hospital) to be a maximum of 65 feet in height, and no other building shall exceed 50 feet in height.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: Hospital, Medical Offices, Medical Uses, General Office, Retail Uses related to Medical (ie: pharmacies, medical supply/uniform stores, prosthetics, florist, gift shop, Ambulance Facility, Helpad for Medical Uses, Hotel, Restaurants, Daycare, Senior Housing Facilities, Wellness Center, and Churches.

PARCEL 2

- Net Area: 672,131 sq. ft. or 15.4± acres
- Maximum Building Coverage: 201,639 sq. ft. or 30 percent
- Maximum Gross Floor Area: 268,853 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall allow the Hospital Structures to be a maximum of 100 feet in height, the Medical Office Building (associated with the hospital) to be a maximum of 65 feet in height, and no other building shall exceed 50 feet in height.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: Hospital, Medical Offices, Medical Uses, General Office, Retail Uses related to Medical (ie: pharmacies, medical supply/uniform stores, prosthetics, florist, gift shop, Ambulance Facility, Helpad for Medical Uses, Hotel, Restaurants, Daycare, Senior Housing Facilities, Wellness Center, and Churches.

PARCEL 3

- Net Area: 55,732 sq. ft. or 1.27± acres
- Maximum Building Coverage: 201,639 sq. ft. or 30 percent
- Maximum Gross Floor Area: 22,293 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 4

- Net Area: 66,000 sq. ft. or 1.51± acres
- Maximum Building Coverage: 19,800 sq. ft. or 30 percent
- Maximum Gross Floor Area: 26,400 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 5

- Net Area: 37,586 sq. ft. or 0.86± acres
- Maximum Building Coverage: 11,276 sq. ft. or 30 percent
- Maximum Gross Floor Area: 15,034 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 6

- Net Area: 46,754 sq. ft. or 1.07± acres
- Maximum Building Coverage: 14,026 sq. ft. or 30 percent
- Maximum Gross Floor Area: 18,702 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 7

- Net Area: 46,006 sq. ft. or 1.05± acres
- Maximum Building Coverage: 13,802 sq. ft. or 30 percent
- Maximum Gross Floor Area: 18,402 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 8

- Net Area: 46,644 sq. ft. or 1.07± acres
- Maximum Building Coverage: 13,993 sq. ft. or 30 percent
- Maximum Gross Floor Area: 18,658 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 9

- Net Area: 525,926 sq. ft. or 12.07± acres
- Maximum Building Coverage: 157,778 sq. ft. or 30 percent
- Maximum Gross Floor Area: 210,370 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum Number of Dwelling Units: 29 du/acre
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 10

- Net Area: 107,997 sq. ft. or 2.47± acres
- Maximum Building Coverage: 32,399 sq. ft. or 30 percent
- Maximum Gross Floor Area: 43,199 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PARCEL 11

- Net Area: 137,531 sq. ft. or 3.15± acres
- Maximum Building Coverage: 41,259 sq. ft. or 30 percent
- Maximum Gross Floor Area: 55,012 sq. ft. or 40 percent
- Floor Area Ratio: 40 percent
- Maximum building height shall be in accordance with the Wichita-Sedgwick County Unified Zoning Code for parcels developed in the "LC" zoning district.
- Setbacks: See Drawing
- Access Points: See Drawing
- Proposed uses: All permitted uses in the "Limited Commercial" zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #20.

PUD #27


VIA CHRISTI-WEST CAMPUS
PLANNED UNIT DEVELOPMENT



BAUGHMAN COMPANY
315 Ellis St. Wichita, KS 67211 316-262-7271
BaughmanCo.com

OCTOBER 30, 2025

VIA CHRISTI-WEST CAMPUS PLANNED UNIT DEVELOPMENT PUD-27



GENERAL PROVISIONS:

- Total Net Land Area: 4,803,513 sq. ft. or 110.27± acres
Reserves: 530,628 sq. ft. or 12.18± acres
- Maximum Building Coverage: 1,441,054 sq. ft. or 30 percent
Maximum Gross Floor Area: 1,921,405 sq. ft. or 40 percent
- Parking shall be provided in accordance with Article IV of the Unified Zoning Code, unless otherwise specified in the parcel descriptions.
- Setbacks are as indicated on the P.U.D. drawing, or as specified in the parcel descriptions. If contiguous parcels are to be developed under the same ownership, setbacks between those parcels will not be required.
- A Drainage Plan shall be submitted to City Engineering for approval at the time of platting.
- Improvements and Guarantees for arterial street improvements shall be determined at the time of platting.
- Access Controls shall follow the guidelines of the access management policy. All final access control locations shall be determined at the time of platting.
- Signs shall be in accordance with the Sign Code of the City of Wichita for the "LC" district with the following conditions:
 - Two signs shall be allowed along 21st St. N. with a maximum area of 600 sq. ft. with no single sign exceeding 300 sq. ft. Six signs shall be allowed along 151st St. W. with a maximum area of 1,800 sq. ft. with no single sign exceeding 300 sq. ft.
 - All freestanding signs must be monument type signs. Hospital signage along either 21st St. N. or 151st St. W. shall have a maximum height of 30 feet. Multi-tenant signs shall have a maximum height of 20 feet. Single tenant signs shall have a maximum height of 15 feet.
 - As the frontage develops along the arterial roadways, monument type signs shall be spaced a minimum of 150 feet apart, irrespective of how land is leased or sold.
 - Electronic message signs shall be permitted. This sign shall not permit animated, flashing or moving images, and graphics changes will be restricted to one change per second or slower.
 - Portable or off-site signs are not permitted.
 - Window display signs are limited to 25% of the window area.
 - Within this development unlimited 24 square-foot directional signage, limited to six feet in height, and consistent with submitted elevations, shall be permitted. Also, five internal monument signs shall be permitted within the development. The five internal monument signs shall be limited to 50 square feet in area, shall be limited to 10 feet in height, shall not be within 200 feet of an arterial right-of-way, and shall be consistent with submitted elevations.
- All exterior lighting shall be shielded to direct light disbursement in a downward direction.
- All parcels shall share similar or consistent parking lot lighting elements (i.e., fixtures, poles, and lamps, etc.).
 - Light poles for the hospital and MOB parking lots shall not exceed 30 feet in height, excluding the base. No light pole for the hospital or MOB parking lot shall exceed a 20 foot height when located within 300 feet of residential zoned property. Light poles for all other buildings shall not exceed 20 feet in height, excluding the base. Base height for light poles shall not exceed a maximum height of 3 feet.
- Utilities shall be installed underground on all parcels.
- Landscaping for this site shall be required as follows:
 - Development of all parcels within the P.U.D. shall comply with the Landscape Ordinance of the City of Wichita.
 - A landscape plan shall be prepared by a Kansas Landscape Architect for the above referenced landscaping, indicating the type, location, and specifications of all plant material. This plan shall be submitted to the Planning Department for their review and approval prior to issuance of a building permit.
 - A financial guarantee for the plant material approved on the landscape plan for that portion of the P.U.D. being developed shall be required prior to issuance of any occupancy permit, if the required landscape has not been planted.
- Screening to adjacent residentially zoned property shall be a combination of the landscape ordinance and/or maintaining the existing vegetation.
 - Any portion of this P.U.D. that is developed adjacent to residentially zoned property shall have a 30 foot screening buffer for screening purposes.
 - If the adjacent property is rezoned to a use greater than residential, the 30 foot screening buffer shall be waived.
 - All screening within the 30 foot buffer shall be maintained by the owner of the property.
- Rooftop mechanical equipment shall be screened from ground level view per Unified Zoning Code.
- Trash receptacles shall be appropriately screened with walls that are of a pattern and color consistent with the building walls to reasonably screen them from ground view.

PARCEL 1

- | | |
|--|---|
| A. Net Area: | 4,049,967 sq. ft. or 92.57± acres |
| B. Maximum Building Coverage: | 1,214,990 sq. ft. or 30 percent |
| C. Maximum Gross Floor Area: | 1,619,987 sq. ft. |
| D. Floor Area Ratio: | 40 percent |
| E. Maximum building height shall allow the Hospital Structures to be a maximum of 100 feet in height, the Medical Office Building (associated with the hospital) to be a maximum of 65 feet in height, and no other building shall exceed 50 feet in height. | |
| F. Setbacks: | See Drawing |
| G. Access Points: | See Drawing |
| H. Proposed uses: | Hospital, Medical Offices, Medical Uses, General Office, Retail Uses related to Medical (ie: pharmacies, medical supply/uniform stores, prosthetics, florist, gift shop, Ambulance Facility, Helpaid for Medical Uses, Hotel, Restaurants, Daycare, Senior Housing Facilities, Wellness Center, and Churches. |

PARCEL 2

- | | |
|--|---|
| A. Net Area: | 753,546 sq. ft. or 17.30± acres |
| B. Maximum Building Coverage: | 226,064 sq. ft. or 30 percent |
| C. Maximum Gross Floor Area: | 301,419 sq. ft. |
| D. Floor Area Ratio: | 40 percent |
| E. Maximum building height shall allow the Hospital Structures to be a maximum of 100 feet in height, the Medical Office Building (associated with the hospital) to be a maximum of 65 feet in height, and no other building shall exceed 50 feet in height. | |
| F. Setbacks: | See Drawing |
| G. Access Points: | See Drawing |
| H. Proposed uses: | Hospital, Medical Offices, Medical Uses, General Office, Retail Uses related to Medical (ie: pharmacies, medical supply/uniform stores, prosthetics, florist, gift shop, Ambulance Facility, Helpaid for Medical Uses, Hotel, Restaurants, Daycare, Senior Housing Facilities, Wellness Center, and Churches. |

RESERVES

Reserve "A" is hereby reserved for bridges, entry features, entry monuments, signage, landscaping, sidewalks, drainage purposes, floodway, and utilities as confined to easement. Reserve "B" is hereby reserved for bridges, entry features, entry monuments, signage, landscaping, sidewalks, drainage purposes, and floodway. Reserves "C" and "D" are hereby reserved for open space, landscaping, drainage purposes, utilities, streets and signage. Reserves "A" and "B" shall be owned and maintained by the owner of Lot 1, Block A, until such time as the appropriate governing body elects to assume the responsibility for maintenance and improvements to the drainage. No buildings shall be constructed on or placed within said floodways, nor shall any fill, change of grade, creation of channel, or any other work be carried on without the permission of the Engineer for said appropriate governing body. Reserves "C" and "D" shall be owned and maintained by the owner of Lot 1, Block A.

LEGAL DESCRIPTION:

The SW 1/4 of Sec. 2, Twp. 27-S, R-2-W of the 6th P.M., Sedgwick County, Kansas EXCEPT therefrom the following described tract: Beginning at the SW corner of said SW 1/4; thence N01°15'00"W along the west line of said SW 1/4, 665.57 feet; thence N88°38'01"E parallel with the south line of said SW 1/4, 1110.00 feet; thence S01°15'00"E parallel with the west line of said SW 1/4, 665.57 feet to a point on the south line of said SW 1/4; thence S88°38'01"W along the south line of said SW 1/4, 1110.00 feet to the point of beginning, all being subject to road rights-of-way of record.

BENCHMARK:

SW 1/4 CORNER, 3/4" IRON WITH SEDGWICK COUNTY CAP SET IN CONCRETE, ELEV: 1367.00 (NAVD 88)
W 1/4 CORNER, 3/4" IRON WITH SEDGWICK COUNTY CAP SET IN CONCRETE, ELEV: 1365.39 (NAVD 88)

REVISIONS:

Drawn: October 9, 2007
Approved by County Commission: December 19, 2007
Revised per Administrative Adjustment: July 21, 2008
Revised per Administrative Adjustment: June 9, 2009

APPROVED PUD

MAPC PLAN 15, 2007 DM


PLANNED UNIT DEVELOPMENT

WAPD 1/2

PUD-27

VIA CHRISTI-WEST CAMPUS
PLANNED UNIT DEVELOPMENT

Baughman Company, P.A.
315 Blu St. Wichita, KS 67211 P 316-262-7271 F 316-262-6149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE



SCALE: 1" = 150'


LAYOUT NOTES

- Contractor shall be required to provide notice to Kansas One Call at 587-2470 a minimum of three (3) working days prior to any excavation or work adjacent to utilities.
Kansas One Call 1-800-DIG-SAFE
- The Contractor must notify the following in case of an emergency:


Kansas Gas Service (Gas)	1-888-483-4950
Black Hills Energy (Gas)	1-800-303-0357
Wester Energy (Electric)	383-8650
Cox Communications (Telecommunication)	282-4270
AT&T (Telecommunication)	288-4563
City of Wichita Water Dept. (Water)	288-4563 or 288-4906
City of Wichita Sewer Maint. (San. Sewer)	288-4024 or 282-6000
City of Wichita Storm Sewer Maint. (Storm Sewer)	288-4090
City of Wichita Traffic Maint. (Traffic Control)	288-4034 or 288-4203
Conoco Pipeline Co. (Petroleum)	1-800-231-2551
Williams Pipeline Co. (Petroleum)	or 1-800-324-9898
Phillips Pipeline Co. (Petroleum)	1-800-768-8230
- Existing utilities and their locations, as shown on the plans, represent the best information obtainable for design. Location information has been obtained from the various utility companies and is either from company record drawings or company provided field locations. The Contractor will be required to work around existing utilities which do not conflict with proposed construction.
- Traffic affected by demolition on this project shall be handled in accordance with the latest edition of the Manual on Uniform Traffic Control Devices (MUTCD).
- The Contractor shall provide appropriate signage throughout the sequence of construction clearly stating where construction entrances are.
- The Contractor shall take all necessary precautions to protect the general public during the construction and demolition process. This may include the use of fences and signage.

LAYOUT


- Signage and striping shall be installed in accordance with Local City Specifications and Codes. Striping shall be painted markings in conformance with the latest edition of the Standard Specifications for State Road and Bridge Construction by the Kansas Department of Transportation.
- Dimensions shown are to face of curb or edge of pavement unless otherwise noted.




LONGITUDINAL JOINT DETAIL (L.J.)




CONTRACTION JOINT DETAIL (C.J.)




SAW JOINT DETAIL "A"




SAW JOINT DETAIL "B"




1 5" CONCRETE DRIVEWAY PAVEMENT
NOT TO SCALE




2 CURB & GUTTER SECTION
NOT TO SCALE




3 TYP. PATTERN IN WALK
NOT TO SCALE



4 TYP. CONC. WALK SECTION
NOT TO SCALE



5 SIDEWALK JOINTS
NOT TO SCALE



6 EXPANSION JOINT (E.J.)
NOT TO SCALE

SITE DIMENSION PLAN

Scale 1" = 20'-0"

APPROVED

PROD #27 Site + Ped Circ Plan
Per #17 + #19
Date: 2-6-18 SK

DATE:
CONSTRUCTION SET
01.08.2018
CITY COMMENTS
02.02.2018

Alloy
ARCHITECTURE

alloy architecture.com
3500 N. ROCK RD. BLDG. 500
WICHITA, KS 67226
P: 316.634.1111
F: 316.634.1014



PROJECT NUMBER
17110

The drawing and all information herein is the exclusive property of Alloy Architecture and is not to be copied or used in any way without the express written consent of Alloy Architecture. All drawings, specifications, ideas, designs and arrangements appearing herein constitute the original and unpublished work of the architect.

Copyright © 2018
Alloy Architecture

Via Christi
HEALTH
St. Teresa Clinic Consolidation
14700 W. St. Teresa
Wichita, Kansas

SHEET

C1.0

OF

BAUGHMAN COMPANY
315 E. 11th St. Wichita, KS 67211 316-262-7271
BaughmanCo.com