

NORTHGATE COMMERCIAL 2ND ADDITION


WICHITA, SEDGWICK COUNTY, KANSAS

State of Kansas) SS We, Baughman Company, P.A., Surveyors in
Sedgwick County) aforesaid county and state do hereby certify that we have surveyed and
platted "NORTHGATE COMMERCIAL 2ND ADDITION", Wichita, Sedgwick County,
Kansas and that the accompanying plat is a true and correct exhibit of
the property surveyed, described as follows: That part of the SE1/4 of
Sec. 13, Twp. 26-S, R-1-W of the 6th P.M., Sedgwick County, Kansas
described as follows: Beginning at the intersection of the east line of said
SE1/4 with the easterly extension of the north line of Northgate
Commercial Park 1st Addition, an Addition to Wichita, Sedgwick County,
Kansas; thence westerly along the extended north line of said Northgate
Commercial Park 1st Addition with a calculated bearing of N89°09'05"W,
660.67 feet to the SE corner of Lot 5, Block B, Northgate Addition,
Wichita, Sedgwick County, Kansas; thence N00°02'41"E along the east line
of said Block B, 440.37 feet to the NE corner of Lot 1 in said Block B,
said NE corner also being on the south right-of-way line of 55th St. N.
as dedicated in said Northgate Addition; thence S89°05'14"E along the
south right-of-way line of said 55th St. N., and as extended easterly,
660.34 feet to a point on the east line of said SE1/4; thence
S00°00'00"E along the east line of said SE1/4, 439.63 feet to the point
of beginning, all being subject to road rights-of-way of record.

Existing public easements and dedications
being vacated by virtue of K.S.A. 12-512(b).

Baughman Company, P.A.

Michael G. Conrey
Michael G. Conrey



Know all men by these presents that we,
the undersigned, have caused the land in the surveyors certificate to be
platted into Lots, a Block, and a Street to be known as "NORTHGATE
COMMERCIAL 2ND ADDITION", Wichita, Sedgwick County, Kansas. The utility
easement is hereby granted as indicated for the construction and
maintenance of all public utilities. The drainage and utility easements are
hereby granted as indicated for drainage purposes and for the
construction and maintenance of all public utilities. The wall easement is
hereby granted as indicated for the construction and maintenance of a
private screening wall and utility main lines and service lines shall be
allowed to cross this easement. Access controls shall be as depicted on
the face of the plat and are hereby granted to the City of Wichita,
Kansas.

R & R Realty, LLC,
a Kansas limited liability company

Jay W. Russell
Jay W. Russell

Ritchie Associates, Inc., Manager


Rob Ramseyer
Rob Ramseyer

We, the undersigned holders of a mortgage on
the above described property, do hereby consent to this plat of "NORTH-
GATE COMMERCIAL 2ND ADDITION", Wichita, Sedgwick County, Kansas.

Legacy Bank

Steve Gegen, VP
STEVE GEGEN

State of Kansas) SS The foregoing instrument acknowledged be-
Sedgwick County) fore me, this 25th day of March, 2008, by Steve Gegen,
Vice President of Legacy Bank, on behalf of the bank.



Lisa A. Piska, Notary Public

My App't. Exp. 12-2-2009

FINAL TRACING REC'D

3-25-08

SUB 2007-107

This plat of "NORTHGATE COMMERCIAL 2ND
ADDITION", Wichita, Sedgwick County, Kansas has been submitted to and
approved by the Wichita-Sedgwick County Metropolitan Area Planning
Commission, Wichita, Kansas.

Dated this _____ day of _____,
Wichita-Sedgwick County Metropolitan Area Planning Commission

M. S. Mitchell, Chair

John L. Schlegel, Secretary

This plat approved and all dedications
shown hereon accepted by the City Council of the City of Wichita,
Kansas, this _____ day of _____, 2008.

Carl Brewer, Mayor

Karen Sublett, City Clerk

Reviewed in accordance with K.S.A. 58-2005
on this _____ day of _____, 2008.

Tricia L. Robello, L.S. #1246
Deputy County Surveyor
Sedgwick County, Kansas


Entered on transfer record this _____ day
of _____, 2008.

Don Brace, County Clerk

State of Kansas) SS This is to certify that this plat has been
Sedgwick County) filed for record in the office of the Register of Deeds, this _____ day
of _____, 2008 at _____ o'clock _____ M.; and is duly recorded.

Bill Meek, Register of Deeds

Tanya Buckingham, Deputy



= #4 REBAR W/ "BAUGHMAN" CAP (FOUND)
△ = #6 REBAR W/ "BARBER" CAP (FOUND)
□ = #6 REBAR W/ ILLEGIBLE CAP (FOUND)

(M) = MEASURED
(P) = PLATTED
(D) = DESCRIBED
(C) = CALCULATED
(C-P) = CALCULATED PER
PLATTED INFO.

NOTE:
A DRAINAGE PLAN HAS BEEN DEVELOPED FOR THIS SUBDIVISION AND IS
ON FILE WITH THE CITY OF WICHITA, KANSAS. DRAINAGE INTENT SHALL
REMAIN AS DEPICTED OR AS MODIFIED WITH THE APPROVAL OF THE CITY
ENGINEER OF THE CITY OF WICHITA, KANSAS. NO OBSTRUCTIONS WHICH
IMPEDE THE FLOW OF THIS DRAINAGE PLAN SHALL BE ALLOWED.