




PAULA AVE.
NL. HENDRYX AVE. TO SL. UNIVERSITY AVE.
TYPICAL SECTIONS of 30' ASPHALTIC CONCRETE PAVEMENT




TYPICAL SECTION WITH STANDARD CROWN




TYPICAL SECTION WITH ALTERNATE CROWN




STEEL PATTERN



STEEL PATTERN




STANDARD SECTION OF COMBINED CURB & GUTTER



STANDARD SECTION OF ROLL-TYPE CURB & GUTTER

GENERAL NOTES
1. CONTRACTION JOINTS MAY BE CONSTRUCTED IN COMBINED CURB AND GUTTER BY SAWING WITH AN APPROVED CONCRETE SAW. THE SAW CUT SHALL EXTEND 2-1/2" BELOW THE SURFACE OF THE GUTTER AND CURB. SAWED CONTRACTION JOINTS SHALL HAVE A MAXIMUM SPACING OF 10' AND BE FILLED WITH A SPECIFIED JOINT FILLER, SUCH THAT THE JOINT IN THE GUTTER SECTION WILL BE COMPLETELY FILLED.


CITY OF WICHITA, KANSAS
Department of Public Works - Engineering Division
R. W. Linn City Engineer
Date: SEPT. 1972 Project No. DAKS558018



Survey
 Plan
 City Engineer
 City Engineer
 City Engineer

B.M. 141.55 CITY STD. S.W. U.S. 54 & TYLER.
 B.M. 143.06 R.R. SPIKE E.S. R.R. N.W. BELVIEW & TYLER.
 B.M. 143.32 R.R. SPIKE N.W. SIDE TEL. POLE & BYRON & 20'E. TYLER.
 B.M. 139.20 R.R. SPIKE E.S. R.R. S.W. UNIVERSITY & TYLER.
 B.M. 141.00 1/4" N.W. COR. DRWY. 450 S. EVERGREEN.
 B.M. 144.54 1/4" N.W. COR. STEP AT 520 EVERGREEN.

N
 SCALE 1" = 20'



"EARTHWORK QUANTITIES"	
EXCAVATION	COMPACTED FILL
32496 cy	4412 cy
+10% 325	+10% 441
3574 cy	4853 cy

NOTE: Excess Fill Material from University Ave. to be stock piled on this project for Compacted & Loose Fill work necessary to complete this project. Prop. Owner to have any dirt not used on project. Contractor to contact prop. owner about disposal of Material.

PAULA AVE.
 N.L. Hendryx Ave. to S.L. University Ave.
 R.W. Linn City Engineer
 City of Wichita
 PR. NO. DAKS 568018 Date

2 of 5

