
ROSEBERRY COURT PARKING COURT

SERVING LOTS 21 THROUGH 36, BLOCK J, PLANEVIEW SUBDIVISION NO. 1

N


Scale 1" = 80'



IMPROVEMENT DISTRICT MAP

N

Scale: 1" = 1000'




VICINITY MAP

ROBERT A. HARRINGTON LICENSED 9424 KANSAS PROFESSIONAL ENGINEER

PROJECT NO.	472-76-245-81360-000-000-001 818-76-245-50209-000-000-001
CITY OF WICHITA	M. E. LINDEBAK — CITY ENGINEER
LANDCO ENGINEERING	CONSULTANT ENGINEER

B.M. El. 107.61 S-rim MH at Sta. 1+28, 18' R.
B.M. El. 105.99 TC E-end Return SE-corner Intersection
Roseberry St. & Roseberry Court



NOTE:
3" Asphalt Curb Constructed with this Project shall not be paid for Directly, but shall be considered Incidental to the cost of the S.Y. of 5" Asphalt Pavement placed.

EARTHWORK:

EXCAVATION	316.5 C.Y.	COMPACTED FILL (95%)	229.9 C.Y.
+10%	31.7 C.Y.	+10%	23.0 C.Y.
TOTAL	348.2 C.Y.	TOTAL	252.9 C.Y.

ROBERT A. HAGUEWOOD LICENSED 9424 KANSAS PROFESSIONAL ENGINEER

ROSEBERRY COURT PARKING COURT
Serving Lots 21 through 36 inclusive, Block J, Planeview Sub. No. 1
Project No: 472-76-245-81360-000-000-001
813-76-245-5C209-000-000-001
CITY OF WICHITA M. E. LINDEBAK CITY ENGINEER
LANDCO ENGINEERING CONSULTANT ENGINEER
BOOK 3TT DRAWN BY RH DATE 6/84


2/4

FILMED FROM THE BEST AVAILABLE COPY

3/4

5" ASPHALTIC CONCRETE PAVEMENT w. 3" BITUMINOUS BASE TYPICAL TRANSVERSE SECTION

Scale 1" = 5'





NOTE:

1) A tack coat of emulsified asphalt (SC-1H or CSS-1H) shall be applied at an approximate rate of 0.05 gallons per square yard between each lift of asphaltic material.

2) Construction Joints in each lift shall be staggered a minimum of one (1) foot from joints in preceding lifts.

BUMPER BLOCK & PARKING STALL DETAIL






NOTE:

1) The Contractor Shall Install 38 Precast Concrete Bumper Blocks as Shown. The Bumper Blocks Shall be six-feet in Length, Seven to Eight inches Wide at the Base, Approximately Three Inches Wide at the Top, and Five to Six inches in Overall Height, with a Sloping Taper from about Center Height to the Top. Concrete used in Manufacture Shall be Designed for a Compressive Strength to Exceed 3000 psi, and Units to be Reinforced full Length with One or More Steel Reinforcing Rods. The Finish Shall be Smooth, and Off-White in Color. Each Bumper Block Shall have a Hole for Steel Anchor Pins Located near each End, of 5/8" or 3/4" Diameter.

2) Stall Lines shall be painted 6" in width. Paint used shall meet City of Wichita Traffic Operations and Maintenance Division Specification for Heated Rapid Dry Pavement Marking Paint.




DETAIL: 3" ASPHALT CURB
OTHER SUITABLE CURB SECTION MAY BE USED WITH PERMISSION OF FIELD ENGINEER

ROBERT A. HARRINGTON LICENSED 9424 KANSAS PROFESSIONAL ENGINEER

ROSEBERRY COURT PARKING COURT
472-76-245-81360-000-000-001
818-76-245-50209-000-000-001

3/4

FILMED FROM THE BEST AVAILABLE COPY



TOTAL EXC. 316.5 C.Y.

ROSEBERRY COURT
SERVING LOTS 21-36, inclusive, Block J
Planeview Sub. No. 1
472-76-245-81360-000-000-001
810-76-245-50209-000-000-001

FILMED FROM THE BEST AVAILABLE COPY
3 8 4 3 3 0