


BM - 148.89 SW cor conc porch No NE cor Zimmerly & Paige
 BM - 141.19 Top curb NL Zimmerly & E. curb Levitt
 BM - 139.81 in top NE cor E headwall RCBC on Rock Road - 400' S. of Turnpike.

NOTE TO CONTRACTOR
 This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

Note: no drives on No. 5th Street to 14+15.411. San. sewer is built.

Note: Paving Contractor is to cut ditch with 10:1 to 12:1 to drain intersections.

leave 3.5' openings in curb for future C.B.S.





Eastmoor Street

Estimate of Quantities - No drives figured.
 780.3 cu yds. Rph. conc. Pavt. = 722.0
 540.0 cu yds. Comb. cty. Pavt. = 500.0
 1071.6 cu yds. Excavation = 561.2
 1950.0 cu yds. Backfill = 266.7
 100 cu yds. 4" Dr. = 107.0

1 Drive.
 2.81 cu yds. Sep. 4"
 112.4 cu yds. Sep. 6"
 87.0 cu yds. 4" Dr.
 40 cu yds. 4" Dr.

NOTICE: IS A PART OF
 S&W INTERSECTION @ BLACKWILL PROJ. NO. CIB-50
 NOT INCLUDED IN PRIVATE CONTRACT.
 (S&W IS NO SEPARATE PLAN IN R-50)

LEVITT DRIVE
 EL Eastmoor to EL Blackwill
 26-2-30AC
 CITY OF WICHITA, KANSAS
 B.E. SMITH CITY ENGINEER
 PRIVATE CONTRACT



Surveyed by James H. Lind
 11/10/12
 City Engineer
 Checked by J. Lind