

1. Class A-A' Concrete shall be used throughout this project. All reinforcing steel shall conform to A.S.T.M. Specifications.

2. Grading & Reconstruction of N. Abutment - Reconstruction shall be bid as a "Lump Sum" bid.

3. Contractor to provide & maintain proper barricades thru out reconstruction.

