


B.M. 117.41 "X" cut top S.E. wing wall
E. end canal bridge on 10th Street.

B.M. 118.32 "G" in Globe W. end radius
@ S.W. corner 10th & Hydraulic.



NOTE:

Remove sidewalk on north side from end
of bridge to Sta. 2+48 and Construct 4 ft.
sidewalk on property line to elevations shown.
Clear right-of-way, grade parkings & compact fill
for proposed sidewalk. Proposed sidewalk to be
constructed by others.

Adjust existing 2'x5' inlets
to match curb grade.



PROPERTY		CITY	
EXCAVATION	COMP. FILL	EXCAVATION	COMP. FILL
193 Cu.Yds.	92 Cu.Yds.	6 Cu.Yds.	1 Cu.Yd.
+10% 19 "	9 "	1 "	"
Totals 212 Cu.Yds.	101 Cu.Yds.	7 Cu.Yds.	1 Cu.Yd.
	290 "	Sub-Grade Modification	7 "
	391 Cu.Yds.		8 Cu.Yds.



1/2

General Notes:

1. Excess excavated material to be used on Murdock Street. Proj. C10-24
2. This project is to be coordinated with projects C10-10, C10-11, C10-12 and C10-24
3. Excavation from sidewalk project can be used for parking fill on all street projects.

10TH STREET
E.L. WICHITA DRAINAGE
CANAL to W.L. KANSAS
30' Conc. & Curb
B.E. SMITH CITY ENGINEER
CITY OF WICHITA KANSAS
Date: _____

Project No. C10-24