




BLOCK	LOT NO.	ELEVATION (M.S.L.)
1	2, 3	1382
1	1	1382
1	10, 11, 12, 13, 14, 15, 16, 17, 18, 19	1382.9
2	20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47	1382.5
7	1, 2, 3, 4, 5	1381
7	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16	1382.9
7	17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75	1382.4
7	76, 77, 78, 79, 80	1379
6	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12	1377

NOTE:
NO BUILDING PERMITS ARE TO BE ISSUED FOR LOTS 76, 77, 79 AND 80, BLOCK 7 AND FOR LOTS 12-21, 22, BLOCK 6, UNLESS THE LOWEST FLOOD OPENING CAN BE FURNISHED A MINIMUM OF ONE FOOT ABOVE THE BASE FLOOD ELEVATION OR IF THE CITY OF WICHITA HAS RECEIVED A LETTER OF MAP REVISION FROM FEMA WHICH WILL THEN ALLOW BUILDINGS TO BE CONSTRUCTED AT THE LOWEST OPENING.

ENCHARGED:
600 HAZ. IN GATE POST
60' S.W. OF THE S. COR.
ELEV. 1385.0 ONLY

DRAINAGE PLAN SAWMILL CREEK ADDITION

NOTE:
All storm water drain systems shown on this plan are designed to carry the 100 year frequency rainfall event. The Consulting Engineer may reduce the size of pipes to the 2 year frequency rainfall event during design provided that the street and lot grading allows for conveyance of the 100 year frequency rainfall event without damage to any properties located outside the street right-of-way. All calculations are based on the 100 year frequency rainfall event.