



STARR KEY ADDITION

CURVE DATA

Station	Curve	Radius	Length	Chord	Offset
Sta. 67+37.84	192' L	124' R	37' L	192' L	124' R
Sta. 77+92.12	192' L	124' R	37' L	192' L	124' R
Sta. 87+25.34	192' L	124' R	37' L	192' L	124' R

INDUSTRIAL

Notes:

- Grading Contractor shall Complete all roadway Excavation and Embankment in the vicinity of the Bridge prior to the construction of piers and abutments.
- Large Trees to be grubbed Sta. 65+00 to Sta. 90+00, 2-120' 1-90', 1-70', 2-60', 5-50', 13-40' Trees to be grubbed are marked thus. Spare all trees not marked. Total 24.

Scale: 1" = 40' Vert. 1" = 10'