

Stafford

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+50	0.00	148.11	0.00	278.51	0.00
1+00	0.00	152.69	0.00	63.15	0.00	341.66
1+12	0.00	131.47	0.00	159.70	0.00	501.36
1+50	0.00	94.21	26.73	101.38	26.73	602.74
2+00	29.07	12.63	68.03	10.44	94.76	613.18
2+50	44.56	0.51	21.40	0.51	116.16	613.70
2+63.37	41.86	1.56	57.95	3.09	174.11	616.79
3+00	43.58	2.99	83.53	4.16	257.64	620.95
3+50	46.63	1.50	93.25	1.85	350.89	622.80
4+00	54.08	0.50	102.89	0.55	453.79	623.35
4+50	57.05	0.09	15.91	0.02	469.70	623.37
4+57.49	57.60	0.06	100.26	0.06	569.96	623.43
5+00	71.78	0.00	151.71	0.00	721.67	623.43
5+50	93.36	0.00	154.41	0.00	876.08	623.43
6+00	75.56	0.00	40.22	0.00	916.31	623.43
6+14.13	80.60	0.00	80.79	0.00	997.10	623.43
6+42	75.93	0.00	22.70	0.00	1019.79	623.43
6+50	77.28	0.00	132.41	0.00	1152.20	623.43
7+00	65.73	0.00	36.93	0.00	1189.13	623.43
7+16.02	58.77	0.00	74.04	0.00	1263.18	623.43
7+50	59.26	0.00	106.48	0.00	1369.66	623.43
8+00	54.09	0.00	86.44	0.00	1456.10	623.44
8+50	38.58	0.00	28.49	1.45	1484.58	624.89
8+72.65	30.03	2.68	29.89	3.80	1514.47	628.69
9+00	28.99	4.83	52.17	15.42	1566.64	644.11
9+50	27.35	11.83	47.21	24.31	1613.85	668.42
10+00	23.64	14.42	35.38	13.88	1649.23	682.30
10+35.48	30.21	6.70	20.12	4.01	1669.35	686.31
10+52.98	31.88	5.68	19.68	4.44	1689.04	690.75
10+70.48	28.86	8.03	39.00	5.13	1728.04	695.88
11+00	42.49	1.35	42.78	0.58	1770.82	696.46
11+23.08	57.61	0.00	0.00	0.00	1770.82	696.46

Stoneybrook

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+19	133.69	0.00	48.78	0.00	48.78
0+31.39	78.90	0.00	48.72	0.00	97.50	0.00
0+50	62.48	0.00	54.00	0.00	151.50	0.00
0+73.21	63.17	0.00	59.36	0.15	210.86	0.15
1+00	55.18	0.26	47.12	1.09	257.98	1.24
1+25.56	44.60	1.52	0.00	0.00	257.98	1.24


Stafford Ct. (E)

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+19	97.51	0.00	19.31	0.00	19.31
0+26	51.43	0.00	40.94	0.27	60.25	0.27
0+50	40.68	0.61	36.71	1.44	96.96	1.71
0+76.21	34.95	2.35	28.66	3.35	125.61	5.06
1+00	29.99	5.71	25.58	8.11	151.20	13.17
1+25.56	23.90	12.53	21.94	11.30	173.14	24.47
1+50	24.57	12.44	46.26	22.99	219.40	47.47
2+00	25.39	12.39	46.83	22.71	266.23	70.18
2+50	25.19	12.14	45.92	22.04	312.15	92.22
3+00	24.41	11.66	65.90	27.01	378.04	119.22
3+57.85	37.10	13.54	22.66	23.43	400.70	142.65
3+83.44	10.71	35.89	5.39	20.01	406.09	162.66
3+98.44	8.70	36.16	3.30	32.60	409.39	195.26
4+18.94	0.00	49.72	0.00	26.05	409.39	221.31
4+33.44	0.00	47.28	0.00	0.00	409.39	221.31

Stafford Ct (N)

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+19	68.34	0.00	34.23	1.15	34.23
0+36.65	36.40	3.51	18.20	1.35	52.43	2.49
0+50	37.20	1.93	68.90	5.61	121.33	8.11
1+00	37.22	4.13	32.29	4.35	153.62	12.45
1+23.99	35.47	5.66	45.88	4.65	199.50	17.11
1+51	56.25	3.64	85.57	4.52	285.06	21.63
1+84.49	81.72	3.65	45.40	10.54	330.47	32.16
2+04.94	38.17	24.18	12.58	7.48	343.04	39.64
2+19.92	7.16	2.79	0.00	0.00	343.04	39.64

Brentwood South Addition, Paving Improvements
Kinkaid / Stoneybrook
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN	KML
DRAWN	RLS
REVIEW	
UTILITY	
DATE	Oct. 3, 2005

DRAWING FILE: PROJECT NUMBER: 472-84270

SHEET 28 OF 30