BENCHMARK:

BM #2 – RR Spike in the South Face of Power Pole at the Northeast Corner of Maize Road and 29th Street South.
Sta. 1+039.59, 14.74m Lt.
Elev. 411.678 SI Units (1350.65 MSL)

PLANT SCHEDULE

QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONDITION	REMARKS
3	Acer fremanii 'Autumn Blaze'	Autumn Blaze Maple	2" Cal.	B&B	Single Stem Only
5	Cercis reniformis 'Oklahoma'	Oklahoma Redbud	2" Cal.	B&B	Single Stem Only
2	Malus 'Adirondak'	Adirondak Crabapple	2" Cal.	B&B	Single Stem Only
3	Pyrus calleryana 'Capital'	Capital Pear	2" Cal.	B&B	Single Stem Only
1	Ulmus parvifolia	Lacebark Elm	2" Cal.	B&B	Single Stem Only
1	Zelkova serrata 'Green Vase'	Green Vase Zelkova	2" Cal.	B&B	Single Stem Only
9	Spirea japonica 'Gold Mound'	Goldmound Spirea	2–Gal.	Container	Full & Healthy
6	Juniperus sabina 'Monard'	Moor–Dense Juniper	2–Gal.	Container	Full & Healthy
20	Hemerocallis 'Stella de Oro'	Stella de Oro Daylily	1–Gal.	Container	Full & Healthy
7	Pennisetum alopecuroides 'Hameln'	Dwf. Hameln Fountain Grass	1–Gal.	Container	Full & Healthy

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472-83863a	LS03	E:\29th –Tyler to Maize Lscape\

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
NLS	NLS	BDT	April 07	Noted	02–02–E232

CAPITAL IMPROVEMENT PROJECT
29TH STREET NORTH LANDSCAPING
Sta. 1+037.823 to Sta. 1+140.000
29TH STREET NORTH - MAIZE ROAD to TYLER ROAD

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 * 315 ELLIS * WICHITA, KANSAS 67211

SHEET A.3 OF 18