

NOTE TO CONTRACTOR:

Contractor is to give the Mo. Pac. R. Texas
Pac. R. R. Co. an advanced notification of 48 hours
prior to beginning construction near R. R. Tracks
in Wichita St.

NOTIFY: The Roadmaster
Mo. Pacific and Texas Pacific R. R. Co.
1410 East 25th St. No.
Ph. No. 838-8211

Casing pipe to be installed by boring methods using equipment that enables the hole to be removed. Boring without concurrent installation of casing will not be permitted. Casing to be accurately positioned to flow elevation in casing using creosoted wood skids. Casing pipe to be completely filled, with specified sand mix concrete after installation of 8" cast iron sewer pipe.

Bid price of tunnel shall include the steel pipe, pressure grout, skids and straps.

**NOTE TO CONTRACTOR
AND FIELD ENGINEER:**

Contractor to excavate exist.
S. S. at Sta. 2172.0 so Field
Engineer can Verify Flo. Elev.
prior to staking of the
project.

Plan Scale 1" = 20'
Profile Scale 1" = 20' Horiz.
1" = 5' Vert.

Concrete collar constructed on storm sewer will not be paid for directly and shall be considered as subsidiary to other items of work.

NOTE: All pavement, walk, and drive to be replaced.
All pavement, walk, and drive replaced shall conform to applicable standard specifications of the City of Wichita, Kansas.

Sta. 2+70.5 Const. Std. M.H.
Type "A" over exist. 8"
San. Sewer.

Sta. 0100.0
Exist. 2x5 Conc. Inlet

Sta. 0120.0
Proposed San. Sewer

NOTE:
Construct conc. collar around
junction of new pipe with
existing pipe.

Sta. 0155.0
2x3 1/2" grate

NOTE:
Joint between
Cast Iron pipe
and Clay pipe
is to be inside
of tunnel.

105.21 Flo out 12"
105.05 Bottom of Inlet
107.4 Flo in exist 8"
105.54 Flo in proposed 8"

Install 40
lin. ft. of 8"
Clay pipe

Storm Water Pipe Alteration

RELOCATION OF A PART OF
LAT. 5, WEST SUB. A, ON CENTRAL AVE., S.S. NO. 1
CITY OF WICHITA, KANSAS
R. W. LINN CITY ENGINEER
AUG. 1972 PROJECT NO. KANSAS 4-5-3
AUGUST 1972