Sta. 0+00 Exist. Manhole
Begin Project

Plan Scale 1"=40'
Profile Scale Horiz. 1"=40'
Vert. 1"=5'

B.M. 106.86 Corner of top brick step to house at 2847 S. Hillside Ave

Benefit District Line

S.L. Benefit Dist.

Butler's 3rd Addn.

155.5'

140'

130'

109'

30'

78.5'

77'

40'

Exist 8" Sanitary

15' Utility Easmt.

20' Perm. Sewer Easmt.

20' Temp. Const. Easmt.

Sta. 2+68 Constr. Std. Manhole Type A. Install 8" Stub N. 4" Stub E

Unplatted Tracts

Septic Tank

270'

133'

90'

20' Temp. Const. Easmt.

S.N.L. Benefit District

Gothard St.

Hillside Ave.

Sta. 0+00 Exist. M.H. Begin Project

Exist. Ground

105

100

95

90

268 L.F. 8" Pipe @ 0.4%
V.C.P., P.V.C., or A.B.S. Comp.

E 92.44

E 92.04

E 93.24

E 93.48

Sta. 2+68.3 Constr. Std. M.H. Type A or C. Install 8" Stub N. & plug.

0 1 2 +68

PLATE 1 PLAN-PROFILE U. I. P. & R. E. DIAGRAM
100% RAG LINEN ISSUE AND ERASED IN U. S. A.
EUGENE PHYSIOLN CO.

Lat. 63, War Industries Sewer
Proj. No. 468-76-245-80866-000-000-001
City of Wichita, Kansas
R.W. Bruggeman — Dir. of Engineering/City Engineer

Sht. #1 of 1