

SANITARY SEWER PLANS

LAT. 221, S.W.I.

HUNTINGTON PLACE

PROJECT NO.

468-76-245-81577-000-000-001

CITY OF WICHITA, KANSAS
MICHAEL E. LINDEBAK, CITY ENGINEER

AUGUST 1986


GENERAL NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR SHALL BE REQUIRED TO RE-ESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR OR A LICENSED PROFESSIONAL ENGINEER IN ACCORDANCE WITH STATE LAWS.
- A PORTION OF EXCESS EXCAVATED MATERIAL SHALL BE MOUNDED AROUND MANHOLES WHICH EXTEND MORE THAN ONE (1) FOOT ABOVE THE EXISTING GROUND. SUCH MOUNDS SHALL BE CONSTRUCTED WITH A SIX (6) FOOT DIAMETER FLAT TOP WITH 4 TO 1 SIDE SLOPES DOWN TO THE ORIGINAL GROUND. THE ELEVATION OF THE FLAT TOP OF THE MOUND SHALL BE 0.4 FOOT BELOW THE TOP OF THE MANHOLE.
- CONTRACTOR SHALL NOTIFY THE FOLLOWING COMPANIES PRIOR TO ANY EXCAVATION:

ARKLA GAS COMPANY	942-8350
BELL TELEPHONE COMPANY	268-2256
CABLEVISION	269-3340
KPL COMPANY	263-7511
KANSAS GAS & ELECTRIC	261-6248
KANSAS ONE-CALL	1-800-344-7233
- EXISTING UTILITIES AND THEIR LOCATIONS, AS SHOWN ON THE PLANS, REPRESENT THE BEST INFORMATION OBTAINABLE FOR DESIGN. LOCATION INFORMATION HAS BEEN OBTAINED FROM THE VARIOUS UTILITY COMPANIES AND IS EITHER FROM COMPANY RECORD DRAWINGS OR COMPANY PROVIDED FIELD LOCATIONS. THE PLAN LOCATIONS SHOWN ARE NOT GUARANTEED. ADDITIONAL EXISTING UTILITIES MAY ALSO BE ENCOUNTERED.
- ALL STUBS AND PLUGGED PIPES SHALL BE LOCATED WITH GREEN PLASTIC TAPE IN THE SAME MANNER AS RISERS.
- COST OF EXCAVATION, HAULING, AND DUMPING OF EXCESS EXCAVATION SHALL BE SUBSIDIARY TO THE PROJECT.
- TREES TO BE REMOVED ARE MARKED . ALL TREES WHICH IN THE OPINION OF THE FIELD ENGINEER CAN BE SAVED, SHALL BE SAVED.
- RISER PIPE SHALL BE INSTALLED TO SERVE INDIVIDUAL LOTS OR TRACTS IN CONJUNCTION WITH NEW SANITARY SEWER CONSTRUCTION, UNLESS OTHERWISE ORDERED BY THE ENGINEER, BECAUSE OF GROUND WATER, UNSTABLE SOIL OR UNUSUALLY DEEP CONSTRUCTION. RISER LOCATIONS SHALL BE AS APPROVED BY THE PROPERTY OWNER WITH THE CONCURRENCE OF THE ENGINEER. INSTALLATION OF RISERS ON SEWERS BECAUSE OF UNUSUAL DEPTH WILL BE REQUIRED WHEN THE SEWER IS DEEPER THAN TWELVE FEET (12'). THE CONTRACTOR WILL BE REQUIRED TO FILE WRITTEN DOCUMENTATION WITH THE ENGINEER IN A FORM APPROVED BY THE ENGINEER INDICATING THE LOCATIONS WHERE RISERS ARE TO BE INSTALLED AS REQUESTED BY THE PROPERTY OWNER OR HIS AUTHORIZED REPRESENTATIVE. RISER PIPE CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS AS SHOWN ON THE STANDARD RISER DETAIL SHEET.

BENCH MARKS

- B.M. #1: 1/2 mile east of 119th St. West & 13th St.
City of Wichita Bench Mark Disc. due north of 1/4
Section Corner, 8' north of H.L. Pole east-west, 40.6' north
of centerline 13th Street.
ELEV. = 158.73
- B.M. #2: Maize & 9th Street North
City of Wichita Bench Mark Disc, 32' north and 38' east of
Quarter Section Corner
ELEV. = 152.283
- B.M. #3: Chisled "O" on Top of Curb at West end return, S.W. Corner
13th & Parkdale
ELEV. = 156.24



INDEX TO DRAWINGS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2-5	PLAN & PROFILE-LINE
6	DETAIL SHEET
7	TYPE "P" MANHOLE DETAIL
8	VERTICLE RISER DETAIL
9	HUNTINGTON PLACE PLAT

MANHOLE COORDINATES

Manhole No.	North Coordinate	East Coordinate
M.H. 1-0	3048.3190	8008.3923
M.H. 1-1	3044.8958	7956.1443
M.H. 1-2	3113.5077	7750.7461
M.H. 1-3	3109.5881	7490.7717
M.H. 1-4	3070.7757	7138.5391
M.H. 1-5	3500.1561	6829.4452
M.H. 1-6	3852.7515	6806.3435
M.H. 1-7	3982.3270	6623.0077
M.H. 1-8	3976.0679	6527.4764
M.H. 1-9	4271.0233	6508.1512
M.H. 1-10	4320.2677	6329.8230
M.H. 1-11	4427.2997	6275.1664
M.H. 1-12	4553.8540	6266.8747
M.H. 1-13	4741.4517	6254.5834
M.H. 1-14	4789.0127	6251.4673
M.H. 1-15	4916.9852	6129.9024
M.H. 1-16	5037.1768	6132.8807


	HUNTINGTON PLACE	Design: KKL, RCB Drawn by: DPR Checked by: [blank] Date: AUG. 1986 Job no: [blank]
	LATERAL 221	
	S.W.I. SEWER	
	MID-KANSAS ENGINEERING CONSULTANTS PA 3500 NORTH ROCK ROAD BUILDING #800 WICHITA, KANSAS 67226 682-6561	
		Sheet 1 of 9

FILMED FROM THE BEST
AVAILABLE COPY

HUNTINGTON PLACE
LAT. 221 S.W.1.
468-76-245-81577-000-000-001




Scale: 1" = 40' Horiz.
1" = 5' Vert.




PLAN LINE 1

RISER STATIONS	
2+70	LT.
3+50	LT.
4+20	LT.
5+60	LT.
6+30	LT.
6+90	LT.
7+70	LT.

PROFILE LINE 1




Scale: 1" = 40' Horiz.
1" = 5' Vert.





PLAN LINE I

RISER STATIONS	
9+50 LT	14+30 LT
10+10 LT	14+80 LT
10+50 LT	15+30 LT
11+10 LT	15+80 LT
12+60 LT	16+30 LT
13+50 LT	17+10 LT



HUNTINGTON PLACE
LAT. 221 S.W.I.
468-76-245-81577-000-000-001




Scale : 1" = 40' Horiz.
1" = 5' Vert.


RISER STATIONS	
17+90	LT
18+60	LT
19+30	LT

PLAN LINE 1

PROFILE LINE 1




FILMED FROM THE BEST
AVAILABLE COPY....




Scale: 1" = 40' Horiz.
1" = 5' Vert.


PLAN LINE 1




RISER LOCATIONS		
25 + 70	LT	
26 + 90	LT	
28 + 30	LT	
29 + 10	LT	




EXISTING LIFT STATION
TO BE RECONSTRUCTED: MANHOLE I-16



RECONSTRUCTED MANHOLE
MANHOLE I-16 STA. 33+12.4



TYPICAL MANHOLE FLOOR SHAPING



GENERAL NOTES

1. REMOVE ALL SLABS AROUND LIFT STATION. COMPACT ALL SAND BACKFILL AND TOPSOIL. GRADE TO MATCH SURROUNDING AREA.
2. WHERE SHOWN, ABANDONED PIPES SHALL BE PLUGGED ON BOTH ENDS WITH GROUT PER CITY OF WICHITA SPECS.
3. FURNISH ALL MATERIALS, MACHINERY, AND EQUIPMENT NECESSARY FOR THE DEMOLITION AND REMOVAL OF THE ITEMS SHOWN.
4. CONDUCT ALL DEMOLITION IN A SAFE MANNER TO INSURE THE SAFETY OF ALL PERSONNEL AND ALL PROPERTY. ANY DAMAGES TO PROPERTY AND PERSONNEL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
5. THIS LOCATION SHALL BE SEED AFTER PREPARATION OF TOPSOIL.
6. THE CONTRACTOR WILL BE REQUIRED TO PROVIDE TEMPORARY PUMPING AROUND THE EXISTING STRUCTURE DURING THE REHABILITATION OF THE MANHOLE.
7. THE EXISTING LIFT STATION REMOVAL AND MODIFICATION SHALL INCLUDE THE FOLLOWING:
 - A. REMOVE PUMP STATION INCLUDING ALL ELECTRICAL AND PIPES, AND DELIVER TO 1801 S. McLEAN.
 - B. DEMOLISH EXISTING DRIVE, CURB AND GUTTER, AND TOP OF EXISTING MANHOLE.
 - C. WHILE PUMPING AROUND THE EXISTING PUMP STATION MANHOLE, CLEAN, COMPACT SAND, AND INSTALL A NEW MANHOLE FLOOR.
 - D. CONSTRUCT NEW CORBEL AND INSTALL MANHOLE COVER ON EXISTING MANHOLE.
 - E. FILL THE EXISTING SITE WITH TOPSOIL TO EXISTING GRADE, SEED AND MULCH.
 - F. PLUG FORCE MAIN AND DEMOLISH EXISTING AIR RELEASE MANHOLE AND EFFLUENT MANHOLE. BACKFILL AND GRADE TO MATCH EXISTING AREA, SEED AND MULCH.
 - G. REMOVAL OF EXISTING INLET IN DRIVE AND EXTRA PIPE AS REQUIRED TO CONSTRUCT NEW INLET.


	HUNTINGTON PLACE	Design RCB
	DETAIL SHEET	Drawn by DPR Checked by DPR Date AUG. 15, 2006
MID-KANSAS ENGINEERING CONSULTANTS PA 3500 NORTH ROCK ROAD BUILDING #800 WICHITA, KANSAS 67226		Sheet 6 of 9

SEWER APPURTENANCES DETAILS


ADOPTED AS STANDARD DESIGN

BY


CITY OF WICHITA




TYPE P
STANDARD MANHOLE



TYPE P
INSIDE DROP MANHOLE



TYPE P
OUTSIDE DROP MANHOLE



SECTION X
(TYPICAL)

GENERAL NOTES

PRECAST MANHOLE NOTES

1. ALL PRECAST CONCRETE MANHOLE SECTIONS SHALL CONFORM TO THE LATEST REVISION OF A.S.T.M. C478 AS MODIFIED BY THE SPECIFICATIONS.
2. NON-SHRINK GROUT SHALL BE NON-METALLIC TYPE.
3. APPROVED FLEXIBLE WATERSTOP GASKETS SHALL BE INSTALLED TO JOIN THE SEWER TO THE MANHOLE WALL WHEN A.B.S. COMPOSITE PIPE OR P.V.C. PIPE IS USED. FOR OTHER TYPES OF PIPE THE SEWER SHALL BE GROUTED IN PLACE WITH NON-SHRINK GROUT. THE SEWER PIPE SHALL BE SUPPORTED WITH CONCRETE ENCASEMENT A MINIMUM OF 3 FEET FROM THE MANHOLE WALL AND TO THE FIRST JOINT FOR V.C.P. SUCH THAT THE JOINT REMAINS FLEXIBLE.
4. ALL INSIDE SURFACES OF THE CONCRETE MANHOLE WHICH WOULD BE EXPOSED TO SEWER GAS SHALL BE COATED WITH 2 COATS THEMEC SERIES 66 HI-BUILD EPOXYLINE, DRY THICKNESS OF 8 MILS (MIN.)
5. EXTERIOR MANHOLE WALLS SHALL BE COATED WITH 1 COAT MOBILARMA 633 BITUMINUS COATING.
6. JOINT SEALING COMPOUND SHALL BE KENT SEAL NO. 2 OR APPROVED EQUAL.
7. PRECAST MANHOLES SHALL BE SET AT LEAST 4 INCHES INTO THE MANHOLE BASE.
8. TOP OF MANHOLE FLOOR SLAB SHALL BE AT LEAST 3 INCHES BELOW THE FLOW LINE OF THE OUTLET PIPE TO INSURE SUFFICIENT MINIMUM THICKNESS OF SHAPED INVERT.
9. LIFTING HOLES SHALL BE FILLED WITH NON-SHRINK GROUT AND THE INTERIOR SURFACE COATED AS SPECIFIED.
10. MORTAR USED IN MASONRY CONSTRUCTION SHALL CONTAIN 8 SACKS OF CEMENT PER CUBIC YARD. CONCRETE USED IN MANHOLE BASES SHALL CONFORM TO THE REQUIREMENTS OF CONCRETE FOR CONCRETE PAVING SPECIFICATIONS USING CITY CONCRETE PAVING MIX WITHOUT AIR ENTRAINING ADMIXTURE. MORTAR SHALL BE PLACED AROUND THE MANHOLE RING AS SHOWN ON THE DRAWINGS WHEN MANHOLES ARE CONSTRUCTED IN UNPAVED AREAS. MANHOLES CONSTRUCTED WHERE PIPE SIZES ARE SMALLER THAN 24" SHALL HAVE AN INSIDE DIAMETER OF 4". MANHOLES CONSTRUCTED WHERE PIPE SIZES ARE 24" OR LARGER SHALL HAVE AN INSIDE DIAMETER OF 5". COMPLETED MANHOLE SHALL BE WITHOUT LEAKS AND WATER TIGHT.

11. REINFORCING STEEL SHALL BE INSTALLED IN THE MANHOLE BASES AND SHALL CONSIST OF NO. 4 BARS PLACED ON 6" CENTERS IN BOTH DIRECTIONS. THE MANHOLE BASE REINFORCEMENT SHALL BE PLACED AT LEAST 3" ABOVE THE BOTTOM OF THE MANHOLE BASE. ALL COSTS FOR FURNISHING AND INSTALLING REINFORCING STEEL SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.
12. OPENINGS SHALL BE CUT INTO THE MANHOLE WALL WHEN OUTSIDE DROPS ARE CONSTRUCTED ON EXISTING MANHOLES. SUCH OPENINGS CUT INTO EXISTING MANHOLES SHALL BE AS SMALL AS PRACTICAL TO FACILITATE INSTALLING AND GROUTING THE NEW PIPE IN PLACE. WATERSTOP GASKETS SHALL BE USED WITH P.V.C. AND A.B.S. COMPOSITE PIPE. THE NEW PIPE SHALL BE GROUTED INTO THE OPENING USING AN APPROVED NONSHRINK GROUT FOR THE FULL MANHOLE WALL THICKNESS. THE EXTERIOR OF THE COMPLETED CONNECTION SHALL BE SEALED WITH AN APPROVED BITUMINOUS COATING SUCH THAT THE CONNECTION WILL BE WATER TIGHT. FLOOR OF MANHOLE SHALL BE MODIFIED TO FORM NEW FLOW CHANNEL FOR THE NEW CONNECTION AS INDICATED BY THE DRAWING. THIS WORK, INCLUDING MODIFICATION OF MANHOLE FLOOR, SHALL BE PAID FOR AT THE UNIT PRICE BID FOR OUTSIDE DROP STACK CONSTRUCTED ON EXISTING MANHOLE.
13. THE FLOORS OF ALL MANHOLES SHALL BE SHAPED WITH FLOW CHANNELS SUCH THAT THE MANHOLES WILL BE SELF CLEANING AND FREE OF AREAS WHERE SOLIDS COULD BE DEPOSITED AS SEWAGE FLOWS THROUGH THE MANHOLE FROM ALL INLET PIPES TO THE OUTLET PIPE. FLOW CHANNELS SHALL BE FORMED TO MATCH THE BOTTOM HALVES OF THE INFLOWING PIPES AND THE OUTFLOWING PIPE AS SHOWN BY THE DRAWINGS EXCEPT FOR INSIDE DROP MANHOLES. FLOW CHANNELS FOR INSIDE DROP MANHOLES SHALL BE CONSTRUCTED AS INDICATED BY THE DRAWING. MANHOLE FLOORS SHALL HAVE SLOPES OF 3 INCHES PER FOOT IN THE AREAS OUTSIDE OF THE FLOW CHANNELS SLOPED TOWARD THE FLOW CHANNELS. PIPES LAID THROUGH MANHOLES SHALL HAVE THE TOP HALF REMOVED TO REAR LINES FOR THE FULL INSIDE DIAMETER OF THE MANHOLE. MANHOLE FLOORS SHALL THEN BE SHAPED AROUND THE BOTTOM HALF OF THE PIPE WHICH FORMS THE FLOW CHANNEL.
14. PIPES INSTALLED WITHIN THE EXCAVATION MADE FOR THE MANHOLE SHALL BE CRADLED WITH CONCRETE TO THE LIMITS OF THE MANHOLE EXCAVATION. WHEN CLAY PIPE IS USED, THE CRADLE SHALL EXTEND TO THE FIRST JOINT OUTSIDE THE MANHOLE. THE CRADLE SHALL BE TERMINATED AT THE CLAY PIPE JOINT IN A MANNER WHICH WILL MAINTAIN THE FLEXIBILITY OF THE JOINT. COST OF CRADLE WITHIN MANHOLE EXCAVATION OR TO CLAY PIPE JOINTS ADJACENT TO MANHOLE SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.

15. MANHOLE COVER CASTINGS AND MANHOLE FRAME CASTINGS SHALL CONFORM TO THE REQUIREMENTS AS INDICATED IN THE STANDARD SPECIFICATIONS AND AS SHOWN IN THE STANDARD DETAIL DRAWING.
16. THE VERTICAL DROP IN INSIDE DROP MANHOLES SHALL NOT EXCEED 4' FOR INFLOWING PIPES SIZED 12" OR SMALLER AND 2' FOR INFLOWING PIPES LARGER THAN 12". THE CROOKS OF INFLOWING PIPES SHALL NEVER BE SET LOWER THAN THE CROWN OF THE OUTFLOWING PIPE.
17. STANDARD MANHOLES AND STANDARD INSIDE DROP MANHOLES SHALL BE BID AS STANDARD MANHOLES FOR THE TYPE AND DIAMETER INDICATED. OUTSIDE DROP MANHOLES SHALL BE BID AS STANDARD OUTSIDE DROP MANHOLES FOR THE TYPE AND DIAMETER INDICATED. ALL MANHOLE DIAMETERS WILL BE 4' UNLESS INDICATED OTHERWISE.
18. A BRICK MASONRY COLLAR SHALL BE INSTALLED BETWEEN THE CAST IRON FRAME AND THE CONCENTRIC CONE. THE COLLAR WILL HAVE 8" WALLS AND A VERTICAL HEIGHT OF 6" MINIMUM AND 18" MAXIMUM. A 1" COAT OF MORTAR WILL BE PLASTERED ON THE OUTSIDE OF THE COLLAR.

Revised: June 12, 1986

FILMED FROM THE BEST
AVAILABLE COPY....

CITY OF WICHITA, KANSAS



TYPICAL RISER FOR VERTICAL TRENCH WALLS

REVISÉ APRIL, 1980

GENERAL NOTE

RISERS SHALL BE INSTALLED TO SERVE ALL 4" OR 6" TRACS WITH THE MAIN
 SEWER LINE IS BELOW THE WATER TABLE. RISERS SHALL ALSO BE INSTALLED
 TO SERVE ALL LOTS AND TRACTS WHERE THE MAIN SEWER LINE DEPTH IS SUCH
 THAT VOLUME MAKING THE BUILDING SEWER LINE CONNECTION DIFFICULT.
 INSTALLATION OF RISERS BECAUSE OF MAIN LINE SEWER DEPTH SHALL BE AS
 APPROVED BY THE ENGINEER. THE LOCATION OF RISERS TO SERVE DEVELOPED
 PROPERTY SHALL BE APPROVED BY THE PROPERTY OWNER. PIPE STUBS SHALL
 BE INSTALLED IN MANHOLES WHERE LOCATIONS ARE DETERMINED BY THE FIELD ENGINEER.
 SATISFACTORY SERVICE CONNECTIONS SHALL BE MADE TO THE MANHOLE PIPE STUB
 THE VERTICAL DISTANCE BETWEEN THE PIPE LINE OF THE MANHOLE PIPE STUB
 AND THE TOP OF THE MAIN SEWER LINE SHALL NOT EXCEED 4 FT.
 MANHOLE PIPE STUBS SHALL NOT BE SET BELOW AN ELEVATION WHICH WILL
 PERMIT THE TOP OF THE INSIDE OF THE STUB TO MATCH THE TOP OF THE IN-
 SIDE OF THE MAIN SEWER PIPE. PIPE STUBS AND RISERS SHALL BE INSTALLED TO
 SERVE COMMERCIAL OR INDUSTRIAL PROPERTY SHALL BE 6 INCH. PIPE STUBS
 AND RISERS DESTALLED TO SERVE RESIDENTIAL PROPERTY MAY BE EITHER 6
 INCH OR 4 INCH DETERMINED UPON THE AVAILABLE GRADE AND THE SIZE OF
 THE LOT AS DETERMINED BY THE FIELD ENGINEER. ENCASUREMENT OF VITRIFIED
 CLAY MAIN SEWER PIPE SHALL EXTEND TO THE FIRST JOINT IN THE MAIN
 LINE. THE LOT AND MAIN SEWER PIPE SHALL BE ENCASED WITH A MINIMUM
 OF 18 INCHES OF CONCRETE OR P.V.C. MAIN SEWER PIPE SHALL EXTEND A MINIMUM
 OF 3 FT. ON BOTH SIDES OF THE MANHOLE. THE RISERS, 4 INCH INCH
 AND SIX INCH INCH MAIN PIPE SHALL BE ENCASED WITH CONCRETE TO THE TOP OF
 THE KNUCKLE AS INDICATED IN THE DRAWINGS. FOUR INCH AND SIX INCH CLAY
 PIPE USED FOR 8" P.V.C. SHALL BE EXTRA STRENGTH PIPE CONFORMING TO THE
 REQUIREMENTS OF THE LATEST REVISION OF A.S.T.M. DESIGNATION C-754
 STANDARD WITH COMPRESSION JOINTS AS SPECIFIED FOR CLAY PIPE IN STANDARD
 SPECIFICATIONS. FOUR INCH AND SIX INCH P.V.C. SHALL BE STANDARD
 BE PIPE APPROVED FOR USE BY THE CITY BY THE CHIEF PLUMBING AND
 SANITATION INSPECTOR FOR THE CENTRAL INSPECTION DIVISION OF THE
 DEPARTMENT OF HOUSING AND ECONOMIC DEVELOPMENT. LOCATIONS OF THE
 ENDS OF THE RISERS SHALL BE MARKED BY FASTENING GREEN COLORED PLASTIC
 TAPE TO THE END OF THE RISER WHICH SHALL BE EXTENDED TO THE GROUND
 SURFACE AS THE EXCAVATION IS BACKFILLED IN ORDER THAT THE COLORED TAPE
 WILL BE VISIBLE WHEN THE EXCAVATION IS COMPLETED. THE ENDS OF THE RISER
 PIPE MANHOLE STUBS SHALL BE CAPPED OR PLUGGED USING FITTINGS
 FURNISHED BY THE MANUFACTURER OF THE PIPE. CONTRACTOR'S METHODS FOR
 SUPPORTING AND BACKFILLING RISER PIPE SHALL BE APPROVED BY THE
 ENGINEER.


FURNISHING AND INSTALLING RISERS SHALL BE PAID FOR AT THE UNIT PRICES AID FOR 4" PIPE, 6" PIPE AND REINFORCED CONCRETE ENCASMENT FOR THE VARIOUS MAXIMUM PIPE SIZES INDICATED; WHICH PRICE SHALL INCLUDE ALL COSTS FOR COMPLETION OF THIS ITEM INCLUDING SADDLES, SEEDS, CONCRETE, REINFORCING STEEL, CAPS OR PLUGS, AND ALL OTHER NECESSARY MATERIALS OR WORK. CONCRETE ENCASMENT OF THE RISER PIPE TO THE TOP OF THE BED AS SHOWN BY THE DRAWINGS WILL NOT BE PAID FOR DIRECTLY AND THE COST FOR THIS WORK SHALL BE CONSIDERED AS SUBSIDIARY TO THE OTHER ITEMS OF WORK.

THE PROJECT INSPECTOR SHALL REPORT ON INSPECTOR CARDS THE LOCATION OF ALL RISERS CONSTRUCTED AS MEASURED FROM THE NEAREST MANHOLE, THE DIRECTION OF SERVICE, THE ELEVATION OF THE TOP OF THE RISER, AND THE PAY QUANTITIES INVOLVED. THE PROJECT INSPECTOR SHALL ALSO REPORT ON INSPECTOR CARDS THE LOCATION, DIRECTION OF SERVICE, AND SIZE OF ALL STUBS INSTALLED IN MANHOLES.

VIC-8 A
8-31A

118-8 H

FINAL PLAT OF
HUNTINGTON PLACE
AN ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS



FILMED FROM THE BEST
AVAILABLE COPY....