Survey by Young Engineering Checked by Date 1931

Dallas Avenue

Sta 0+00 Existing M.H.

Sta 2+50 Prop. M.H.

Sta 5+00 Prop. M.H.

Sta 7+50 Prop. M.H.

Sta 10+00 Prop. M.H.

Sta 12+85 Prop. M.H.

Oriental Boulevard

Addition

Park

Oriental

Anita

Bennett

Sch. & San Sewer

Atch. Topeka & Santa Fe R.R. Tracks

14

7

Avenue

Scale 1"=40'

B.M. 98.99 60" Spike S.W. Side H.L.P. N.E. Cor. Casado & Oriental Ave.

Plan Scale 1"=40'
Profile Scale 1"=40' Hor, 1"=4' Vertical

Sand Fill Sta 0+03.5 To Sta 0+43.5

Natural Ground

Sand Fill Sta 6+51 To Sta 7+01

1285 l.in. ft. 8" V.C.P. @ .4% Grade

30.00 f/s In Exist. Stub

31.00 f/s

32.00 f/s

33.00 f/s

34.00 f/s

35.14 f/s Out

38.15 Surf.

83.92 f/s Out

90

80

0 1 2 3 4 5 6 7 8 9 10 11 12 13

late 19 Sub. Rel. Sewer 22
City of Wichita, Kansas
B.E. Smith City Engineer
Proj. No. C26-53 Date- Aug '56

e 5 3 e