

CONSTRUCTION PLANS SANITARY SEWER EXTENSIONS HARBOR ISLE ADDITION - PHASE II TO THE CITY OF WICHITA, KANSAS

MICHAEL E. LINDEBAK, P.E. - CITY ENGINEER

LATERAL 84, SANITARY SEWER NO. 23




PROJECT NO. 468-82408

INDEX CODE 742312

GENERAL NOTES:

- Existing utility lines and their location, as shown on the plans, represent the best information obtainable for design. The contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.
- Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be the disposal of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved.

All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.
- The Contractor shall be responsible for maintaining continuous flow of sewage through construction. Contractor's proposed method for maintaining sewage flow shall be approved by the Engineer. Cost of maintaining flow of sewage through construction will not be paid for directly and this cost shall be considered as subsidiary to the other pay items of the work.
- The Contractor shall be responsible for preserving property irons. The Contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor or a licensed professional engineer in accordance with state laws.
- Trees and shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with the proposed new construction shall be saved and protected from damage.
- Contractor shall vacuum test all manholes according to the City of Wichita standard specifications.
- The sewer line Contractor will not be required to complete easement grading.
- All disturbed areas shall have temporary grass seeding applied at a rate of 250 lbs/acre.



JUNE 1995

PLANS PREPARED
BY
POE & ASSOCIATES OF KANSAS, INC.

Consulting Engineers
434 N. Oliver Suite 110 Wichita KS 67208 316/685-4114

INDEX


TITLE SHEET	SHEET 1
LINE NO. 1	SHEET 2
LINE NO. 2	SHEET 3
TYPE "P" MANHOLE	SHEET 4
TYPE "C" MANHOLE	SHEET 5
VERTICAL RISER DETAIL	SHEET 6
HARBOR ISLE ADDITION PLAT	SHEET 7

BENCH MARKS

(City of Wichita Datum)


- "C" Cut in S. Hdl. of Culvert @ 45th & Meridian.
Elev. 141.07
- City of Wichita Disc @ NW. Cor. of Keywest & Meridian.
Elev. 141.85
- "C" Cut on top of curb on W. end of median @ Timbercreek Cir. & Meridian.
Elev. 142.33



*Booked
Per Plan
1/10/96*



8-14-95


F:\MPS\CA\UP\5604\5604-722 Mod Aug. 2 08 22 35 1995 Steve Schmitt P&E & ASSOC.






POE & ASSOCIATES OF KANSAS, INC.	
Consulting Engineers	
434 N. Oliver, Suite 110 • Wichita, KS 67208 • 316/268-4114	
DESIGNED BY	J. H. H.
DRAWN BY	J. H. H.
CHECKED BY	S. Schmidt
DATE	June 1995
PROJECT	3 of 7
HARBOR ISLE ADDITION - PHASE II	
Lateral B4, Sanitary Sewer No. 23	
Line No. 2	
CITY OF WICHITA, KANSAS	
Project No. 458-B2408	
Index Code 742312	


SEWER APPURTENANCES DETAILS ADOPTED AS STANDARD DESIGN BY CITY OF WICHITA




**TYPE P
STANDARD MANHOLE**



**TYPE P
INSIDE DROP MANHOLE**



**TYPE P
OUTSIDE DROP MANHOLE**




**SECTION X
(TYPICAL)**

GENERAL NOTES PRECAST MANHOLE NOTES

1. ALL PRECAST CONCRETE MANHOLE SECTIONS SHALL CONFORM TO THE SPECIFICATIONS OF U.S.P.D. RATE AS MODIFIED BY THE CITY OF WICHITA.
2. NON-SHRINK GROUT SHALL BE NON-METALLIC TYPE.
3. APPROVED ELASTIC WATERSTOP GASKETS SHALL BE INSTALLED TO FORM THE WATERSTOP JOINTS. THE JOINTS SHALL BE COMPOSED OF TWO GASKETS, ONE ON EACH SIDE OF THE JOINT. THE JOINTS SHALL BE INSTALLED IN SUCH A MANNER AS TO PREVENT THE INGRESS OF WATER INTO THE JOINTS.
4. ALL INSIDE SURFACES OF THE CONCRETE MANHOLE WHICH WOULD BE EXPOSED TO THE SEWER SHALL BE COATED WITH A COAT OF EPDM RUBBER GROUT TO PREVENT CORROSION OF THE SEWER PIPE.
5. EXTERIOR MANHOLE WALLS SHALL BE COATED WITH 1 COAT OF EPDM RUBBER GROUT TO PREVENT CORROSION OF THE SEWER PIPE.
6. JOINT SEALING COMPOUND SHALL BE KENT SEAL NO. 2 OR APPROVED EQUAL.
7. PRECAST MANHOLES SHALL BE SET AT LEAST 4 INCHES INTO THE EXISTING PAVEMENT.
8. TOP OF MANHOLE FLOOR SLAB SHALL BE AT LEAST 3 INCHES BELOW EXISTING PAVEMENT SURFACE.
9. LISTING HOLES SHALL BE FILLED WITH NON-SHRINK GROUT AND THE INTERIOR SURFACE COATED AS SPECIFIED.
10. MANHOLE USED IN MASONRY CONSTRUCTION SHALL CONTAIN 4 BARS OF #4 REINFORCING STEEL IN EACH WALL. THE BARS SHALL BE SPACED AT 48 INCHES ON CENTER. THE BARS SHALL BE LAPPED AT LEAST 48 INCHES. THE LAPS SHALL BE STAGGERED. THE BARS SHALL BE BENT UP AT LEAST 18 INCHES AT THE TOP OF THE MANHOLE.

11. REINFORCING STEEL SHALL BE INSTALLED IN THE MANHOLE BASES AND IN THE MANHOLE WALLS. THE STEEL SHALL BE SPACED AT 48 INCHES ON CENTER. THE STEEL SHALL BE LAPPED AT LEAST 48 INCHES. THE LAPS SHALL BE STAGGERED. THE STEEL SHALL BE BENT UP AT LEAST 18 INCHES AT THE TOP OF THE MANHOLE.
12. OPENINGS SHALL BE CUT INTO THE MANHOLE WALL WHEN OUTSIDE DROPS ARE REQUIRED. THE OPENINGS SHALL BE CUT IN SUCH A MANNER AS TO PREVENT THE INGRESS OF WATER INTO THE JOINTS. THE OPENINGS SHALL BE REINFORCED WITH STEEL. THE REINFORCEMENT SHALL BE SPACED AT 48 INCHES ON CENTER. THE REINFORCEMENT SHALL BE LAPPED AT LEAST 48 INCHES. THE LAPS SHALL BE STAGGERED. THE REINFORCEMENT SHALL BE BENT UP AT LEAST 18 INCHES AT THE TOP OF THE MANHOLE.
13. THE FLOORS OF ALL MANHOLES SHALL BE CHASED WITH FLOW CHANNELS. THE CHANNELS SHALL BE CHASED IN SUCH A MANNER AS TO PREVENT THE INGRESS OF WATER INTO THE JOINTS. THE CHANNELS SHALL BE REINFORCED WITH STEEL. THE REINFORCEMENT SHALL BE SPACED AT 48 INCHES ON CENTER. THE REINFORCEMENT SHALL BE LAPPED AT LEAST 48 INCHES. THE LAPS SHALL BE STAGGERED. THE REINFORCEMENT SHALL BE BENT UP AT LEAST 18 INCHES AT THE TOP OF THE MANHOLE.
14. PIPES INSTALLED WITHIN THE EXISTING MANHOLE SHALL BE INSTALLED IN SUCH A MANNER AS TO PREVENT THE INGRESS OF WATER INTO THE JOINTS. THE PIPES SHALL BE REINFORCED WITH STEEL. THE REINFORCEMENT SHALL BE SPACED AT 48 INCHES ON CENTER. THE REINFORCEMENT SHALL BE LAPPED AT LEAST 48 INCHES. THE LAPS SHALL BE STAGGERED. THE REINFORCEMENT SHALL BE BENT UP AT LEAST 18 INCHES AT THE TOP OF THE MANHOLE.

15. MANHOLE COVER CASTINGS AND MANHOLE FRAME CASTINGS SHALL CONFORM TO THE REQUIREMENTS INDICATED IN THE STANDARD SPECIFICATIONS AND AS SHOWN IN THE STANDARD DETAIL DRAWING.
16. THE VERTICAL FREE FALL DROP INSIDE MANHOLES SHALL NOT EXCEED 2'. THE CROWN OF INFLOWING PIPES SHALL NEVER BE SET LOWER THAN THE CROWN OF THE OUTFLOWING PIPE.
17. STANDARD MANHOLES AND STANDARD INSIDE DROP MANHOLES SHALL BE 18\"/>



**ALTERNATE CONSTRUCTION
IN UNPAVED AREAS**

HARBOR ISLE ADDITION
PHASE II
PROJECT NO. 468-82408
INDEX CODE 742312
REVISED MAY 1993
NOTE NO. 15 REVISED JAN. 1991
Revised 3-21-89
Revised 4-10-88
Revised: June 12, 1986

101151


SEWER APPURTENANCES DETAILS

ADOPTED AS STANDARD DESIGN


BY

City of Wichita, Kansas


STANDARD MANHOLE TYPE "C"



INSIDE DROP MANHOLE TYPE "C"





OUTSIDE DROP MANHOLE TYPE "C"



GENERAL NOTES


- MORTAR USED IN MASONRY CONSTRUCTION SHALL CONTAIN 8 SACKS OF CEMENT PER CUBIC YARD. CONCRETE USED IN MANHOLE WALLS AND BASES SHALL CONFORM TO THE REQUIREMENTS OF CONCRETE FOR CONCRETE PAVEMENT CONSTRUCTION AS SPECIFIED IN THE CITY STANDARD PAVING SPECIFICATIONS USING CITY CONCRETE PAVEMENT MIX WITHOUT AIR ENTRAINING ADMIXTURE. MORTAR SHALL BE PLACED AROUND THE MANHOLE RING AS SHOWN ON THE DRAWINGS WHEN MANHOLES ARE CONSTRUCTED IN UNPAVED AREAS. TYPE "C" MANHOLES CAN BE CONSTRUCTED ONLY WHERE PIPE SIZES ARE 8" OR SMALLER. THE INSIDE DIAMETER OF TYPE "C" MANHOLES SHALL BE 4'. COMPLETED MANHOLE SHALL BE WITHOUT LEAKS AND WATER TIGHT.
- REINFORCING STEEL SHALL BE INSTALLED IN THE MANHOLE BASE. REINFORCING STEEL SHALL CONSIST OF NO. 4 BARS PLACED ON 6" CENTERS IN BOTH DIRECTIONS. REINFORCING STEEL SHALL BE PLACED 6" ABOVE THE BOTTOM OF THE MANHOLE BASE. COST OF FURNISHING AND INSTALLING REINFORCING STEEL SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.
- AN OPENING SHALL BE CUT IN THE MANHOLE WALL FOR THE UPPER INLET PIPE FOR INSIDE AND OUTSIDE DROP MANHOLES. THE UPPER INLET PIPE SHALL BE GROUTED INTO THIS OPENING WITH NON-SHRINK GROUT. THE EXTERIOR OF THIS COMPLETED CONNECTION SHALL BE SEALED WITH AN APPROVED BITUMINOUS COATING SUCH THAT THE CONNECTION WILL BE WATER TIGHT.
- THE FLOORS OF ALL MANHOLES SHALL BE SHAPED WITH FLOW CHANNELS SUCH THAT THE MANHOLES WILL BE SELF CLEANING AND FREE OF AREAS WHERE SOLIDS COULD BE DEPOSITED AS SEWAGE FLOWS THROUGH THE MANHOLE FROM ALL INLET PIPES TO THE OUTLET PIPE. FLOW CHANNELS SHALL BE FORMED TO MATCH THE BOTTOM HALVES OF THE INFLUING PIPES AND THE OUTFLOWING PIPE AS SHOWN BY THE DRAWINGS EXCEPT FOR INSIDE DROP MANHOLES. FLOW CHANNELS FOR INSIDE DROP MANHOLES SHALL BE CONSTRUCTED AS INDICATED BY THE DRAWING. MANHOLE FLOORS SHALL HAVE SLOPES OF 3 INCHES PER FOOT IN THE AREAS OUTSIDE OF THE FLOW CHANNELS SLOPED TOWARD THE FLOW CHANNELS. PIPES LAID THROUGH MANHOLES SHALL HAVE THE TOP HALF REMOVED TO REVEAL LINES FOR THE FULL INSIDE DIAMETER OF THE MANHOLE. MANHOLE FLOORS SHALL THEN BE SHAPED AROUND THE BOTTOM HALF OF THE PIPE WHICH FORMS THE FLOW CHANNEL.
- PIPES INSTALLED WITHIN THE EXCAVATION MADE FOR THE MANHOLE SHALL BE CRADLED WITH CONCRETE TO THE LIMITS OF THE MANHOLE EXCAVATION. WHEN CLAY PIPE IS USED, THE CRADLE SHALL EXTEND TO THE FIRST JOINT OUTSIDE THE MANHOLE. THE CRADLE SHALL BE TERMINATED AT THE CLAY PIPE JOINT IN A MANNER WHICH WILL MAINTAIN THE FLEXIBILITY OF THE JOINT. COST OF CRADLE WITHIN MANHOLE EXCAVATION OR TO CLAY PIPE JOINTS ADJACENT TO MANHOLE SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.
- MANHOLE COVER CASTINGS AND MANHOLE FRAME CASTINGS SHALL CONFORM TO THE REQUIREMENTS AS INDICATED IN THE STANDARD SPECIFICATIONS AND AS SHOWN IN THE STANDARD DETAIL DRAWING.
- THE VERTICAL FREE FALL DROP INSIDE MANHOLES SHALL NOT EXCEED 2'. THE CROWNS OF INFLUING PIPES SHALL NEVER BE SET LOWER THAN THE CROWN OF THE OUTFLOWING PIPE.
- STANDARD MANHOLES TYPE "C" AND STANDARD INSIDE DROP MANHOLES TYPE "C" SHALL BE BID AS STANDARD MANHOLES FOR THE TYPE AND DIAMETER INDICATED. OUTSIDE DROP MANHOLES TYPE "C" SHALL BE BID AS STANDARD OUTSIDE DROP MANHOLES FOR THE TYPE AND DIAMETER INDICATED. ALL MANHOLE DIAMETERS WILL BE 4' UNLESS INDICATED OTHERWISE.

VERTICAL RISER DETAILS ADOPTED AS STANDARD DESIGN BY CITY OF WICHITA, KANSAS OCTOBER 1992



GENERAL NOTES

1. RISERS: Risers shall be installed to serve all lots or tracts where the sanitary sewer main is below the water table. Risers shall also be installed to serve all lots and tracts where the sanitary sewer main depth is greater than 12 feet below the proposed ground elevation. Installation of risers because of field conditions shall be as approved by the Construction Engineer. The location of the risers to serve developed property shall be approved by the property owner and the Construction Engineer.
2. PIPE STUBS: Pipe stubs shall be installed in manholes where installation of manholes will provide satisfactory service connection as determined by the Construction Engineer. The vertical distance between the floating of the manhole pipe stub and the floating of the sanitary sewer main out of the manhole shall not exceed 2 feet. Risers shall be utilized at manhole pipe stubs as indicated in Note 1. Manhole pipe stubs shall be set such that the top of the stub is not lower than the top of the sanitary sewer main.
3. SIZING: Pipe stubs and risers shall be sized according to the plans and riser table where risers are indicated by the plans. Where risers or pipe stubs are required because of field conditions, the risers and stubs shall be 8-inch diameter for commercial or industrial properties and 4" or 6" diameter for residential properties, based on lot size and sanitary sewer main depth. Sizing of risers and stubs shall be approved by the Construction Engineer prior to installation.
4. RISER OR STUB MATERIAL: Risers and stubs shall be constructed of SR 35 PVC Pipe or Schedule 40 PVC Pipe, meeting the requirements of the latest revision of A.S.T.M. A11 pipe joints shall be solvent welded.
5. REINFORCED CONCRETE ENCASMENT: Riser connections to clay pipe sanitary sewers shall be reinforced concrete encased both ways from the riser centerline. The reinforced concrete encasement shall extend three feet from the riser centerline or stop at the first sanitary sewer pipe joint within three feet of the riser centerline. Riser connections to PVC Sanitary Sewer mains shall be reinforced concrete encased one foot each way from the riser centerline. The concrete encasement shall be reinforced using reinforcing steel as shown in the appropriate drawing. The concrete shall conform to the City Standard Specifications for concrete pavement.
6. BEDDING: Bedding around the sanitary sewer riser shall be compacted Pipe Bedding Type 1 or 2. The bedding shall be placed and compacted from the depth of the sanitary sewer main to the top of the sanitary sewer riser pipe. Compacted Pipe Bedding Type 1 or 2 shall be required for all risers whether constructed in vertical wall or sloped wall trenches. Bedding material and construction practices shall be approved by the Construction Engineer prior to installation.
7. SUPPORT OF RISERS: Sanitary sewer riser pipe shall be supported during trench backfill. The riser pipe shall be held in a vertical position at all times until trench backfill and compaction has been completed. Contractor's methods for supporting and backfilling the riser pipe shall be approved by the Construction Engineer.
8. PLUGGING: The ends of the riser pipes and manhole stubs shall be plugged using an airtight solvent welded cap or plug. Cap or plug fittings shall be approved by the Construction Engineer prior to installation. Caps or plugs which do not provide an airtight seal will not be accepted.
9. TOP OF THE RISER PIPE: The top elevation of the sanitary sewer riser pipe shall be built per plan elevations, unless otherwise directed by the Construction Engineer. Where riser elevations are not shown on the plans, the top of the risers shall be set at an elevation four feet below the proposed ground surface. If ground water is encountered, the top of the riser pipe shall be set at an elevation two feet (min.) above the maximum water table elevation, regardless of the riser elevation shown on the plans.
10. MARKING: Locations of the ends of the sanitary sewer riser pipe shall be marked by fastening green colored plastic tape to the end of the riser. The tape shall be supported by a length of wooden 2 x 4, extending from the top of the riser pipe to the proposed ground surface. The green tape shall be visible and extend one foot above the proposed ground surface. The green tape shall be 4 mil Polyethylene film with a minimum width of three inches, specifically manufactured for the purpose of identification of underground sewers.
11. LOCATION MEASURES: The project inspector shall record and document the location of all risers constructed as measured from the nearest manhole, indicating the direction from the manhole, the direction and distance from the main, riser size, and elevation of the top of the riser.
12. RISER LOCATION: The riser shall be located per plan if shown. If not shown on the plan, the riser shall be located at the center of the lot, within one foot of the property side of the easement for the lot being served. All riser locations shall be approved by the Construction Engineer prior to installation.
13. PAYMENT: "Sanitary sewer risers" shall be paid for at the contract unit price per each, which price shall be full compensation for all pipe, fittings, marking tape, length of wooden 2 x 4, reinforced concrete encasement, support during backfill, backfill, labor, site restoration, and any other items necessary to complete the work.
"Manhole stubs" shall be paid for at the contract unit price per each, which shall be full compensation for all labor, material, and incidentals necessary to complete the work including all pipe, fittings, reinforced concrete encasement, and all other items as required and listed for "Sanitary Sewer Risers".




NOTE: RISER PIPE REQUIREMENTS AT MANHOLE STUBS SHALL BE SIMILAR TO THOSE SHOWN ABOVE.

HARBOR ISLE ADDITION
PHASE II
PROJECT NO. 468-92408
INDEX CODE 742312

Sheet 6 of 7

10-1-J-11



CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
1	209.78'	116.77'	59.94'	115.27'	S71°30'32"W	31°53'47"
2	900.00'	197.27'	99.03'	196.89'	N04°16'46"E	17°33'32"
3	204.00'	101.77'	51.93'	100.65'	N14°16'29"E	28°33'57"
4	286.00'	62.36'	31.31'	62.23'	N06°23'19"W	12°45'38"
5	469.00'	75.14'	37.65'	75.05'	N74°51'08"W	09°10'44"
6	365.00'	263.27'	137.65'	257.60'	S07°53'40"W	41°19'35"
7	340.00'	320.69'	173.40'	308.94'	N8°43'00"E	54°02'33"
8	234.00'	39.03'	19.58'	39.05'	N85°34'59"E	08°49'04"
9	311.00'	104.29'	52.64'	103.80'	S09°46'54"E	14°22'58"
10	305.00'	148.09'	75.53'	146.63'	N05°18'46"W	27°43'04"
11	483.00'	158.68'	80.10'	157.92'	N89°08'01"W	14°23'06"
12	309.00'	185.01'	95.37'	182.26'	S17°02'08"E	34°18'17"
13	210.00'	85.90'	43.56'	85.31'	S87°08'26"E	23°26'15"
14	50.00'	252.49'	35.60'	58.00'	S88°00'00"W	289°55'56"
15	50.00'	252.29'	35.60'	58.00'	S88°24'15"E	289°05'56"
16	50.00'	277.38'	38.75'	78.18'	S49°35'42"W	269°17'55"
17	50.00'	252.29'	35.60'	58.00'	N90°00'00"W	283°05'56"
18	50.00'	221.43'	66.67'	80.00'	N39°16'51"W	253°44'23"
19	300.00'	66.81'	33.55'	66.68'	N02°23'39"W	12°45'38"
20	201.24'	64.15'	32.35'	63.88'	N80°52'36"W	18°15'48"

LINE	DIRECTION	DISTANCE
100	N87°35'20"E	130.23'
101	S34°18'17"E	84.38'
102	N00°00'00"E	119.63'
103	N02°00'00"W	40.34'
104	N09°00'00"W	153.07'
105	N28°33'22"E	117.83'
106	N12°48'03"W	179.65'
108	S70°15'44"E	186.18'
109	N81°02'26"E	88.88'
110	N08°35'45"E	78.40'
111	N19°13'18"W	154.62'
112	S89°59'30"W	175.00'
113	N00°00'00"W	118.69'
114	N10°13'12"E	100.58'
115	S89°59'30"W	81.42'
116	N00°00'00"W	278.36'
117	N55°41'43"E	128.62'
118	N75°23'19"W	42.10'


NOTE:

The minimum low opening elevation for homes built in this addition shall be 134.0 (City of Wichita Datum) 1321.4 (MSL).

The minimum basement floor elevation for homes built in this addition shall be 131.0 (City of Wichita Datum) 1318.4 (MSL).

BENCHMARKS

1. "□" cut on southwest corner of north headset at Meridian Avenue and Main.
Elev. 138.83 (City of Wichita Datum)



6-21-94

HARBOR ISLE ADDITION

TO WICHITA - SEDGWICK COUNTY, KANSAS

PROJECT NO. 468-82408
INDEX CODE 742312

