STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0502-01	2009	129	226

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH)

WORK ZONE SIGN (SPECIAL)		
SIGN NO.	16.25 SQ.FT. & LESS	16.26 SQ.FT. & OVER
ARRA-5	2	
ARRA-6	2	

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

* QUANTITY MOST USED ON THE PROJECT AT ANY ONE TIME

WORK ZONE SIGNS *			
SIGN NO.	SIZE - SQ.FT.		
	0-9.25	9.26-16.25	16.26 & OVER
W20-1		20	
R3-2	4		
R3-1	2		
R1-1	2		
R4-7			2
R11-2		16	
M4-10	7		
R5-1	4		
R1-2	1		
R6-1	6		
KM4-20	5		
R2-1			6
W4-2L		2	
R4-1			2
W3-5		2	
W20-5		4	
M4-8A	2		
M4-9	7		
W20-3		2	
W20-2		2	
R11-4		1	
W6-3		1	
W1-4L		3	
W13-1	1		
W1-4R		1	
W1-6	1		

BARRICADES *	CHANNELIZING DEVICES *	
TYPE III (4' TO 12')	FIXED	PORTABLE
63		317

LIGHTED DEVICES *	
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)	126
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	
ARROW DISPLAY	
PORTABLE CHANGEABLE MESSAGE SIGN	2

RECAPITULATION OF QUANTITIES

ITEM	QUANTITY	UNIT
WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)	39	EACH PER DAY
WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)	49	EACH PER DAY
WORK ZONE SIGNS (16.26 SQ.FT. & OVER)	8	EACH PER DAY
WORK ZONE BARRICADES (TYPE III - 4' TO 12')	63	EACH PER DAY
CHANNELIZER (FIXED)		EACH PER DAY
CHANNELIZER (PORTABLE)	317	EACH PER DAY
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)	126	EACH PER DAY
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN	2	EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		
4" SOLID (TYPE I TAPE)	25870	STA./LINE
4" SOLID (TYPE II TAPE)	10584	STA./LINE
4" BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE II TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE I TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE II OR IIA TAPE)		STA./LINE
4" BROKEN(3.3')(FLEXIBLE RAISED PAVEMENT MARKER)		STA./LINE
4" DOTTED EXTENSION (TYPE I TAPE)		STA./LINE
4" DOTTED EXTENSION (TYPE II TAPE)		STA./LINE
SOLID (LINE MASKING TAPE)		STA./LINE
BROKEN (LINE MASKING TAPE)		STA./LINE
PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
*CONCRETE SAFETY BARRIER (TYPE F3)(TEMPORARY)	2570	LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-INSTALL ONLY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-RELOCATE)		LIN. FT.
INERTIAL BARRIER SYSTEM		EACH
REPLACEMENT MODULES (F200)		EACH
REPLACEMENT MODULES (F400)		EACH
REPLACEMENT MODULES (F700)		EACH
REPLACEMENT MODULES (F1400)		EACH
REPLACEMENT MODULES (F2100)		EACH
WORK ZONE SIGN (SPECIAL)(16.25 SQ.FT. & LESS)	4	EACH
WORK ZONE SIGN (SPECIAL)(16.26 SQ.FT. & MORE)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL	1	LUMP SUM
FLAGGER (SET PRICE)	1	HOUR

*INCLUDES INSTALLATION AND REMOVAL

NO.	DATE	REVISIONS	BY	APP'D
3	8-8-07	2007 SPEC REVISION	M.B.	A.A.A.
2	12-29-05	ADDED TYPE A & RED TYPE B LIGHTS	B.H.	A.A.A.
1	2-1-05	CONST. SIGN SPECIAL CHART	B.H.	A.A.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

TE795 9/1/00

FHWA APPROVAL 8-8-07		APP'D Anthony A. Airoboire	
DESIGNED B.A.H.	DETAILED B.A.H.	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

Plotted By : $$USERNAME$$ $$$KDOTGRP$$$$,6th Floor
Plot File : $$$$$$$$$$$$DGNSPEC$$$$$$$$$$$$
Plot Date : $$$$$SYTIME$$$$$$