

1. THE FIELD SURVEY INFORMATION SHOWN ON THE PLANS REPRESENT THE EXISTING TOPOGRAPHIC CONDITIONS AS BEST AS COULD BE DETERMINED. AT LOCATIONS WHERE THE NEW CONSTRUCTION IS TO MATCH EXISTING FEATURES, IT MAY REQUIRE FIELD ADJUSTMENTS OF TRANSITION LENGTHS AND PROFILE GRADES.
2. ALL CONSTRUCTION AND MATERIALS SHALL COMPLY WITH CITY OF WICHITA STANDARDS AND SPECIFICATIONS.
3. UTILITY SERVICE LINES, POLES, VALVE BOXES, METERS, ETC. ARE TO BE ADJUSTED AS NECESSARY BY OTHERS PRIOR TO CONSTRUCTION UNLESS THE PLANS SPECIFICALLY CALL FOR THEIR ADJUSTMENT BY THE CONTRACTOR OR UNLESS THE PLANS SPECIFICALLY IDENTIFY A UTILITY TO BE ADJUSTED BY ITS OWNER DURING CONSTRUCTION. EXISTING UTILITIES AND THEIR LOCATION, AS SHOWN ON THE PLANS, REPRESENT THE BEST INFORMATION OBTAINABLE FOR DESIGN. THE PLAN LOCATIONS ARE NOT GUARANTEED AND ADDITIONAL UTILITIES MAY ALSO BE ENCOUNTERED. THE CONTRACTOR WILL BE REQUIRED TO WORK AROUND EXISTING UTILITIES WITHIN THE RIGHT-OF-WAY WHICH DO NOT CONFLICT WITH PROPOSED CONSTRUCTION.
4. RUBBLE FROM THE REMOVAL OF MISCELLANEOUS STRUCTURES AND EXCESS EXCAVATION WHICH IS TO BE WASTED SHALL BE DISPOSED OF ON SITES TO BE PROVIDED BY THE CONTRACTOR. THESE SITES SHALL BE APPROVED BY THE ENGINEER AS TO SUITABILITY, APPEARANCE, AND SITE LOCATION, SITES THAT IN THE OPINION OF THE ENGINEER, WILL LEAVE AN UNSIGHTLY APPEARANCE WILL NOT BE APPROVED.

ALL DISPOSAL SITES MUST BE APPROVED BY THE KANSAS DEPARTMENT OF HEALTH AND ENVIRONMENT. MATERIAL EITHER STOCKPILED OR DISPOSED OF IN A FLOODPLAIN WOULD REQUIRE A KANSAS STATE BOARD OF AGRICULTURE PERMIT. ANY MATERIALS DUMPED IN WATERS OF THE UNITED STATE OR WETLANDS IS SUBJECT TO U.S. CORPS OF ENGINEERS PERMITTING REGULATIONS. ANY MATERIAL BURIED OR STOCKPILED BEYOND APPROVED CONSTRUCTION LIMITS WOULD REQUIRE ADDITIONAL ARCHAEOLOGICAL INVESTIGATIONS UNLESS BURIED IN A PREVIOUSLY APPROVED BORROW LOCATION.
5. CONTRACTOR WILL BE REQUIRED TO PROVIDE A MINIMUM ADVANCE NOTICE OF FORTY-EIGHT(48)HOURS TO UTILITY COMPANIES PRIOR TO STARTING ANY EXCAVATION AS FOLLOWS:

KANSAS ONE CALL 1-800-344-7233 OR 687-2470(LOCAL WICHITA)

THE CONTRACTOR MUST NOTIFY THE FOLLOWING IN CASE OF AN EMERGENCY.

COX COMMUNICATION 262-4270 OR 263-2061
SBS 1-800-870-8390
KANSAS GAS SERVICE 1-888-482-4950
WESTAR 1-800-383-1183
AQUILA 1-800-303-0752
CITY OF WICHITA(WATER & SEWER) 268-4555

THE CONTRACTOR SHALL NOTIFY PIPELINE COMPANIES AT LEAST 24 HOURS IN ADVANCE OF ANY WORK BEING PERFORMED ACROSS AND/OR ADJACENT TO PIPELINES.
6. TREES AND SHRUBS IN PUBLIC RIGHT-OF WAY WHICH ARE IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE REMOVED BY THE CONTRACTOR WITH THE ENGINEERS APPROVAL. TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE SAVED AND PROTECTED FROM DAMAGE.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR WILL BE REQUIRED TO REESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE ESTABLISHED BY A LICENSED LAND SURVEYOR IN ACCORDANCE WITH STATE LAWS.
8. THE CONTRACTOR SHALL GIVE ALL PROPERTY OWNERS AND/OR TENANTS OF DEVELOPED PROPERTY DIRECTLY ABUTTING THE CONSTRUCTION OF THIS PROJECT A MINIMUM OF TEN(10) DAYS ADVANCE NOTICE PRIOR TO START OF CONSTRUCTION.
9. THE CONTRACTOR MUST EXAMINE THE CONSTRUCTION SITE PRIOR TO BIDDING AND BE SATISFIED AS TO THE WORK SHOWN FOR COMPLETION. AFTER BIDS HAVE BEEN RECEIVED, THE CONTRACTOR SHALL NOT ASSERT THAT THERE WAS A MISUNDERSTANDING OF THE QUANTITIES OF WORK OR OF THE NATURE OF THE WORK TO BE COMPLETED.
10. THE CONTRACTOR SHALL NOT START WORK ON THE PROJECT UNTIL THE PROJECT INSPECTOR IS ASSIGNED TO THE PROJECT AND IS PRESENT ON THE SITE. ANY WORK DONE WITHOUT INSPECTION WILL BE REQUIRED TO BE UNCOVERED FOR INSPECTION.
11. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL IN ACCORDANCE WITH THE CURRENT ADDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND KDOT STANDARDS TO ENSURE A SAFE WORK ZONE FOR THE TRAVELING PUBLIC.
12. WHERE REMOVAL OF EXISTING FENCES IS DEEMED NECESSARY BY THE CONTRACTOR, THE CONTRACTOR SHALL COORDINATE REMOVAL WITH ADJACENT PROPERTY OWNERS. ALL REMOVAL AND RESETING OF FENCES SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE INCLUDED IN THE LUMP SUM BID.

13. ALL LAWN/TURF AREAS DISTURBED BY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS SHALL BE RESTORED WITH GRASS. RESTORATION OF DISTURBED AREA SHALL INCLUDE, BUT NOT BE LIMITED TO, TOP SOIL PREPARATION, FERTILIZING, SEEDING, MULCHING (ALL SEEDED AREAS, OUTSIDE THE LIMITS OF EROSION MAT PLACEMENT), AND/OR RESEEDING, AND INSTALLATION OF EROSION CONTROL MAT ON SLOPES. ALL SEEDING WORK SHALL BE IN ACCORDANCE WITH THE CITY OF WICHITA STANDARD SPECIFICATIONS AND THE CITY OF WICHITA ADMINISTRATIVE REGULATIONS NO. AR 6.5 WHICH GOVERNS CLEANUP AND RESTORATION OR REPLACEMENT FOLLOWING CONSTRUCTION. ALL SEEDED AREAS ON SLOPES SHALL BE COVERED WITH AN APPROVED EROSION MAT.
14. AREAS BENEATH THE PAVEMENT SHALL BE PROOF ROLLED WITH APPROVED EQUIPMENT TO IDENTIFY ANY SOFT AREAS, WHICH SHALL BE REMOVED OR AERATED TO PROVIDE A STABLE SUBGRADE. THIS WORK SHALL BE INCLUDED IN THE LUMP SUM BID.
15. SAW CUTTING OF PAVEMENT SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE INCLUDED IN THE LUMP SUM BID. SAW CUTTING OF EXISTING PAVEMENT SHALL BE FULL DEPTH OF PAVEMENT.
16. CLEARING AND GRUBBING SHALL INCLUDE REMOVAL OF ALL GRASS AND OTHER VEGETATION WITHIN THE LIMITS OF CONSTRUCTION AND THE RIGHT OF WAY LIMITS. NO BURNING WILL BE ALLOWED ON THE PROJECT.
17. GROUND WATER MAY BE ENCOUNTERED DURING CONSTRUCTION WHICH MAY REQUIRE DEWATERING. DEWATERING SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE INCLUDED IN THE LUMP SUM BID.
18. TEMPORARY SHORING AND/OR BRACING OF EXCAVATION SLOPES SHALL BE PROVIDED AS NECESSARY DURING CONSTRUCTION. TEMPORARY SHORING AND/OR BRACING SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE INCLUDED IN THE LUMP SUM BID.
19. THE CONTRACTOR SHALL CONTAIN HIS CONSTRUCTION OPERATIONS TO PERMIT TRAFFIC THROUGH AND ACROSS EXISTING ROADWAYS EXCEPT 37TH STREET WHICH MAY BE CLOSED FOR UP TO TWO DAYS FOR CONSTRUCTION OF THE 24 INCH PIPE ACROSS THE ROAD.
20. THIS PROJECT SHALL BE BID STORMWATER PUMP STATION NO. 11 (LUMP SUM) AND SHALL INCLUDE ALL ITEMS AND INCIDENTALS SHOWN IN THE PLANS AND SPECIFICATIONS TO COMPLETE THE PROJECT. IN ADDITION EROSION CONTROL ITEMS SHALL BE BID AT UNIT PRICES. SEE SH. C18 FOR QUANTITIES.
21. THE CITY SHALL CONTINUE TO PROVIDE STORM WATER PUMPING DURING SIGNIFICANT STORM EVENTS WHEN THE GATED STRUCTURE THROUGH THE LEVEE IS CLOSED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL OTHER STORM WATER PUMPING, KEEPING THE EXCAVATION DEWATERED, AND THE PROTECTION OF THE WORK AND HIS EQUIPMENT.

J:\2008Proj\06827\DWG\002- GENERAL NOTES.dwg 3/11/2010 - 7:49am

CITY OF WICHITA, KANSAS	
PUMP STATION NO. 11	
CIVIL	
GENERAL NOTES	
DESIGNED MDC	SCALE As Shown
DETAILED LRM	DATE 3-10-2010
CHECKED	SHEET C2 OF C31

