



EARTHWORK COMPUTATIONS:

CL STA.	AREA (Sq.-Ft.)	AVG. END AREA (Sq.-Ft.)	AVG. LENGTH (Ft.)	ACCUMULATED E/W VOLUME (Cu.-Ft.)
0+92	0	32.06	8	256.48
1+00	64.12	87.60	10	1132.48
1+10	111.07	111.09	10	2243.38
1+20	111.11	93.57	15	3646.93
1+35	76.03	66.47	15	4643.98
1+50	56.91	51.66	15	5418.88
1+65	46.41	38.35	11	5840.73
1+76	30.29	18.26	4	5913.77
1+80	6.24	3.12	10	5944.97
1+90	0			
TOTAL ESTIMATED CY FILL				S/T 5,945 Cu.-Ft. 220 Cu.-Yds.

YOUNG & ASSOCIATES, P.A.
Civil and Environmental Engineers

CONSENT TO PRINT OR REPRODUCE THIS DOCUMENT IS HEREBY GRANTED TO THE USER OF THIS DOCUMENT FOR PERSONAL USE ONLY. ANY OTHER USE, INCLUDING REPRODUCTION, DISTRIBUTION, OR TRANSMISSION IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN PERMISSION OF YOUNG & ASSOCIATES, P.A., IS STRICTLY PROHIBITED. THE USER OF THIS DOCUMENT SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES AND AUTHORITIES. THE USER OF THIS DOCUMENT SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES AND AUTHORITIES.

CHANNEL CROSS-SECTION
4' x 8' Storm Sewer Inlet at Mt. Vernon & Ceasna Park

City of Wichita
Sedgwick County, Kansas

scale: as noted
drawn by: das
checked by: cry
date: 8/25/05
P/N:
revisions: