



STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0240-01	2004	11	42




\* Form front face & back face of ftg. 150 mm - 305 mm as needed.

SECTION THRU WINGWALL



OPTIONAL BAR DETAIL

The Contractor shall have the option of using Dowel Bars to match vertical wall bars as shown, however no allowance will be made for additional steel required for bar laps.




VERTICAL CONSTRUCTION JOINTS


NOTE: Vertical construction joints shall be perpendicular to the longitudinal axis of the RCB and shall be placed at any location as needed for construction and as approved by the Engineer.

NOTE: Barrel Construction Joints located in a median with less than 1.5 m of fill or at locations specified by the Engineer, shall be protected by a bentonite based system as shown. Place the bentonite on the exterior walls and top slab. See requirements for bentonite in the KDOT Specifications for "Bridge Backwall Protection System". Material and installation of the bentonite system shall be subsidiary to the bid item "Grade 28 Concrete".


NOTE: Horizontal construction joints shall be a roughened finish.



PLAN VIEW SKEWED R.C.B.



SECTION




SECTION


\* Omit Drain Pipe when distance is less than 600 mm.  
 † 100 mm Perforated Pipe (Install ea. 1 220 mm in Elev.)  
 \*\* NOTE: As an alternative, all backfill for the wall (within 750 mm of finish grade) may be granular backfill material. Measurement for quantity shall be to the same limits as listed in the General Notes.

Extend filter fabric backing and lap a minimum of 100 mm. Wrap all sides and ends. Strip Drain (Extend to top of footing). Cut 100 mm square hole in plastic cover at top of footing)

OPTIONAL STRIP DRAIN Detail 'A'



VERTICAL WINGWALL DRAINAGE FOR FREE-STANDING WINGWALLS ONLY



WINGWALL PLAN

†† See wingwall detail sheet for drain spacing.  
 ∅ Completely wrap granular material with geotextile fabric.

GENERAL NOTES


- Wingwall Drainage:**
- All wingwalls with weepholes shall have horizontal wingwall drainage as shown. Free-standing wingwalls shall also have the vertical wingwall drainage. Strip drains may be used in lieu of aggregate. See KDOT Specifications for "Abutment Strip Drains" for strip drain requirements.
  - Construction and materials for wingwall drainage, including weepholes, geotextile fabric, granular material, and strip drain shall be subsidiary to the bid item, "Grade 28 Concrete". Granular material for wingwall drainage shall conform to the requirements of UD-1. Weepholes may be a formed opening or corrugated polyethylene tubing.
- Wingwall Subbase:**
- Wingwall subbase shall be constructed at all wingwall footings to assure the assumed coefficient of friction between the concrete footing and the foundation, with the following exceptions:
    - Wingwall subbase will not be required for footings on RCB's 1.830 m or less in height unless otherwise determined by the Engineer.
    - The subbase will also not be required for footings founded on rock or clean, granular material as determined by the Engineer.
  - Subbase shall consist of 100 mm compacted granular material consisting of commercial grade clean sand or UD-1 material. All excavation, material and labor necessary to construct the wingwall subbase shall be subsidiary to "Grade 28 Concrete".

- Seal Course:**
- Seal Course consisting of 75 mm minimum of Commercial Grade Concrete shall be constructed to the limits directed by the Engineer. No reinforcing in the floor of the slab or wall footing shall be placed until the Seal Course has gained sufficient strength to permit working upon it without injury.

GENERAL NOTES

- Foundation Stabilization:**
- At sites where the wingwall footing or culvert floor is located within the limits of an existing streambed or is founded on unsuitable material, the Engineer will determine the depth of Foundation Stabilization.
  - Foundation Stabilization may be required under the box and/or wingwalls as directed by the Engineer. The granular material placed for foundation stabilization shall be measured and paid for at the contract price per cubic yard for "Foundation Stabilization". Material for Foundation Stabilization shall be suitable backfill material as approved by the Engineer. The excavation for the placement of granular material shall be subsidiary to the bid item, "Foundation Stabilization".
- Granular Backfill (Wingwalls):**
- In locations where the material behind the wingwall consist of soils judged as high plasticity clays, fat clays, expansive clays or organic clays, Granular Backfill (Wingwalls) shall be used. Granular Backfill construction may be used separately or combined with Foundation Stabilization as directed by the Engineer.
  - Measurement for the bid item, "Granular Backfill (Wingwalls)", shall be measured in m<sup>3</sup> to the theoretical limits as shown Drainage pipe, rodent screens, and excavation shall be subsidiary to the bid item, "Granular Backfill (Wingwalls)".
  - Material for Granular Backfill (Wingwalls) shall conform to the requirements of UD-1 or BD-1. Drainage Pipe shall be corrugated polyethylene tubing conforming to KDOT Specifications.

Overexcavate and backfill with granular material. Compact in 200 mm lifts meeting Type B Compaction requirements.



PLAN

GRANULAR BACKFILL AND FOUNDATION STABILIZATION

NO.	DATE	REVISIONS	BY	APP'D
5	5/15/02	Removed Wing Height Stipulation	RAM	KFH
4	3/19/02	Concrete from Class to Grade	RAM	KFH
3	3-28-97	Wrap granular drains	RAM	KFH
2	9-20-96	Strip drain & bentonite joints	RAM	KFH
1	10-2-91	Change drainage details	RAM	KFH

**KANSAS DEPARTMENT OF TRANSPORTATION**

**RCB AUXILIARY DETAILS**

BR020-SI

FHWA APPROVAL	6/4/02 APP'D	KENNETH F. HURST
DESIGNED	RAMI DETAILED	TRACED
DESIGN CK.	RRRI DETAIL CK.	RRRI QUAN. CK.
		TRACE CK.

Std. Base File: br020si.dgn  
 Plotted By: unfiled  
 File: \*\*\*\*\*DGNINSPEC\*\*\*\*\*  
 Plot Date: 2/5/2004