FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS			43	106

INLET AND MANHOLE DATA

REMARKS	LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL										
	STATION	ROUTE IDENTIFICATION	DISTANCE LT./RT.	INLET (TYPE IA) (CURB) SINGLE	INLET (TYPE I) (CURB) SINGLE	INLET (TYPE I) (CURB) DOUBLE	INLET (TYPE I) (CURB) TRIPLE	RC MANHOLE	MANHOLE (TYPE P)					
	41+48.07	CENTRAL	36.0 RT.	1										
	38+27.43	CENTRAL	36.0 RT.					1						
	34+35.99	CENTRAL	36.0 RT.					1						
	31+86.68	CENTRAL	36.0 RT.					1						
	31+86.68	CENTRAL	34.0 LT					1						
	26+79.82	CENTRAL	34.0 LT					1						
	21+68.96	CENTRAL	34.0 LT					1						
	21+19.38	CENTRAL	33.5 LT					1						
	20+66.79	CENTRAL	33.0 LT				1							
	18+47.72	CENTRAL	32.0 LT				1							
	18+12.49	CENTRAL	32.6 LT						1					
	17+41.38	CENTRAL	32.0 LT				1							
	13+40.24	CENTRAL	32.0 LT				1							
	9+97.16	CENTRAL	32.0 LT						1					
	6+27.16	CENTRAL	32.0 LT						1					
	6+24.49	CENTRAL	42.5 LT			1								
	41+48.07	CENTRAL	32.0 LT			1								
	21+70.55	CENTRAL	31.5 RT			1								
	21+16.53	CENTRAL	51.3 RT						1					
	20+69.22	CENTRAL	31.5 RT			1								
	10+91.80	MISSION	17.0 RT			1								
	10+91.80	MISSION	17.0 LT			1								
	10+75.00	HAMPTON	17.0 RT			1								
	10+75.00	HAMPTON	17.0 LT			1								
TOTALS (THIS SHEET)				1		8	4	7	4					

CONDUIT DATA

LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL		
STATION	ROUTE IDENTIFICATION	LT./RT.	TYPE OF CONDUIT SIZE	TYPE OF CONDUIT MATERIAL	LENGTH
47+57.28	CENTRAL	RT	48"x63"	HERCP	209.21'
41+48.07	CENTRAL	RT	48"x63"	HERCP	320.65'
38+27.43	CENTRAL	RT	48"x63"	HERCP	391.42'
34+35.99	CENTRAL	RT	48"x63"	HERCP	249.32'
31+86.68	CENTRAL	CROSSING	48"x63"	HERCP	70.04'
31+86.68	CENTRAL	LT	48"x63"	HERCP	560.85'
26+79.82	CENTRAL	LT	48"x63"	HERCP	510.87'
21+68.96	CENTRAL	LT	48"	RCP	49.02'
21+19.38	CENTRAL	LT	48"	RCP	53.15'
20+66.79	CENTRAL	LT	42"	RCP	219.07'
18+47.72	CENTRAL	LT	36"	RCP	35.24'
18+12.49	CENTRAL	LT	36"	RCP	71.10'
17+41.38	CENTRAL	LT	36"	RCP	400.51'
13+40.24	CENTRAL	LT	24"	RCP	343.72'
9+97.16	CENTRAL	LT	24"	RCP	370'
6+27.16	CENTRAL	LT	24"	RCP	16.22'
41+48.07	CENTRAL	CROSSING	24"	RCP	68.05'
21+68.96	CENTRAL	CROSSING	24"	RCP	65.02'
21+70.55	CENTRAL	RT	24"	RCP	57.53'
21+16.53	CENTRAL	RT	24"	RCP	51.29'
23+07.38	MISSION	RT	24"	RCP	60.70'
10+91.80	MISSION	RT	24"	RCP	34.13'
18+12.49	HAMPTON	RT	24"	RCP	42.40'
10+75.00	HAMPTON	RT	24"	RCP	34.14'

CENTRAL PAVEING IMPROVEMENTS

SUMMARY OF QUANTITIES

WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN KWL
DRAWN RA
REVIEW
UTILITY
DATE July 10, 2006
DRAWING FILE quantities
PROJECT NUMBER 472-83874
R/B JOB 2387
SHEET 43 OF 106