STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0187-01	2006	46	47

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH)

CONSTRUCTION SIGN (SPECIAL)		
SIGN NO.	1.50m² & LESS	1.51m² & OVER

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

* QUANTIFY MOST USED ON THE PROJECT AT ANY ONE TIME

CONSTRUCTION SIGNS *			
MUTCD NO.	SIZE - m²		
	0-0.85	0.86-1.50	1.51 & OVER
R3-1R	2		
R3-1L	1		
R5-8	2		
R11-2		2	
R11-4		2	
W20-2		2	
W20-3		2	
M4-9	6		
M4-9R	4		
M4-9L	4		
M4-10L	1		
M4-10R	1		

BARRICADES *	CHANNELIZING DEVICES *	
TYPE III (1.2 m TO 2.4 m)	FIXED	PORTABLE
18		

LIGHTED DEVICES *	
CONSTRUCTION WARNING LIGHT (TYPE "A" LOW INTENSITY)	12
CONSTRUCTION WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	
ARROW DISPLAY	
PORTABLE CHANGEABLE MESSAGE SIGN (LED)	

RECAPITULATION OF QUANTITIES

ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 0.85 m²)		EACH PER DAY
CONSTRUCTION SIGNS (0.86 TO 1.50 m²)		EACH PER DAY
CONSTRUCTION SIGNS (1.51 m² & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 1.2m TO 2.4 m)		EACH PER DAY
CHANNELIZER (FIXED)		EACH PER DAY
CHANNELIZER (PORTABLE)		EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE "A" LOW INTENSITY)		EACH PER DAY
CONSTRUCTION WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN (LED)		EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		
100 mm SOLID (TYPE I TAPE)		km/LINE
100 mm SOLID (TYPE II TAPE)		km/LINE
100 mm BROKEN (2.5 m) (TYPE I TAPE)		km/LINE
100 mm BROKEN (2.5 m) (TYPE II TAPE)		km/LINE
100 mm BROKEN (1.0 m) (TYPE I TAPE)		km/LINE
100 mm BROKEN (1.0 m) (TYPE II OR IIA TAPE)		km/LINE
100 mm BROKEN (1.0 m) (PAINT)		km/LINE
100 mm DOTTED EXTENSION (TYPE I TAPE)		km/LINE
100 mm DOTTED EXTENSION (TYPE II TAPE)		km/LINE
SOLID (LINE MASKING TAPE)		km/LINE
BROKEN (LINE MASKING TAPE)		km/LINE
EXISTING PAVEMENT MARKING REMOVAL		meter
GLARE SCREEN		meter
CONCRETE SAFETY BARRIER (TYPE F3)(TEMPORARY)		meter
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-INSTALL ONLY)		meter
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-RELOCATE)		meter
INERTIAL BARRIER SYSTEM		EACH
MODULE F90 (REPLACEMENT)		EACH
MODULE F180 (REPLACEMENT)		EACH
MODULE F320 (REPLACEMENT)		EACH
MODULE F640 (REPLACEMENT)		EACH
MODULE F960 (REPLACEMENT)		EACH
CONSTRUCTION SIGN (SPECIAL)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL		LUMP SUM
FLAGGER (SET)	1	HOUR
Snow Fence	1	LUMP SUM

NO.	DATE	REVISIONS	BY	APP'D
3	12-29-05	ADDED TYPE A & RED TYPE B LIGHTS	B.H.	A.A.A.
2	2-1-05	CONST. SIGN SPECIAL CHART	B.H.	A.A.A.
1	12-17-03	REMOVED TYPE I AND IV CSB, MODIFIED CSB NOTE	B.A.H.	S.A.B.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

TE795SI 9/1/00

FHWA APPROVAL 12-29-05		APP'D Anthony A. Airobaire	
DESIGNED B.A.H.	DETAILED B.A.H.	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

46

Plotted By : examples
Plot File : gnCIVIL98169\05693\DGN\e795si.dgn
Plot Date : 7/27/2006
ESOB, 6th Floor