F.H.W.A. REGION NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	54-87 K-8258-04	2004	32	60

REMOVAL OF EXISTING STRUCTURES

LOCATION	STATION TO STATION	SIDE	ITEMS
Armour	49+723.529 to 49+991.008	7.211 Lt. to 4.367 Lt.	Water Line
Armour	49+900.299 to 49+902.268	10.200 Lt. to 5.871 Lt.	4.747 m Storm Sewer
Armour	49+901.770 to 49+902.181	5.462 Rt. to 10.200 Rt.	4.079 m Storm Sewer
Armour	49+902.243	5.194 Lt.	Storm Sewer Inlet
Armour	49+902.243 to 49+901.770	5.194 Lt. to 5.462 Rt.	10.666 m Storm Sewer
Armour	49+901.770	5.462 Rt.	Storm Sewer Inlet
Armour	49+929.122	4.353 Lt.	Storm Sewer Inlet
Armour	49+929.122 to 49+926.790	4.353 Lt. to 8.861 Rt.	13.419 m Storm Sewer
Armour	49+926.790	8.861 Rt.	Storm Sewer Inlet
Armour	49+926.790 to 49+925.272	8.861 Rt. to 15.450 Rt.	6.096 m Storm Sewer
Armour	49+929.163 to 49+929.522	5.032 Lt. to 14.862 Lt.	9.840 m Storm Sewer
Armour	49+929.522 to 49+930.149	14.862 Lt. to 21.952 Lt.	6.437 m Storm Sewer
N. Ftg. Rd.	3+491.030 to 3+493.769	12.002 Rt. to 1.850 Rt.	10.512 m Storm Sewer

REMOVAL OF EXISTING STRUCTURES

LOCATION	STATION TO STATION	SIDE	ITEMS

Note: The items listed for removal may not be complete. Payment for items not listed but whose removal is required to accommodate construction of the proposed improvements, as determined by Engineer, shall not be paid for directly, but shall be included in the bid item "Removal of Existing Structures."

DATE
BY
REFERENCES NOTED
REFERENCES CHECKED

Plotted:
SCALE 1:500
Drawn by:
File:

Cook, Flatt & Strobel
ENGINEERS, P.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF
REMOVAL OF EXISTING STRUCTURES

City Of Wichita — Sedgwick, Co.

J:\00011ph2\ARMOUR NORTH\32 Removals.dwg 8/26/2004 11:27:38 AM CDT