STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0247-01	2005	32	48

SUMMARY OF PAVEMENT MARKINGS

LOCATION	4" Solid WHITE Edge Line	6" Solid WHITE Edge Line	6" Broken WHITE Lane Line	6" Broken WHITE Lane Line (PCP)	6" Dotted WHITE Extension Line	6" Solid WHITE LANE LINE	8" Solid WHITE Gore Line	12" Solid WHITE Diagonal Line	12" Solid WHITE Chevron Line	12" Solid WHITE Type I Crosswalk Line	24" Solid WHITE Type II Crosswalk Line	24" Solid WHITE Stop Line	4" Solid YELLOW Edge Line	4" Solid YELLOW Double Line	4" Solid YELLOW Line	4" Broken YELLOW Line	6" Solid YELLOW Edge Line	12" Solid YELLOW Diagonal Line
Sta. 25+55.63 to Sta. 27+45.97			800											3,200				
TOTALS																		

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION								STOP	ONLY	X-ING	SCHOOL
TOTALS											

NOTE: For specific pavement marking details and dimensions see plan sheets

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

RECAPITULATION OF QUANTITIES

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(6")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(8")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(12")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(4")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(6")		ft
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(12")		ft
		EACH
		EACH
		EACH
		EACH
PAVEMENT MARKING (EPOXY)(WHITE)(4")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(6")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(8")		ft
PAVEMENT MARKING (EPOXY)(WHITE)(12")		ft
PAVEMENT MARKING (EPOXY)(YELLOW)(4")		ft
PAVEMENT MARKING (EPOXY)(YELLOW)(6")		ft
PAVEMENT MARKING (EPOXY)(YELLOW)(12")		ft
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(12")		ft
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(24")		ft
PAVEMENT MARKING (INTERSECTION GRADE)(YELLOW)(12")		ft
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(6")	800	ft
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(YELLOW)(4")	3,200	ft
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(12")		ft
PAVEMENT MARKING REMOVAL		ft

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

NO.	DATE	REVISION	BY	APP'D
3				
2				
1	07/26/2005	New FHWA Approval Date	JFF	BDG

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

TE311

FHWA APPROVAL	07/26/2005	APP'D Brian D. Gower	
DESIGNED JFF	DETAILED JFF	QUANTITIES	TRACED
DESIGN CK. BDG	DETAIL CK. BDG	QUAN. CK.	TRACE CK.

Plotted By : $$USERNAME$$ $$$KDOTGRP$$$$, 6th Floor
Plot File : $$$$$$$$$$$$DGNSPEC$$$$$$$$$$$$$$
Plot Date : $$$$$SYTIME$$$$$$