





Does water flow around the ditch check? ☐

Does water flow under the ditch check? ☐

Does the silt fence sag excessively? ☐

Has the silt fence torn or become detached from the posts? ☐

Does sediment need to be removed from behind the ditch check? ☐



CONCRETE BLOCK FILTER FOR AREA DRAIN
(INLET PROTECTION)

All gravel filters installed around area drains should be inspected and repaired after each runoff event. Sediment should be removed when material is within 3" of the top of any block. Periodically, the gravel should be raked to increase infiltration and filtering of runoff waters. Accumulated sediment is to be removed immediately from roads and streets after every runoff event.