


STATE OF KANSAS
DEPARTMENT OF TRANSPORTATION



CONSTRUCTION PLANS FOR PROPOSED
29th STREET NORTH
MAIZE ROAD to TYLER ROAD
FEDERAL AID URBAN SYSTEM PROJECT

FOR
THE CITY OF WICHITA,
SEDGWICK COUNTY, KANSAS

FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	N 87-0294-01	2004	1	129

STP-N 029(401)


GRADING
STORM SEWER
SURFACING
PAVEMENT MARKING

Note:
All Dimensions shown without the SI suffix
are in meters. All elevations shown are in
meters


Traffic Note:
Traffic shall be carried through construction.
See sheet no. 75a - 81 for Construction Sequences.

INDEX

1	Title Sheet
2	Key Sheet
3	General Notes
4-6	Typical Sections
7-8	Pavement Details
9-10	Valley Gutter Details
11	Standard Drive Details
12-24	29th Street North Paving Plans
25-27	Tyler Road Paving Plans
28	Intersection Joint Plan
29	Intersection Grading Plan
30-51	Storm Water Sewer Plan/Profiles
52-64	Storm Water Sewer Details
65	29th Street & Maize Road Signalization Plan
66	29th Street & Maize Road Wiring Plan
67	29th Street & Tyler Road Signalization Plan
68	29th Street & Tyler Road Wiring Plan
69-72	Marking & Signing Plan
73-75	Traffic & Street Sign Details
75a-81	Construction Sequencing
82-83	Traffic Control Details
84	Drainage Plan
85-86	Recapitulation of Quantities
87-90	Erosion Control Details
91-121	29th Street Cross Sections
122-129	Tyler Road Cross Sections



SITE




VICINITY MAP

City Project No. 472-83863
O.C.A. No. 706868
Oct. 2004

DESIGN DATA

AADT (2000)	1,000
AADT (2030)	14,000
DHV	10%
T	3%
V	65 km/hr
C of A	N/A
Clear Zone	1.8m

Gross Length of Project	1,665.652 m
Exceptions	0.000 m
Additions	0.000 m
Net Length of Project	1,665.652 m
Net Length of Bridges	0.000 m
Net Length of Road	1,665.652 m



APPROVED - DATE

James R. Armour 10-18-04

JIM ARMOUR, P.E., ACTING CITY ENGINEER
CITY OF WICHITA, KANSAS

KDOT
METRIC

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
319-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211