



Sta. 55+38.79 Const.  
 10" Reinf. Conc. Valley Gutter, Lt.  
 Saw Cut and Match Exist. 90.50' Lt.

Sta. 56+50.56 21.00' Lt. Const.  
 Br. No.  
 42'-56'-42'  
 Reinforced Concrete Haunched Slab Spans  
 Pile Bent Abutments & Column Bent Piers  
 1-39' Roadway, 1-10' Sidewalk, 0° Skew  
 See Sh. No's. 209, 212, & 213

Sta. 59+96.66 Const.  
 10" Reinf. Conc. Valley Gutter, Lt.  
 Saw Cut and Match Exist. 66.12' Lt.

Sta. 60+21.68 Const.  
 6" Conc. Full Radius Drive, Lt.  
 Saw Cut and Match Exist. 85.40' Lt.  
 Remove and Replace Driveway to Realign

STA. 61+00 END  
 Construction 143rd Street East

Sta. 59+14.90 Const.  
 6" Conc. Full Radius Drive, Rt.  
 Saw Cut and Match Exist. 75.80' Rt.

Sta. 58+83.98 Const.  
 10" Reinf. Conc. Valley Gutter, Rt.  
 Saw Cut and Match Exist. 74.53' Rt.

Sta. 56+50.56 5.00' Rt. Const.  
 Br. No.  
 42'-56'-42'  
 Reinforced Concrete Haunched Slab Spans  
 Pile Bent Abutments & Column Bent Piers  
 1-37' Roadway, 1-6' Sidewalk, 0° Skew  
 See Sh. No's. 209-211

Point No.	Station	Offset to HE	Description	Elevation	
				Flowline	Top Curb
1	51+76.53	0.00' Rt.	Tie In	17.57	18.24
2	51+76.53	18.00' Rt.	Tie In	17.03	17.70
3	52+45.77	18.00' Rt.	P.I.	16.54	17.21
4	54+80.00	0.00' Rt.	P.C.	14.53	15.20
5	55+38.79	12.15' Lt.	Tie In	13.74	14.41
6	55+45.77	7.00' Rt.	Tie In	13.85	14.52
7	57+55.35	24.00' Lt.	Tie In	12.25	12.92
8	57+55.35	7.00' Rt.	Tie In	12.76	13.43
9	58+04.22	20.89' Lt.	Nose	12.08	12.75
10	58+04.22	7.00' Rt.	Nose	12.49	13.16

Point No.	Station	Offset to HE	Description	Elevation	
				Flowline	Top Curb
1	54+93.95	58.00' Lt.	End of Return, 32.50' R.	12.68	13.18
2	55+38.79	58.00' Lt.	Tie In Point to Bridge	12.06	N/A
3	58+36.38	40.00' Rt.	End of Return, 32.50' R.	11.32	11.82
4	59+26.05	29.16' Rt.	End of Return, 32.50' R.	11.40	11.90
5	59+54.02	33.69' Lt.	End of Return, 32.50' R.	11.34	11.84
6	60+35.02	28.34' Lt.	End of Return, 32.50' R.	11.84	12.34
7	60+07.16	110.20' Lt.	End of Return, 27.50' R.	08.60	09.10
8	60+07.16	60.77' Lt.	End of Return, 27.50' R.	10.12	10.62
9	58+99.25	104.07' Rt.	End of Return, 27.50' R.	11.80	12.30
10	59+03.20	50.05' Rt.	End of Return, 27.50' R.	10.50	10.80

- UTILITIES**
- Cable: Cox Communications
  - Gas<sub>1</sub>: Kansas Gas Service
  - Gas<sub>2</sub>: Southern Star Pipeline
  - Gas<sub>3</sub>: Coffeyville Resources
  - Power: Westar
  - Sanitary Sewer: Wichita Water & Sewer
  - Storm Water Sewer: Wichita Water & Sewer
  - Telephone: AT&T
  - Traffic Signal: City of Wichita
  - Water: Wichita Water & Sewer

All stations and offsets are to back of curb unless otherwise shown.  
 See Sh. No's. 102-130 for SWS Plans.  
 See Sh. No's. 136-139 for San. Sewer Plans.  
 See Sh. No's. 140-162 for Water Plans.

**CITY OF WICHITA**  
**143RD STREET EAST**  
**PLAN**  
**STA. 51+76.53 TO STA. 61+00**

2:40 PM  
 2/18/2011  
 J:\CIVIL\07432\DWG\PAV\EK243SR02.DWG  
 SURV. - PLOT CADD DES. - DR. - TR. - APP.