1 2 3 4 5

D C B A

LEVEE P

LEVEE P

LEVEE D

LEVEE D

RECOVER 10' WIDE STRIP OF RIGHT-OF-WAY FROM PARKING AREA BY:
-REMOVING 6" OF GRAVEL SURFACE
-PLACING 6" OF TOPSOIL
-SEEDING AND MULCHING

REMOVE ALL FLOOD CONTROL FENCE WHERE EXISTING CHAIN LINK IS IN PLACE.
DO NOT REMOVE CHAIN LINK FENCE.

REMOVE ALL TREES WITHIN THE LEVEE RIGHT-OF-WAY, UP TO AND INCLUDING ANY TREES IN THE CHAIN LINK FENCE.

REMOVE ALL TREES WITHIN THE LEVEE RIGHT-OF-WAY, UP TO AND INCLUDING ANY TREES IN THE CHAIN LINK FENCE.

FC18

FC19

BEGIN PROPOSED FENCE

END PROPOSED FENCE
ATTACH TO CORNER POST OF CHAIN LINK FENCE.

SET 6" POST FOR BOUNDARY MARKER

INSTALL 69 LF OF ACCESS CONTROL FENCE ON RIGHT-OF-WAY

SET 6" POST FOR BOUNDARY MARKER

MATCHLINE - SEE SHEET LM-2.02

MATCHLINE - SEE SHEET LM-2.04

THIS SHEET:
FENCE TO BE DEMOLISHED: 722 LF
NEW FENCE TO BE INSTALLED: 69 LF

FENCE COORDINATES*		
POINT NAME	NORTHING	EASTING
FC18	1710394	1650706
FC19	1710415	1650771

N

50' 25' 0 50'

GRAPHIC SCALE

NOTES:

1. TREES TO BE REMOVED THAT ARE GREATER THAN 15' FROM THE TOE OF THE LEVEE MAY BE CUT FLUSH WITH GROUND SURFACE AND TREATED TO PREVENT FUTURE GROWTH. SEE SHEETS G-1.02 AND G-1.03.
*2. COORDINATES PROVIDED ARE IN NAD83 STATE PLANE, SOUTH ZONE AND SHALL ONLY BE USED FOR THE INITIAL LOCATION OF FENCE TO BE INSTALLED. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING THE CURRENT LEGAL RIGHT-OF-WAY AND PLACING THE PROPOSED FENCE THEREON.

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4630
Fax: (785) 272-4676

CITY OF WICHITA

SYSTEMWIDE VEGETATION MAINTENANCE - PHASE 3
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
8855
5-20-2011
KANSAS
PROFESSIONAL ENGINEER

DESIGNED BY: Larry Sample, PE		DATE: 5-20-2011
DWN BY: RES	CKD BY: LBK	APP BY: L. SAMPLE
FILE NAME: 09_TREE REMOVAL PLAN.dgn		

AMEC PROJ. NO. 5-6150-0001

TREE REMOVAL PLAN

LM-2.03

SHEET 9 OF 42